CITY OF BEAUMONT PUBLIC WORKS AGREEMENT

This PUBLIC WORKS AGREEMENT ("Agreement") is made and effective November 1, 2022 by and between the City of Beaumont, a municipal corporation ("CITY"), and <u>All American Asphalt, a corporation</u> ("CONTRACTOR"). In consideration of the mutual covenants and conditions set forth herein, the parties agree as follows:

I. <u>SCOPE OF WORK</u>

The CONTRACTOR shall perform within the time set forth in Article 2 of this Agreement and shall furnish all labor, materials, equipment, tools, utility services, and transportation and perform and complete all work required in connection with the Pennsylvania Avenue Widening Project CIP 2017-009 (hereinafter "Project"). CITY's Invitation for Bids ("Invitation") for the Project, dated September 9, 2022, and CONTRACTOR's Bid in response to the Invitation, dated October 3, 2022, are attached hereto as Exhibits A and B, respectively and incorporated herein by this reference. The Scope of Work for the Project is set forth in the Invitation. In the event that any terms of the Bid are different from the Invitation for Bids, the Invitation for Bids shall control. Any additional terms in the Bid that purport to bind the City to any additional terms not contained in this Agreement and related attachments shall not be binding on the City.

By entering into this Agreement, CONTRACTOR acknowledges that there may be other contractors on the site whose work will be coordinated with that of its own. CONTRACTOR expressly warrants and agrees that it will cooperate with other contractors and will do nothing to delay, hinder, or interfere with the work of other separate contractors, the CITY, the Construction Manager, the Engineer, or utilities. CONTRACTOR also expressly agrees that, in the event its work is hindered, delayed, interfered with, or otherwise affected by a separate contractor, its sole remedy will be a direct action against the separate contractor. To the extent allowed by law, the CONTRACTOR will have no remedy, and hereby expressly waives any remedy against the CITY, the Construction Manager (if any), and the Engineer on account of delay, hindrance, interference or other events.

II. <u>TIME FOR PROJECT COMPLETION</u>

All of CONTRACTOR's work on the Project shall be completed within durations established for the individual activities. All work shall commence ten (10) calendar days after receiving a written Notice of Award from the CITY or Construction Manager, if a Construction Manager is employed by CITY on the Project. CONTRACTOR shall refer to the invitations for bids, and Project Plans and Specifications, all of which, as set forth below, are incorporated herein by reference, for contractual obligations regarding individual activity durations.

III. THE CONTRACT SUM

The CITY shall pay to the CONTRACTOR for the performance of this Agreement, subject to any additions and deductions provided in the Project documents, the sum of seven million two hundred and ninety-one thousand two hundred and fifty dollars (\$7,469,250).

IV. PROGRESS PAYMENTS

Based upon Applications for Payment submitted to the Engineer by the CONTRACTOR and Certificates for Payment issued by the Engineer, the CITY shall make progress payments on account of the Contract Sum to the CONTRACTOR as provided in the General Conditions, which are fully incorporated into this Agreement by this reference.

This Agreement is subject to the provisions of Article 1.7 (commencing at Section 20104.50) of Division 2, Part 3 of the Public Contract Code regarding prompt payment of contractors by local governments. Article 1.7 mandates certain procedures for the payment of undisputed and properly submitted payment requests within 30 days after receipt, for the review of payment requests, for notice to Contractor of improper payment requests, and provides for the payment of interest on progress payment requests which are not timely made in accordance with that Article. This Agreement hereby incorporates the provisions of Article 1.7 as though fully set forth herein.

V. INDEMNITY, DEFENSE AND HOLD HARMLESS AGREEMENT

CONTRACTOR shall indemnify, defend with legal counsel approved by CITY, and hold harmless CITY, its officers, officials, employees and volunteers from and against all liability, loss, damage, expense, cost (including without limitation reasonable legal counsel fees, expert fees and all other costs and fees of litigation) of every nature arising out of or in connection with CONTRACTOR's negligence, recklessness or willful misconduct in the performance of work hereunder or its failure to comply with any of its obligations contained in this Agreement, except such loss or damage which is caused by the sole or active negligence or willful misconduct of the CITY. Should conflict of interest principles preclude a single legal counsel from representing both CITY and CONTRACTOR, or should CITY otherwise find CONTRACTOR's legal counsel unacceptable, then CONTRACTOR shall reimburse the CITY its costs of defense, including without limitation reasonable legal counsels fees, expert fees and all other costs and fees of litigation. The CONTRACTOR shall promptly pay any final judgment rendered against the CITY (and its officers, officials, employees and volunteers) with respect to claims determined by a trier of fact to have been the result of the CONTRACTOR's negligent, reckless or wrongful performance. It is expressly understood and agreed that the foregoing provisions are intended to be as broad

and inclusive as is permitted by the law of the State of California and will survive termination of this Agreement.

CONTRACTOR obligations under this section apply regardless of whether or not such claim, charge, damage, demand, action, proceeding, loss, stop notice, cost, expense, judgment, civil fine or penalty, or liability was caused in part or contributed to by an Indemnitee. However, without affecting the rights of CITY under any provision of this agreement, CONTRACTOR shall not be required to indemnify and hold harmless CITY for liability attributable to the active negligence of CITY, provided such active negligence is determined by agreement between the parties or by the findings of a court of competent jurisdiction. In instances where CITY is shown to have been actively negligent and where CITY active negligence accounts for only a percentage of the liability involved, the obligation of CONTRACTOR will be for that entire portion or percentage of liability not attributable to the active negligence of CITY.

VI. PREVAILING WAGES

- A. Contractor shall comply with all applicable laws and regulations relating to prevailing wages. Wage rates for this Project shall be in accordance with the "General Wage Determination Made By the Director of Industrial Relations Pursuant To California Labor Code, Part 7, Chapter 1, Article 2, Sections 1770, 1773 and 1773.1", for Riverside County. Wage rates shall conform with those posted at Beaumont City Hall and the Project site.
- B. The following Labor Code sections are hereby referenced and made a part of this Agreement:
 - 1. Section 1775 Penalty for Failure to Comply with Prevailing Wage Rates.
 - 2. Section 1777.4 Apprenticeship Requirements.
 - 3. Section 1777.5 Apprenticeship Requirements.
 - 4. Section 1813 Penalty for Failure to Pay Overtime.
 - 5. Sections 1810 and 1811 Working Hour Restrictions.
 - 6. Section 1775 Payroll Records.
 - 7. Section 1773.8 Travel and Subsistence Pay.

VII. <u>RECORD AUDIT</u>

In accordance with Government Code, Section 8546.7, records of both the CITY and the CONTRACTOR shall be subject to examination and audit by the Auditor General for a period of three (3) years after final payment.

VIII. FINAL PAYMENT

Final payment, constituting the entire unpaid balance of the Agreement Sum, shall be paid by the CITY to the CONTRACTOR no sooner than thirty-five (35) days after a Notice of Completion has been recorded, unless otherwise stipulated in the Notice of Completion, provided the work has then been completed, the Agreement fully performed, and a final Certificate for Payment has been issued by the Engineer.

IX. <u>CONTRACTOR'S FAILURE TO PROCURE COMPLETION OF PROJECT</u>

In the event CONTRACTOR fails to furnish tools, equipment, or labor in the necessary quantity or quality, or fails to prosecute the work or any part thereof contemplated by this Agreement in a diligent and workmanlike manner, and if the CONTRACTOR for a period of three (3) calendar days after receipt of written demand from CITY or its designated representative to do so, fails to furnish tools, equipment, or labor in the necessary quantity or quality, and to prosecute its work and all parts thereof in a diligent and workmanlike manner, or after commencing to do so within said three (3) calendar days, fails to continue to do so; then the CITY may exclude the CONTRACTOR from the premises, or any portion thereof, and take possession of said premises or any portion thereof, together with all material and equipment thereon, and may complete the work contemplated by this Agreement or any portion of said work, either by furnishing the tools, equipment, labor or material necessary, or by letting the unfinished portion of said work, or the portion taken over by the CITY to another contractor or by a combination of such methods. In any event, the procuring of the completion of said work, or the portion thereof taken over by the CITY, shall be a charge against the CONTRACTOR, and may be deducted from any money due or becoming due to CONTRACTOR from the CITY, or the CONTRACTOR shall pay the CITY the amount of said charge, or the portion thereof unsatisfied. The sureties, provided for under this Agreement shall become liable for payment should CONTRACTOR fail to pay in full any said cost incurred by the CITY.

X. <u>INSURANCE</u>

Prior to the beginning of and throughout the duration of the Project, CONTRACTOR and its subcontractors shall maintain insurance in conformance with the requirements set forth below. Attached hereto as Exhibit C are copies of Certificates of Insurance and the waiver of subrogation endorsement as required by Section 6.B.1. CONTRACTOR will use existing coverage to comply with these requirements. If that existing coverage does not meet the requirements set forth herein, CONTRACTOR agrees to amend, supplement or endorse the existing coverage to do so.

CONTRACTOR acknowledges that the insurance coverage and policy limits set forth in this section constitute the minimum amount of coverage required. Any insurance proceeds available to CONTRACTOR or its subcontractors in excess of the limits and coverage identified in this Agreement and which is applicable to a given loss, claim or demand, will be equally available to CITY.

A. Types of Insurance

Without limiting CONTRACTOR's indemnification of CITY, and prior to commencement of Work, CONTRACTOR shall obtain, provide and maintain at its own expense during the term of this Agreement, policies of insurance of the type and amounts described below and in a form satisfactory to CITY:

- 1. General liability insurance. CONTRACTOR shall maintain commercial general liability insurance with coverage at least as broad as Insurance Services Office form CG 00 01, in an amount not less than \$1,000,000 per occurrence, \$2,000,000 general aggregate, for bodily injury, personal injury, and property damage, and a \$2,000,000 completed operations aggregate. The policy must include contractual liability that has not been amended. Any endorsement restricting standard ISO "insured contract" language will not be accepted.
- 2. Automobile liability insurance. CONTRACTOR shall maintain automobile insurance at least as broad as Insurance Services Office form CA 00 01 covering bodily injury and property damage for all activities of the CONTRACTOR arising out of or in connection with Work to be performed under this Agreement, including coverage for any owned, hired, non-owned or rented vehicles, in an amount not less than \$1,000,000 combined single limit for each accident.
- 3. Umbrella or excess liability insurance. If CONTRACTOR is using umbrella coverage to meet part of its liability insurance requirements under Paragraph 1 of this Section, CONTRACTOR shall obtain and maintain an umbrella or excess liability insurance that will provide bodily injury, personal injury, completed operations and property damage liability coverage at least as broad as the primary coverages set forth above, including commercial general liability and employer's liability. Such policy or policies shall include the following terms and conditions:
 - A drop down feature requiring the policy to respond in the event that any primary insurance that would otherwise have applied proves to be uncollectable in whole or in part for any reason;
 - Pay on behalf of wording as opposed to reimbursement;
 - Concurrency of effective dates with primary policies;
 - Policies shall "follow form" to the underlying primary policies; and
 - Insureds under primary policies shall also be insureds under the umbrella or excess policies.

4. Workers' compensation insurance. CONTRACTOR shall maintain Workers' Compensation Insurance (Statutory Limits) and Employer's Liability Insurance (with limits of at least \$1,000,000) for CONTRACTOR's employees in accordance with the laws of the State of California, Section 3700 of the Labor Code. In addition, CONTRACTOR shall require each subcontractor to similarly maintain Workers' Compensation Insurance and Employer's Liability Insurance in accordance with the laws of the State of California, Section 3700 for all of the subcontractor's employees.

CONTRACTOR shall submit to CITY, along with the certificate of insurance, a Waiver of Subrogation endorsement in favor of CITY, its officers, agents, employees and volunteers.

5. Pollution liability insurance. Environmental Impairment Liability Insurance shall be written on a CONTRACTOR's Pollution Liability form or other form acceptable to CITY providing coverage for liability arising out of sudden, accidental and gradual pollution and remediation. The policy limit shall be no less than \$1,000,000 dollars per claim and in the aggregate. All activities contemplated in this Agreement shall be specifically scheduled on the policy as "covered operations." The policy shall provide coverage for the hauling of waste from the project site to the final disposal location, including non-owned disposal sites.

Products/completed operations coverage shall extend a minimum of three (3) years after project completion. Coverage shall be included on behalf of the insured for covered claims arising out of the actions of independent contractors. If the insured is using subcontractors, the Policy must include work performed "by or on behalf" of the insured. Policy shall contain no language that would invalidate or remove the insurer's duty to defend or indemnify for claims or suits expressly excluded from coverage. Policy shall specifically provide for a duty to defend on the part of the insurer. The CITY, its officials, officers, agents, and employees, shall be included as insureds under the policy.

6. Builder's risk insurance. Upon commencement of construction and with approval of CITY, CONTRACTOR shall obtain and maintain builder's risk insurance for the entire duration of the Project until only the CITY has an insurable interest. The Builder's Risk coverage shall include the coverages as specified below.

The named insureds shall be CONTRACTOR and CITY, including its officers, officials, employees, and agents. All Subcontractors (excluding those solely responsible for design Work) of any tier and suppliers shall be included as additional insureds as their interests may appear. CONTRACTOR shall not be required to maintain property insurance for any portion of the Project following transfer of control thereof to CITY.

The policy shall contain a provision that all proceeds from the builder's risk policy shall be made payable to the CITY. The CITY will act as a fiduciary for all other interests in the Project.

Policy shall be provided for replacement value on an "all risk" basis for the completed value of the project. There shall be no coinsurance penalty or provisional limit provision in any such policy. Policy must include: (1) coverage for any ensuing loss from faulty workmanship, Nonconforming Work, omission or deficiency in design or specifications; (2) coverage against machinery accidents and operational testing; (3) coverage for removal of debris, and insuring the buildings, structures, machinery, equipment, materials, facilities, fixtures and all other properties constituting a part of the Project; (4) Ordinance or law coverage for contingent rebuilding, demolition, and increased costs of construction; (5) transit coverage (unless insured by the supplier or receiving contractor), with sub-limits sufficient to insure the full replacement value of any key equipment item; (6) Ocean marine cargo coverage insuring any Project materials or supplies, if applicable; (7) coverage with sub-limits sufficient to insure the full replacement value of any property or equipment stored either on or off the Site or any staging area. Such insurance shall be on a form acceptable to CITY to ensure adequacy of terms and sublimits and shall be submitted to the CITY prior to commencement of construction.

B. Other provisions or requirements

- 1. Proof of insurance. CONTRACTOR shall provide certificates of insurance to CITY as evidence of the insurance coverage required herein, along with a waiver of subrogation endorsement for workers' compensation. Insurance certificates and endorsements must be approved by CITY's risk manager prior to commencement of performance. Current certification of insurance shall be kept on file with CITY at all times during the term of this contract. CITY reserves the right to require complete, certified copies of all required insurance policies, at any time.
- 2. Duration of coverage. CONTRACTOR shall procure and maintain for the duration of the contract insurance against claims for injuries to persons or damages to property, which may arise from or in connection with the performance of the Work hereunder by CONTRACTOR, his agents, representatives, employees or subcontractors. CONTRACTOR must maintain general liability and umbrella or excess liability insurance for as long as there is a statutory exposure to completed operations claims. CITY and its officers, officials, employees, and agents shall continue as additional insureds under such policies.

- 3. Primary/noncontributing. Coverage provided by CONTRACTOR shall be primary and any insurance or self-insurance procured or maintained by CITY shall not be required to contribute with it. The limits of insurance required herein may be satisfied by a combination of primary and umbrella or excess insurance. Any umbrella or excess insurance shall contain or be endorsed to contain a provision that such coverage shall also apply on a primary and non-contributory basis for the benefit of CITY before the CITY's own insurance or self-insurance shall be called upon to protect it as a named insured.
- 4. CITY's rights of enforcement. In the event any policy of insurance required under this Agreement does not comply with these requirements or is canceled and not replaced, CITY has the right but not the duty to obtain the insurance it deems necessary and any premium paid by CITY will be promptly reimbursed by CONTRACTOR or CITY will withhold amounts sufficient to pay premium from CONTRACTOR payments. In the alternative, CITY may cancel this Agreement.
- 5. Acceptable insurers. All insurance policies shall be issued by an insurance company currently authorized by the Insurance Commissioner to transact business of insurance or is on the List of Approved Surplus Line Insurers in the State of California, with an assigned policyholders' Rating of A- (or higher) and Financial Size Category Class VII (or larger) in accordance with the latest edition of Best's Key Rating Guide, unless otherwise approved by the CITY's risk manager.
- 6. Waiver of subrogation. All insurance coverage maintained or procured pursuant to this agreement shall be endorsed to waive subrogation against CITY, its elected or appointed officers, agents, officials, employees and volunteers or shall specifically allow CONTRACTOR or others providing insurance evidence in compliance with these specifications to waive their right of recovery prior to a loss. CONTRACTOR hereby waives its own right of recovery against CITY, and shall require similar written express waivers and insurance clauses from each of its subconsultants.
- 7. Enforcement of contract provisions (non estoppel). CONTRACTOR acknowledges and agrees that any actual or alleged failure on the part of the CITY to inform CONTRACTOR of non-compliance with any requirement imposes no additional obligations on the CITY nor does it waive any rights hereunder.
- 8. Requirements not limiting. Requirements of specific coverage features or limits contained in this Section are not intended as a limitation on coverage, limits or other requirements, or a waiver of any

coverage normally provided by any insurance. Specific reference to a given coverage feature is for purposes of clarification only as it pertains to a given issue and is not intended by any party or insured to be all inclusive, or to the exclusion of other coverage, or a waiver of any type. If the CONTRACTOR maintains higher limits than the minimums shown above, the CITY requires and shall be entitled to coverage for the higher limits maintained by the CONTRACTOR. Any available insurance proceeds in excess of the specified minimum limits of insurance and coverage shall be available to the CITY.

- **9.** Notice of cancellation. CONTRACTOR agrees to oblige its insurance agent or broker and insurers to provide to CITY with a thirty (30) day notice of cancellation (except for nonpayment for which a ten (10) day notice is required) or nonrenewal of coverage for each required coverage.
- **10. Additional insured status**. General liability policies shall provide or be endorsed to provide that CITY and its officers, officials, employees, agents, and volunteers shall be additional insureds under such policies. This provision shall also apply to any excess/umbrella liability policies.
- **11.Prohibition of undisclosed coverage limitations.** None of the coverages required herein will be in compliance with these requirements if they include any limiting endorsement of any kind that has not been first submitted to CITY and approved of in writing.
- **12. Separation of insureds.** A severability of interests provision must apply for all additional insureds ensuring that CONTRACTOR's insurance shall apply separately to each insured against whom claim is made or suit is brought, except with respect to the insurer's limits of liability. The policy(ies) shall not contain any cross-liability exclusions.
- **13. Pass through clause.** CONTRACTOR agrees to ensure that its subconsultants, subcontractors, and any other party involved with the project who is brought onto or involved in the project by CONTRACTOR, provide the same minimum insurance coverage and endorsements required of CONTRACTOR. CONTRACTOR agrees to monitor and review all such coverage and assumes all responsibility for ensuring that such coverage is provided in conformity with the requirements of this section. CONTRACTOR agrees that upon request, all agreements with consultants, subcontractors, and others engaged in the project will be submitted to CITY for review.
- **14.CITY's right to revise requirements.** The CITY reserves the right at any time during the term of the contract to change the amounts and types of insurance required by giving the CONTRACTOR a ninety (90)

day advance written notice of such change. If such change results in substantial additional cost to the CONTRACTOR, the CITY and CONTRACTOR may renegotiate CONTRACTOR's compensation.

- **15. Self-insured retentions.** Any self-insured retentions must be declared to and approved by CITY. CITY reserves the right to require that self-insured retentions be eliminated, lowered, or replaced by a deductible. Self-insurance will not be considered to comply with these specifications unless approved by CITY.
- **16. Timely notice of claims.** CONTRACTOR shall give CITY prompt and timely notice of claims made or suits instituted that arise out of or result from CONTRACTOR's performance under this Agreement, and that involve or may involve coverage under any of the required liability policies.
- **17. Additional insurance**. CONTRACTOR shall also procure and maintain, at its own cost and expense, any additional kinds of insurance, which in its own judgment may be necessary for its proper protection and prosecution of the Work.

XI. <u>CONTRACTOR'S LICENSE</u>

CONTRACTOR must possess at the time of commencing work and throughout the Project duration, a Contractor's License, issued by the State of California, which is current and in good standing. CONTRACTOR shall ensure that any subcontractor working on the Project possesses at the time of commencing work and throughout the Project duration, a Contractor's License, issued by the State of California, which is current and in good standing.

XII. <u>REGISTRATION REQUIREMENTS</u>

A. Pursuant to Section 1771.1(a) of the Labor Code:

"A contractor or subcontractor shall not be qualified to bid on, be listed in a bid proposal, subject to the requirements of Section 4104 of the Public Contract Code, or engage in the performance of any contract for public work, as defined in this chapter, unless currently registered and qualified to perform public work pursuant to Section 1725.5. It is not a violation of this section for an unregistered contractor to submit a bid that is authorized by Section 7029.1 of the Business and Professions Code or by Section 10164 or 20103.5 of the Public Contract Code, provided the contractor is registered to perform public work pursuant to Section 1725.5 at the time the contract is awarded."

B. CONTRACTOR must be registered with the Department of Industrial Relations (DIR) of the State of California in order to be eligible to work on public works projects. CONTRACTOR must ensure registration with the DIR that is active and in good standing.

C. No contractor or subcontractor may be listed on a bid proposal for a public works project (submitted on or after March 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5 [with limited exceptions from this requirement for bid purposes only under Labor Code section 1771.1(a)].

No contractor or subcontractor may be awarded a contract for public work on a public works project (awarded on or after April 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5.

This project is subject to compliance monitoring and enforcement by the Department of Industrial Relations.

D. The CONTRACTOR is not subject to public works requirements (including registration with the DIR) if the public works project is under \$1,000, unless the CITY knows that the same CONTRACTOR will be awarded total project costs in excess of \$1,000 for a given year.

XIII. CORPORATION IN GOOD STANDING

If CONTRACTOR is a corporation, the undersigned hereby represents and warrants that the corporation is duly incorporated and in good standing in the State of California, and that Mark Luer whose title is President is authorized to act for and bind the corporation.

XIV. PROVISIONS REQUIRED BY LAW

Each and every provision of law and clause required by law to be inserted in this Agreement shall be deemed to be inserted herein and the Agreement shall be read and enforced as though it were included herein, and if through mistake or otherwise any such provision is not inserted, or is not currently inserted, then upon application of either party the Agreement shall forthwith be physically amended to make such insertion or correction.

XV. SUBSURFACE HAZARDOUS MATERIALS

- A. In the event trenches or other excavations extend deeper than four (4) feet below the surface, the CONTRACTOR shall promptly, and before the following conditions are disturbed, notify the CITY in writing of any:
 - Material that the CONTRACTOR believes may be material that is hazardous waste, as defined in Section 25117 of the Health and Safety Code that is required to be removed to a Class I, Class II or Class III disposal site in accordance with the provisions of existing law.
 - 2. Subsurface or latent physical conditions at the site differing from those indicated.
 - 3. Unknown physical conditions at the site of any unusual nature, different materially from those ordinarily encountered and generally recognized as inherent in the Work or the character provided for in the CONTRACT.
- B. Upon receipt of said notification the CITY will investigate the conditions, and if it finds that the conditions do materially so differ, or do involve hazardous waste, and cause a decrease or increase in the CONTRACTOR's cost of or the time required for performance of any part of the work, the CITY will issue a change order under the procedures described in the General Conditions.
- C. In the event that a dispute arises between the CITY and the CONTRACTOR whether the conditions materially differ, or involve hazardous waste or cause a decrease or increase in the CONTRACTOR's cost of or time required for performance of any part of the work, the CONTRACTOR shall not be excused from any scheduled completion date provided for by the Agreement, but shall proceed with all work to be performed under the

Agreement. The CONTRACTOR shall retain any and all rights provided either by Agreement or by law which pertain to the resolution of disputes and protests between the contracting parties.

XVI. <u>COMPONENT PARTS OF THE CONTRACT</u>

This Agreement entered into consists of the following CONTRACT DOCUMENTS, all of which are component parts of the Agreement as if herein set out in full or attached hereto:

Notice Inviting Bids
Scope of Work Summary
Information for Bidders
Bid Form
Non-Collusion Affidavit
Site Visit Certification
Faithful Performance Bond
Labor and Materials Payment Bond
General and Supplemental

Special Conditions
 Project Construction Schedule
 Proposed Subcontractors

Bid Bond
Information Required of Bidder
Construction Services Agreement
Certificate Regarding Worker's
Compensation
Drug-free Workplace Certification
Plans and Specifications
Addenda
Drawings
Change Orders
Shop Drawing Transmittals
Contractor's Certificate Regarding
Non-Asbestos Containing
Materials

All of the above named CONTRACT DOCUMENTS are intended to be complementary. Work required by one of the above named CONTRACT DOCUMENTS and not by others shall be done as if required by all.

XVII. ENTIRE CONTRACT

This Agreement constitutes the entire contract of the parties. No other agreements or contracts, whether oral or written, pertaining to the work to be performed, exists between the parties. This Agreement can be modified only by an amendment in writing, signed by both parties.

[Signatures on following page.]

SIGNATURE PAGE TO

CITY OF BEAUMONT PUBLIC WORKS AGREEMENT

CITY:

CONTRACTOR:

CITY OF BEAUMONT

ALL AMERICAN ASPHALT

Ву: _____

By:

Print Name: _____

Lloyd White, Mayor

Title:

CITY OF BEAUMONT PUBLIC WORKS AGREEMENT

EXHIBIT "A"

CITY'S INVITATION FOR BIDS

(Insert behind this page.)



NOTICE INVITING BIDS

The City of Beaumont, Public Works Department ("City") is soliciting bids for:

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

BID DATES, TIMES, & LOCATIONS: Bid Published: Bids Must Be Received By: Place Of Bid Receipt:

Questions In By: Bid Opening Date: Bid Opening Location: September 9, 2022 October 3, 2022 @ 11:00 A.M. 550 E. Sixth Street (City Hall) Beaumont, CA 92223 September 21, 2022 @ 11:00 A.M. October 3, 2022 @ 1:15 P.M. 550 E. Sixth Street (City Hall), Room 4 Beaumont, CA 92223

Bids received after this time will be discarded. Bids shall be valid for 90 calendar days after the bid opening date. Bids must be submitted on the City's Bid Forms. Bids must be prepared on the approved Bid forms and in the manner prescribed in the Instructions to Bidders. Bids must be submitted with the following subject:

"BID FOR CIP 2017-009 PENNSYLVANIA AVENUE WIDENING"

LOCATION OF WORK:

The work to be completed is located in the City of Beaumont on Pennsylvania Avenue, between 1st Street and 6th Street.

DESCRIPTION OF WORK:

The proposed work shall be performed in accordance with the contract documents, including but not limited to the general conditions, special conditions, technical specifications, contract drawings, permits, and all other reference documents.

In general, the work includes construction of the Pennsylvania Avenue Rodway Widening Project which includes road widening and associated improvements within the City rightof-way, Caltrans right-of-way, and Union Pacific Railroad (UPRR) right-of-way. Detailed work includes, but is not limited to, removals, excavation, grading, new pavement, pavement overlay, curb and gutter, sidewalk, ADA curb ramps, driveways, medians, street improvements, storm drain installations and improvements, installation of biofiltration systems, culvert installations and extensions, surface utility feature adjustments, pavement markings, striping, signing, traffic control, and traffic signal installation and modifications.

CONTRACT LENGTH:

The work for this contract shall not exceed 365 calendar days. Contract time shall

NOTICE INVITING BIDS



commence upon issuance of the Notice to Proceed from the City.

AWARD OF CONTRACT:

The City shall award the Contract for the Project to the lowest responsive, responsible bidder as determined from the base bid. The City reserves the right to reject any or all bids or to waive any irregularities or informalities in any bids or in the bidding process.

The City of Beaumont hereby affirmatively ensures that minority business enterprises will be afforded full opportunity to submit Bids in response to this Notice, and that minorities nor minority business enterprises will not be discriminated against on the basis of race, color, national origin, ancestry, sex, or religion in any consideration leading to the award of contract. For further information, please see the form titled "Notice of Requirement for Affirmative Action to Ensure Equal Employment Opportunity (Executive Order 11246)" within the Bid Documents.

CONTRACT DOCUMENTS AND SPECIFICATION:

Copies of the Contract Documents and Specification are available for inspection at no cost to the bidder at City Hall. The documents can also be downloaded from the City's Website (<u>https://www.beaumontca.gov</u>) and <u>www.PUBLICPURCHASE.COM</u> and reviewed at no cost.

BID & BIDDER:

Bids must be accompanied by cash, a certified or cashier's check, or a Bid Bond in favor of the City in an amount not less than ten percent (10%) of the submitted Total Bid Price.

Each bid shall be accompanied by the security referred to in the Contract Documents, the non-collusion affidavit, the list of proposed subcontractors, and all additional documentation required by the Instructions to Bidders.

The successful bidder will be required to furnish the City with a Performance Bond equal to 100% of the successful bid, and a Payment (Labor and Materials) Bond equal to 100% of the successful bid, prior to execution of the Contract. All bonds are to be secured from a surety that meets all of the State of California bonding requirements, as defined in Code of Civil Procedure Section 995.120, and is admitted by the State of California.

Each bidder shall be a licensed contractor pursuant to the Business and Professions Code and shall be licensed in the following appropriate classification(s) of contractor's license(s), for the work bid upon, and must maintain the license(s) throughout the duration of the Contract:

• California Class "A" and/or Class "C" license

Pursuant to the requirements of the CalRecycle-Rubberized Pavement Grant Program, the successful bidder must complete and submit CalRecycle Form 168 – Reliable



Contractor Declaration, signed under penalty of perjury, stating that within the preceding three (3) years, none of the events listed in Section 17050 of Title 14 (<u>www.calrecycle.ca.gov/Laws/Regulations/Title14/</u>), California Code of Regulations, Natural Resources, Division 7, has occurred with respect to the contractor or subcontractor(s). The contractor or subcontractor must not be listed on the CalRecycle Unreliable List (<u>www.calrecycle.ca.gov/Funding/Forms</u>) otherwise, the City may be required to terminate that contract. Obtain the Reliable Contractor Declaration form (CalRecycle 168) from the CalRecycle web page.

FOR FURTHER INFORMATION CONTACT: Public Works Department Tel: (951) 769-8522 E-mail: <u>dchristensen@beaumontca.gov</u>

NOTICE INVITING BIDS

CITY OF BEAUMONT PUBLIC WORKS AGREEMENT

EXHIBIT "B"

CONTRACTOR'S Bid

(Insert behind this page.)



Pennsylvania Avenue Widening CIP 2017-009

BID FORM

NAME OF BIDDER: All American Asphalt

The undersigned, hereby declare that we have carefully examined the location of the proposed Work, and have read and examined the Contract Documents, including all plans, specifications, and all addenda, if any, for the following Project:

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

We hereby propose to furnish all labor, materials, equipment, tools, transportation, and services, and to discharge all duties and obligations necessary and required to perform and complete the Project for the following BASE BID TOTAL BID PRICE:

BASE	BASE BID PRICE	BID PRICE
BID	(IN WRITTEN FORM)	(IN NUMBERS)
TOTAL BID PRICE	Seven Million Two Hundred Ninvetyone Thousand Two Hundud FIFLY dollars	7,291,250.

ALTERNATIVE	ALTERNATIVE BID PRICE	ALTERNATIVE PRICE
BID	(IN WRITTEN FORM)	(IN NUMBERS)
TOTAL ALTERNATIVE PRICE	Eight Hundred Sixty Two Thou Sand, Five Hundred dullars	8 62, 500.

In case of discrepancy between the written price and the numerical price, the written price shall prevail.

1




BASE BID

BID SCHEDULE A CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTIT UNIT	ΓY/	UNIT PRICE (FIGURES)	TOTAL COST (FIGURES)
1	Mobilization	1	LS	648,880	648,880.
2	Stormwater and Non-Stormwater Pollution Control	1	LS	50,000 .	50,000 .
3	Clearing & Grubbing	1	LS	150,000.	150,000.
4	Roadway Excavation	7,500	CY	75.	562,500.
5	Remove Concrete	63	CY	470.	29,610.
6	Remove Bollards	4	EA	600.	2,400.
7	Remove Tree	2	EA	2,700.	5,400.
8	Remove Asphalt Concrete Pavement	1,060	CY	100.	106,000.
9	Remove Headwall	9	EA	12,500.	112,500.
10	Remove Drainage Inlet	3	EA	7,000.	21,000.
11	Remove 60-Inch CMP Bubbler	1	EA	16,000.	16,000.
12	Remove 18-Inch CMP	450	LF	270.	121,500.
13	Remove Chain Link Fence	280	LF	17.	4,760.
14	Cold Mill AC Pavement (2")	7,100	SY	le .	42,600.
15	Class 2 Aggregate Base	5,670	CY	@j 55.	311,850.
16	Hot Mix Asphalt	3,150	TON	120.	378,000.
17	RHMA-G Overlay (Variable Depth)	2,400	TON	145.	348,000.
18	Imported Borrow	250	СҮ	50.	12,500.
19	Lime Treatment	14,000	SY	30.	420,000



ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTIT UNIT	-Υ/	UNIT PRICE (FIGURES)	TOTAL COST (FIGURES)
20	Minor Concrete (Curb)	570	LF	25.	14,250.
21	Minor Concrete (Curb and Gutter)	3,130	LF	50	156,500.
22	Minor Concrete (Colored Stamped Hardscape Median)	2,790	SF	18.	50,220.
23	Minor Concrete (Longitudinal Gutter; W=2')	35	LF	50.	1,750.
24	PCC Pavement (Driveway)	1,580	SF	25.	39,500
25	Detectable Warning Surface	120	SF	160.	19,200.
26	Minor Concrete (Sidewalk Per County of Riverside Std Detail 401)	15,820	SF	9.	142,380.
27	Minor Concrete (Curb Ramp Per County of Riverside Std No. 403 Type A)	4	EA	8,000.	32,000
28	Minor Concrete (Curb Ramp Per County of Riverside Std No. 403 Type B)	2	EA	8,000.	16,000.
29	Minor Concrete (Cross Gutter Per County of Riverside Std No 209)	390	SF	25.	9,750
30	3-Inch Thick Stabilized Decomposed Granite	810	SF	/5.	12,150
31	4-Inch Thick Gravel Approach	1,960	SF	10.	19,600.
32	Chain Link Fence (CL-6)	580	LF	70.	40,600.
33	Chain Link Double Gate (CL-6)	4	EA	2,750	11,000.
34	24-Inch CMP	20	LF	530.	10,600.
35	36-Inch CMP	40	LF	575.	23,000
36	42-Inch CMP	40	LF	640.	25,600.
37	18-Inch RCP	150	LF	475.	25,600. 71,250.



Ł



ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTIT UNIT	Ύ/	UNIT PRICE (FIGURES)	TOTAL COST (FIGURES)
38	24-Inch RCP	440	LF	445.	195,800.
39	42-Inch RCP	140	LF	1,200.	168,000.
40	60-Inch Type GMP (MOD) Steel Pipe Bubbler Structure	1	EA	41,000.	41,000
41	Jack and Bore 42-Inch RCP	100	LF	3,750	375,000.
42	Concrete Encasement	300	CY	400.	120,000
43	Rip Rap Apron	40	CY	1,365.	54,600.
44	Modular Wetland Model# MWS-L-4-15- C	1	EA	160,000	160,000
45	Modular Wetland Model# MWS-L-8-24- 4'6"-C	1	EA	210,000	210,000.
46	Pipe Culvert Straight Headwall	20	CY	4,300.	86,000.
47	Precast Type OL Drainage Inlet	2	EA	31,000.	62,000.
48	Precast Type G3 Drainage Inlet	2	EA	23,000.	46,000.
49	Type IX Inlet	1	EA	28,000.	28,000
50	Concrete Pipe Inlet Type OCP with Steel Plate Per Caltrans Std Plan D75B	1	EA	21,000.	21,000.
51	Catch Basin Per RCFD & WCD Std No. CB100 (W=7')	1	EA	16,500.	16,500.
52	Catch Basin Per RCFD & WCD Std No. CB100 (W=28')	1	EA	36,500.	36,500. 36,500.
53	Storm Drain Manhole No. 1 Per RCFD & WCD Std Dwg No MH251	3	EA	15,000	45,000.
54	Storm Drain Manhole No. 2 Per RCFD & WCD Std Dwg No MH252	1	EA	17,800-	17,800.
55	Concrete Collar Per RCFD & WCD Std No. M803	6	EA	4,500.	27,000.
56	Pipe Culvert Wingwall Per UPRR Standard Type A-1	40	СҮ	4,500	180,000.



ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTITY/ UNIT		UNIT PRICE (FIGURES)	TOTAL COST (FIGURES)
57	Adjust Valve Cover to Grade	21	EA	960.	20,160.
58	Adjust Sewer Manhole to Grade	5	EA	1,300.	6,500.
59	Adjust Storm Drain Manhole to Grade	1	EA	1, 300.	1,300.
60	Pavement Marking and Signing	1	LS	41,000.	41,000.
61	Traffic Control	1	LS	825,000.	825,000.
62	Traffic Signal Modification	1	LS	290,000.	290,000.
63	Testing and Removal of Lead Painting Striping	3,200	LF	2.20	7, 040.
64	Hazardous Soils Management	1	LS	25,000.	25,000.
65	Burrowing Owl Survey	1	LS	1,200.	1,200.
66	Nesting Bird Survey	1	LS	20,000	20,000.
67	Paleontological Monitoring	1	LS	25,000	25,000.
68	UPRR Flagging	1	LS	Pre-Set Amount	\$100,000
PROJECT BASE BID SUBTOTAL:					7,291,250.



ALTERNATIVE BID BID SCHEDULE B CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

ITEM NO.	DESCRIPTION OF ITEMS	EST. QUANTITY/ UNIT		UNIT PRICE (FIGURES)	TOTAL COST (FIGURES)
1	Remove ADL Contaminated Soils (Within City and Caltrans Right-of- Way)	1,700	СҮ	325.	552,500.
2	Remove Contaminated Soils (Within UPRR Right-of-Way)	400	CY	330.	132,000.
3	Reuse ADL Contaminated Soils (Within City and Caltrans Right-of-Way)	1,700	CY	70.	119,000.
4	Reuse Contaminated Soils (Within UPRR Right-of-Way)	400	CY	85.	34,000.
5	Archeological Discovery	1	LS	25,000.	25,000.
	PROJECT ALTERNATIVE BID SUBTOTAL:				

In case of discrepancy between the unit price and the item cost set forth for a unit basis item, the unit price shall prevail and, shall be utilized as the basis for determining the lowest responsive, responsible bidder. However, if the amount set forth as a unit price is ambiguous, unintelligible or uncertain for any cause, or is omitted, or is the same amount as the entry in the "Item Cost" column, then the amount set forth in the "Item Cost" column for the item shall prevail and shall be divided by the estimated quantity for the item and the price thus obtained shall be the unit price. Final payment shall be determined by the Engineer from measured quantities of work performed based upon the unit price.

In case of discrepancy between the written price and the numerical price, the written price shall prevail.



BID CERTIFICATION

Bidder certifies that it is licensed in accordance with the law providing for the registration of Contractors,

License No.	#267073
Expiration Date	1-31-2024
Class of license	A, C-12

If the bidder is a joint venture, each member of the joint venture must include the above information.

The undersigned acknowledges receipt, understanding and full consideration of the following addenda to the Contract Documents:

- 1. Addenda No. <u>1</u> thru <u>1</u>
- Attached is the required bid security in the amount of not less than 10% of the Total Bid Price.
- 3. Attached is the fully executed Non-Collusion Affidavit form.
- 4. Attached is the completed Designation of Subcontractors form.
- 5. Attached is the completed Bidder Information Form.
- 6. Attached is the completed Contractor's Certificate Regarding Workers' Compensation form.

Bidder acknowledges and understands that, pursuant to Public Contract Code Section 20676, sellers of "mined material" must be on an approved list of sellers published pursuant to Public Resources Code Section 2717(b) in order to supply mined material for this Contract.

I hereby certify under penalty of perjury under the laws of the State of California, that all of the information submitted in connection with this Bid and all of the representations made herein are true and correct.

Name of Bidder	All American Asphalt	
Signature	1	
Name and Title	Michael Farkas, Secretary	
Dated	9-30-2022	



CONTRACTOR'S CERTIFICATE REGARDING WORKERS' COMPENSATION

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake selfinsurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this Contract.

Name of Bidder	All American Asphalt	
Signature		
Name and Title	Michael Farkas, Secretary	
Dated	9-30-2022	



DESIGNATION OF SUBCONTRACTORS CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

In compliance with the Subletting and Subcontracting Fair Practices Act of the Public Contract Code of the State of California, each bidder shall set forth below: (a) the name and the location of the place of business and (b) the portion of the work which will be done by each subcontractor who will perform work or labor or render service to the Contractor in excess of one-half of 1 percent of the prime contractor's total bid or ten thousand dollars (\$10,000), whichever is greater.

Portion of the Work	Subcontractor	Location of Business	% of Work
Fence	ACE Fence Cu	La Prente, Ca	,7090
Survey	C L Survey & Muping	Covona, Cø	, 80 90
Storm Drain	O'Dully	Romoland, Ca	30.09%
Lime Treat Rolway externation	Pavement Necyclin 545tem	Jurupa, Valley, Ca	9.3490
Cruck Seal	Pavement Rohab	Covona, Ce	.09 90
Striping	Superior Pavement Markeng	Cypress, Ca	, 59 70
Tree Vemoral	Tree Smith Enterrise	Anaherm, ca	.0790
Electrical	Elecnor Belco Electric	Chino, Ca	3.80 %



Portion of the Work	Subcontractor	Location of Business	% of Work

Name of Bidder	All American Asphalt
Signature	
Name and Title	Michael Farkas, Secretary
Dated	9-30-2022



INFORMATION REQUIRED OF BIDDERS CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

A. INFORMATION ABOUT BIDDER

[**Indicate not applicable ("N/A") where appropriate.**]

NOTE: Where Bidder is a joint venture, pages shall be duplicated and information provided for all parties to the joint venture.

1.0	Name of Bidder:	All American Asphalt
2.0	Type, if Entity:	Corporation
3.0	Bidder Address:	400 E. Sixth Street
. <u> </u>		Corona, CA 92879

951-736-7646	951-736-7600
Facsimile Number	Telephone Number

4.0 License Information:

#267073	A, C-12	1-31-2024	
License No.	Class of License	Expiration Date	

#1000001051 DIR Registration No.

5.0 How many years has Bidder's organization been in business as a Contractor?

53 years

6.0 How many years has Bidder's organization been in business under its present

name? 53 years

5.1 Under what other or former names has Bidder's organization operated?

None

INFORMATION REQUIRED OF BIDDERS



7.0 If Bidder's organization is a corporation, answer the following:

7.1	Date of Incorporation:	5-26-69
7.2	State of Incorporation:	California
7.3	President's Name:	Mark Luer
7.4	Vice-President's Name(s):	Edward J. Carlson
7.5	Secretary's Name:	Michael Farkas
7.6	Treasurer's Name:	Michael Farkas

8.0 If an individual or a partnership, answer the following:

8.1 Date of Organization:

N/A

8.2 Name and address of all partners (state whether general or limited partnership):

N/A

9.0 If other than a corporation or partnership, describe organization and name principals: N/A

10.0 List other states in which Bidder's organization is legally qualified to do business.

None



11.0 What type of work does the Bidder normally perform with its own forces? Grading, Paving & Concrete

12.0 Has Bidder ever failed to complete any work awarded to it? If so, note when,

where, and why:

No

13.0 Within the last five years, has any officer or partner of Bidder's organization ever

been an officer or partner of another organization when it failed to complete a contract?

No

If so, attach a separate sheet of explanation:

N/A

14.0 List Trade References:

Robertson's Ready Mix

200 S. Main St., #200

Corona, CA 92879

15.0 List Bank References (Bank and Branch Address):

Citizens Business Bank

12808 Central Ave.

Chino, CA 91710



16.0 Name of Bonding Company and Name and Address of Agent:

(Surety) Fidelity & Deposit Co. of Maryland

(Agent) <u>Foundation Risk Partners Corp.</u> 5530 Trabuco Road - Irvine, CA 92620

INFORMATION REQUIRED OF BIDDERS



B. LIST OF CURRENT PROJECTS (Backlog)

[**Duplicate Page if needed for listing additional current projects.**]

Project	Description of	Completion	Cost of	Contact Name &
	Bidder's Work	Date	Bidder's Work	Phone
				· · · · · · · · · · · · · · · · · · ·
		See Attach	ed"	
-				

30595 30126 30347 30367	30300 30339 30348	30738 30766	30319 30262	30269 30229 30243	30185	30166 30178	30280 30594	30134 30268	30240	30100	30587	30186	30022	29997 30535	29926	30198	30079	29946	29897	29744	29197 30923	29593	29684	29518	29342	29464	29463	29403	29050	29082	29295	28905	28903 28903	28901	28696	29891	28617	28313	29333	28199	28017	27946	27632	28165	27296 27216	Job No.#
5/2/2018 5/7/2018 5/14/2018 5/14/2018	4/26/2018 -4/30/2018 5/2/2018	4/25/2018 4/25/2018 4/25/2018	-4/10/2018 4/17/2018	4/4/2018 4/5/2018 4/10/2018	3/27/2018	3/15/2018 3/21/2018	3/13/2018 3/14/2018	3/6/2018 3/7/2018	2/15/2018	2/8/2018	2/4/2018	1/30/2018	1/24/2018	1/18/2018	1/1/2018	12/18/2017	12/13/2017	11/30/2017	11/6/2017	10/30/2017	10/16/2017	9/27/2017 9/27/2017	9/6/2017	7/19/2017	7/17/2017	7/6/2017	7/1/2017	6/5/2017 6/5/2017	4/14/2017	4/11/2017	3/22/2017	1/19/2017	1/19/2017	1/19/2017	12/1/2016	11/2/2016	10/12/2016	9/14/2016	9/13/2016 9/14/2016	7/1/2016	4/25/2016	3/10/2016	1/1/2016	9/15/2015 10/15/2015	7/1/2015	Date
Atkinson City of Long Beach Lennar Homes City of Hermosa Beach	City of Simi Valley Lennar Homes City of Indian Wells	City of Santa Cianta California Professional Engineering 2016 Atkinson	Riverrock Real Estate Group City of West Covina	Chino Development Corp. Caltrans City of Santa Clarita	Department of Transportation	City of Invindale Caltrans	Ortiz Enterprises Inc.	Chino Development Corp.	Meridian Parkway County of Orange	SL Ontario	OHL, USA	Flatiron West, Inc.	County of Riverside Trans. Dept. Dennis Lorton & Associates		KB Homes	The New Home Company	Peterson Chase	City of Yucaipa	City of Industry	Hardy & Harper	Pardee Homes	County of Riverside Trans. Dept.	Department of Transportation	SL Ontario	Parkwest Rescom	Christopher Development	SL Ontario	Speiker Development	Lewis-Hillwood	City of Long beach City of Costa Mesa	Guy F. Atkinson			ICDC	Foremost Companies	OHL	City of Norwalk	Calatlantic Group	Los Angeles Foremost Companies	Chino Preserve Development	Five Point Communites	Chino Development Corp.	Five Point Communities	City of Industry Atkinson	City of Inglewood Hardy & Harper	Agency / Owner
Limonite & L15 - County of Riverside Runway 12-30 Rehabilitation Euclid Avenue Improvements Hermissa Avenue Pavement Resultacing Project	FY 2017-18 Annual Major Streets La Palma Cook Street Rubbenzed Pavement Overlay/	12 2016-03_ Slumy Traffic Signal@Green River&Montana Scott Road & I-215 - County of Riverside	Centerstone Plaza Residential Street Rehabilitation at Various Locations	07-3009U4 Route 110 Soledad Canyon Road Ruether	Route 512-007604	2017/2015 Resurtacing Project (12-007704) Route 91 Ramp Rehabilitation	OSO Parkway Bridge - FD2 - County of Orange	Pine Avenue improvements Stages 1 & 2	Barton Road Screet Improvements	Merril Avenue Street Improvements	Route 110; 07-29/304 Route 91,105,110,405 07-286/04	07-202124, Route 710	Alessandro Blvd Eastbound bike Lane improvements	Deeriake Route 110, 405 07-293704	Archibald - Eucalyptus to Parkvlew	Bedford	07-307804 Cold Plane, HMA, JPCP, & Upgrade ADA R	Sth Street Improvements Program	San Savaline IIII.provenierius - rounaria Baldwin Park Boulevard and Amar Road Guardrail	Cedar Street & Reed Lane	Railroad Canyon Widening Podola Springs PA-6 Access Road	Gilman Springs Road and SH-79 Northbound Ramps	Copies State Lesson and Lesson and Lesson and Lesson and State Lesson and Les	Park Place Ph 2 St Improvements	Misinise regins D4 MBB Dire Ave Steel Improvements	Tr. 18998 Park Place 2	e Wa	Reata Glob /1-15 Interchange Improvement	Renissance & Linden Street Improvements	Tewinkle Park Parking Lot Improvements	07-252824 Route 5 Annual Street Improvements B-7084	Orchard Hills N3 Street Improvements	Orchard Hills N3 Street Improvements	Orchard Hills N3 Street Improvements	Terramor Intract Terramor Intract Barrance from Alton to Marine Way	Olada Aleba Installi	Rehabilitation of Alondra Boulevard from Studebaker Re 2 Orchard Hills Backhone	Hentage Lakes Dr & Mccall Blvd - Menifee	/enhurs	Tr. 1936/1935/1955/18480	District 4 Area 3 & Pusan My FIC Project-Figureoa Comdor Streetscape Improvel 4	Tr. 18480 Street Improvements	Alton Parkway from Barranca to Technology	Industry Business Center Roadway 3 07-1193U4, Route 10	Century Blvd. Mobility Improvement Project 8 Elysian Rreservoir Improvements Project 8	La Pala Gap Closure
\$ 2,668,098.00 \$ 1,820,438.00 \$ 958,430.00 \$ 2,160,864.46	\$ 1,517,770.00 \$ 1,072,000.00 \$ 599,599.59	\$ 93,387.00 \$ 3,281,677.50	\$ 518,750.00 \$ 427,770.00	 3,360,000.00 29,757,315.00 167,766.00 	\$ 8,330,362.00 \$ 8,330,362.00	\$ 285,503.10 \$ 974,781.35	\$ 2,157,960.00	\$ 3,685,159.70	\$ 1,492,622.00 \$ 85,562.71 \$ 798,000,00	\$ 1,112,085.00	\$ 408,570.00 \$ 1 580 580 00	\$ 499,025,00	\$ 1,609,342.55 \$ 60,582.20 \$ 46,031,00	\$ 2,139,646.00	\$ 297,052.00	\$ 1,214,417.00	\$ 1,334,310,00 \$ 400,013.00 \$ 133 777 00	\$ 962,888,00 \$ 1 354 516 00	\$ 170,811.00 \$ 445,821.50	\$ 12,880.00	\$ 5,062,746.00 \$ 959 000.00	\$ 589,540,00 \$ 781 175 nn	\$ 5,871,030.00 \$ 3,776,106,16	\$ 800,965.90 \$ 27 260 00	\$ 185,375.00 \$ 1,000,207.00	\$ 153,578.80 \$ 3,609.257.00	\$ 73,700.00 \$ 75,800.00	\$ 1,608,291.00 \$ 3,149,197.50	4,630,000.00	\$ 450,002.50 \$ 1 564 080 10	\$ 4,800,000.00	\$ 693,366.70 \$ 484 020 25	\$ 443,778,75 \$ 638,421,48	\$ 452,169,88	\$ 1,815,000.00 \$ 2,609,295,00	\$ 32,330,151.81 \$ 1 260,635.00	\$ 686,686.00 \$ 2220,000,00	\$ 990,249.92 \$ 905,212,26	\$ 1,397,636,00 \$ 2,232,659,00	\$ 831,551.40 \$ 343,872.50	\$ 1,192,000.00 \$ 11.806.000.00	\$ 1,646,289.00 \$ 304 997 00	\$ 2,414,828.13 \$ 2,414,828.13	\$ 18,784,000.00 \$ 9,349,470.14	\$ 18,118,000.00 \$ 712,675.00	9 333,052,66
31,582 5,900 1,800 7 660	8,000 1,200 3,780	35,435	3,640 2,600	62,600 169	58,550	4,920	28,235	9,000	65 65	4,000	1,860	3,447	0 300 300	1,340	640	4,500	3,010		د, 27 ت 160 151	2 275	14,000	10 000	32,300	4,400	5 000	1,100 24.170	1,100	12,200 45,500	25,000	390 9 500	46,300 75 000	1,180	2,100	2,650	4,000	373,000	5,222	5,888 3,500	40	2,500	7,000	4,000	6,000 6,000	9,410 135,000	15,622 0	117,000
0 Day & 562 Da		0 45 Day/	3 a o	35	500		0 9	400	10 450	250	en o			1.2	200	1,000		180	57		1,200	30	600	600 Day		160		0 Day	4,000	176 800	5.000			7,000	500	-	172	500 00	1,000	600 Day/N	1,200	1,000	500	14,059	12,142 Day	
y/Night 356 Working Days / & Nitr 60 Calendar Days Day 90 Days Day 80 Working Days	y 40 Wo y 45 Wo	ay 45 Wo Night 360 Wo	Day 15 Working Days Day 40 Working Days	Wo	Vight 180 Working Days	Nor	No.	Wo	Day 90 Working Days	Day 90 Working Days	Vight 250 Working Days	Night 1250 Working Day	av 1 Wo	ght 700 Wo	Day 30 Days	Day 80 Days	light 80 Working Days	Day 90 Working Days	Day 30 Calendar Days		Day 85 Working Days Day 90	y 35 Wo	Vight 270 Working Days		3	Day 90 Working Days Day 120 Days	Day	Day 120 Days & Nite 496 Working Days	Day 180 Working Days	Day 18 Working Days	Day 520 Working Days Day 365 Days	Day Dav	Day Day		Day 95 Days 90 Days	Day Day 240 Working Days	Day 60 Working Days Day 120 Working Days		4 595 Cale 95	/ 8 E	Day 75 Days Day 200 Working	Day 90 Working Day 2 years	hay 120 1ay 60 Days	ay 250 Working	5	2 4
Gordon Michele		111		Jim Maurice									Maurice	1					Edward	Cody	_	Maurice		Miguel	Michele	Miguel	Miguel	Michele	Miguel	Maurice	Gordon	Miguel	Migue)			Brett	Jerry Miguel	Michele	Gordon Michele	Miguel Brett	Michele Gordon	Miguel Brett	Michele	-	Cody	ł
John M		John W Art	5. 20	5					_ ;	5			Art	5. 9	5	Jol	7.	John W John W	5.	<u>م</u>	교 등			д ,	5 7	۵.	٤,		Έ,	מה	5	a a	מת	סכ ס	꼬늘	πΩ	מ מכ	<u>د د</u>	10		07	교능	7 7 7		Jim	1

31156	31670	31178	31674	3119/	31215	31153	31152	31150	31207	30981	31222	31214	31559	31146	31035	31029	31017	30976	30999	30966	31051	30847	30965	31001	31698	30886	30877	30837	30814	32489	30971	30921	30819	30840	60805 60/05	30861	30860	30779	30817	30748	30/02	30758	30745	30741	31130	30701	30695	30674	31422	30713	30637	30663	30576	30571	30580	30579	30475	30474	30440 30463	30481	30443	30425	30767	30417	30454	30441	30581	30658	30518	JOD INU.#	
2/22/2019 2/22/2019	2/20/2019	· 2/20/2019	2/14/2019	2/12/2019	2/4/2019	· 1/31/2019	1/29/2019	1/23/2019	1/10/2019	1/10/2019	1/4/2019	1/4/2019	BLUC/FC/CF	12/5/2018	12/5/2018	11/29/2018	11/29/2018	11/16/2018	11/6/2018	11/6/2018	10/30/2018	10/29/2018	10/25/2018	10/22/2018	10/18/2018	10/16/2018	10/11/2018	10/10/2018	10/10/2018	10/8/2018	10/3/2018	10/3/2018	9/25/2018	9/18/2018	9/17/2018	9/13/2018	9/13/2018	9/13/2018	9/12/2018 9/12/2018	9/4/2018	8/30/2018	8/23/2018	8/23/2018	8/22/2018	8/17/2018	8/17/2018 R/17/2018	8/16/2018	8/9/2018 8/9/2018	8/1/2018	8/1/2018	8/1/2018	7/23/2018	7/17/2018	7/12/2018	7/9/2018	7/5/2018	6/14/2018	6/12/2018	6/7/2018	6/5/2018	6/5/2018	6/4/2018	6/1/2018	6/1/2018	5/29/2018	5/29/2018	5/24/2018	5/23/2018	5/22/2018	4/22/2018	7.10
Brookfield Homes Philbin Construction	LA Metro / Atkinson City of San Gabriel	LA Metro / Deco Pave	Flattron Corp.	City of Cathedral City	SoCal San Pedro SPV	County of Ventura City of Downey	City of Chino	Leatherwood Construction	City of Downey	Los Angeles County Department	Lennar Homes	Brookfield Homes	Lennar Homes	City of San Clemente	City of Burbank	Five Point Communities	Skanska USA Civil	City of Long Beach	Caltrans	Dennis Lorton & Associates	City of Huntington Beach	Belco Electric	City of Beverly Hills	Park West Rescom	OHL USA	City of Santa Ana Caltrans	Caltrans	Alston Construction	Leatherwood Construction	Walsh Construction	Spectrum Construction	County of Riverside Transportation	LACSD	City of Santa Fe Springs	Five Point Communites	ICDC	ICÓC	City of Norco	County of Cranne	City of Loma Linda	Chume Construction	County of Riverside Purchasing a	County of San Bernardino	City of San Clemente Riverside Transportation Departm	Brightview Landscape	Martin Harris Constnuction	C.S. Legacy	City of Westlake Village	County of Orange	County of Orange	City of Lynwood	City of Malibu	City of Fontana	Lown of Apple Valley City of Norwalk	City of Lynwood	Lennar Homes	City of Jurupa Valley City of San Dimas	City of Yucaipa	REDA (Perris Gateway)	DR Horton	Cathedral City	City of Yortha Linda	City of Inglewood	County of Orange	City of Highland	Pomona Unified School District	City of Paramount	County of Orange	City of Santa Fe Springs	City of San Jacinto	Annoul Dumor
Archibald & ORR Improvements Hentage Lake - Menifee	2018 CDBG Street Improvement Project Cash Contract	Metro Sound Wall #11-2	Rediands Passenger Rail Project (RPRP) Mainline 20118/2010 Payament Rehab Program	Ortega Road Widening and Sidewalk Gap Closure	Western Ave. & In-Trad Improvements	Fire Station Interim Construction	Slurry Seal Maintenance Work	D5 Rach B East (#20511801 & 20651801)	Paramount Boulevard Median Island Improvement	o South LA County Malibu Area	Summit @ Rosena Penmeter Streets	The Groves - Whittier	Phillid Descrievia Latit - III - Sait statit sepisitativ Brines Boad Improvements	Juan	ent Pro	District 5 Phase II Masler Backbone Street	SR-60 Truck Lanes	2010 Devement Dehah Droject	Route 142 08-1E8504	Bristol Street Parking Lot	Pavement Management Program Sectors B. C. D & E -	Street Light Conduit Installation	Arkell Drive Street Improvements	Ridge Valley Parkway PCC Trail	Roule 5 12-0C8904	OBA3010 Route 79- Hemet	08-1E5104 Widening of Sholder and Installing Rumble	Almond & Jurupa	D5 Reach 8 East	OC Streetcar	12-DN2704 Route 91 Weight Station	Camino Aventura Sidev	Fill Below Grade Portions of Rail opurs at Puente Hills	Florence Street Rehabilitation (Norwalk Blvd to	OCGP Sports Park Access Rd	Enterna	Water Quality Basins 70A	Second St Widening st I-15 Inter	Rossmoor Phase 1C - Crackseal and AC Repairs JOC	Pavement Rehabilitation at Vanous Locations (CIP#18-	Route 405 12-0H0454	In Triple Crown Road/Fire Station 54 Road Paving Project	Cherry Avenue and Andel Drive	Siurry Seal for Camino de Estrella Frujeci No.	Saddleback College Running Track	Santa Fe Swap Meet	Wells Arlanza Sidewalk Improvements	Joint City Pavement Renab. FY 16-19 Duncan Ave Street Improvements (4011.67.907)	Rossmoor North & Collectors Grind & Overlay	Rossmoor Full Depth	Olanda Street & Virginia Ave Improvement Project	2017-18 Street Maintenance Project	Citrus Avenue rom Santa Ana Avenue to Slover	Local Street Rehabilitation (Project No. 7919)	Olanda Street Improvement (Project No. 4011.67.908)	Hentage Tract 3/406-3	San Dimas Avenue ET AL Pavement Rehabilitation	Acacia Avenue, California Street, 1st Street and Alley	Harley Knox Improvements	Singleton Hd - Calimesa	Dinah Shore Drive & Date Palm Improvement	2018 Parking Lot Rehabilitation & ADA Improvements	North La Brea Avenue Improvement	JOC - HCA Parking Lot	Route 15 (08-1H0904)	Intersection Improvements at Diamond Ranch High	Paramount BivdArtenal Street Resurfacing	John Wayne Airport	N. Residential St. Improvements	Esplanade Ave Street Improvement (SJ-393)	Project Title
\$ 515,623.0 \$ 137,992.0	\$ 21,500.0 \$ 377,334.0	\$ 2,092,660.0	\$ 2,913,039.6	\$ 459,998.0	\$ 3,658,952.0	\$ 1,377,000.0	\$ 372,805.0	\$ 115,289.0	\$ 1,521,946.0 \$ 3,878,618.0	\$ 1,000,000.0	\$ 3,119,000.0	\$ 4,648,913.9	0 800 800 800 80 80 80 80 80 80 80 80 80	\$ 1,107,107.0	\$ 1,387,770.0	\$ 1,377,896.0	\$ 4,597,892.5	4 341,700.0	\$ 5,439,395.0	\$ 42,400.0	\$ 2,175,778.0	\$ 19,296.0	\$ 209,660.0	\$ 200,351.8	\$ 1,350,691.0	\$ 288,296,0	\$ 1,788,310.0	\$ 78,400.0	\$ 178,705.0	\$ 2,645,117.5	\$ 223,862.0	\$ 2,019,190.5	S 246,670.0	\$ 973,887.0	\$ 642,341.0	\$ 1,475,002.52 \$ 195,000.02	\$ 1,504,996.4	\$ 353,294.00	\$ 1,197,842.28	\$ 419,966.1	\$ 345,000.00	\$ 95,645.00 • 106 078 50	\$ 5,442,912.00	\$ 2.008,439.00	\$ 295,000.00	\$ 796,000.00 \$ 379,000.00	\$ 25,300.00	\$ 2,350,700.00 \$ 1,137,855.78	\$ 2,347,264.42	\$ 1,749,702,68	\$ 1,539,949.00	\$ 654,979.86	\$ 502,703.00	\$ 1,747,202.00	\$ 260,975.94	\$ 1,199,903.70	\$ 1,627,965.00	\$ 349,895.00	\$ 3,820,847.00	\$ 1,684,585.00	\$ 2,023,923.00	\$ 436,735.00	\$ 4,540,992.00	\$ 441,904.00	\$ 786,170.30	\$ 274,103.00 \$ 1 710 300 00	\$ 837,770.00	\$ 3,668,233.00	\$ 409,877.00	\$ 381,410.00	
500 500	1,200	14,770	19,000	640	10,000	550	100	630	35,800		21,528	22,000	230	2,200	000,7	5,800	46,000	8 000	29,920	280	8,080	20	391	3 300	14,500	123	onn 5,250	250	850	1 22,242	2,030	2,333	300	6,600	300	775	600	115	7,882	2,950	4,100	240 160	43,000	10,105	2,100	250	220	9,100 1,600	0	0	22 BUD 1,100	1,867	552 13 000	11,400	1 640	5,245	9,620	3638 638	8,500	4,300	8,111	666	8,850	2,550	940	150 11.320	2,400	10 000	1,070	ŏ	AC Tonnage C
200 Day 200 Day 700 Day	100 Night Day	0 Night	1.700 Day/Nigh	490 Day	2,000 Day	Day	50 Day	Day	723 Day Night	Day	2,000 Day	2,000 Day/Nigh	Day		400	1,500 Day		120 Day	20 Night	0 Day	50 Day	0 Day	26 Day	20 Day	Night	152 Day	15 Day	Day	Day	1 000 Dav	Day	1,860 Day	110 Dav	120 Day	200 Day	100 Day	250 Day	47 Day	0 Day	63 Day	Day	40 Day	40 Day	0 Day	Day	Day	0 Day	544 Day	335 Dav	0 Day	5 178 Day	2,000 Day	340 Day	700 Day	360 Dav	1,200 Day	230 Day	300 Day	1,500 Day	20 Day	1,470 Day	40 Day	D Night	30 Day	235 Day/Night	25 Day	300 Day	2 340 Day	225 Day		Concrete Day/Nigh
40 Days 20 Days 40 Working Days	30 Working Days	520 Working Days	90 Calander Days	50 Working Days	180 Days	36 Calendar Days	55 Working Days	20 Working Days	990 Working Days	75 Winteing Dave	80 Days	1 120 Days	5 Working Days	00 000	DO Cale	40 Working Days	1 650 Working Days	120 Calendar	Teo working Days	Š	60 Working Days	1 Working Day	20 Working Days	65 Working Days	250 Working Days	Wo	365 Working Days	5	20 Days	30 days	250 Working Days	65 Working Days	Wor	35 Working Days	Wo	30 Working Days	Nor	45 Working Days	Wor	30 Working Days	Wo	2 Working Days	180 Working Days	30 Working Days	30 days	30 days	2 0	70 Working Days	2	365 Calendar Days	140 Working Days	45 Working Days	Nor	Wor	40 Working Days	40 Working Days	Wor	40 Working Days	250 Working Days	30 Working Days	World	Word	1 Working Days	20 Working Days	35 Working Days	75 Working Days	35 Working Days	120 Working Days	30 Working Days	30 Calander Days	Contract Time
Miguel Cody	Maurice	Gordon	Cody	Maurice	Grea	Greg	Cody	Greg	L Geg	Jeny	-	-	-	Gordon	lonv	Greg	Edward	Cody	Jenry	Maurice	Maurice	Maurice	Greg	Maurice	Jim	Jim	Cody	Michele	Michele	Michele	i a	Edward	Maurice	Maurice	Michele	Michele	Miguel	Edward	Gordon	Edward	Jim	Maurice	Jim	Jim	Riguel	Michele	Maurice	Edward	Gordon	Gordon	Lim	Edward	Greg	Edward	Maurice	Michele	Maurice	Greg	Michele	Maurice	Maurice	Greg	Maurice	Gordon	Edward	Maurice	Cody	Miguel	Maurice	Edward	P.M.
Jim John W Rick	Jim Kir	A		John W	N u lo	Rick	John M	Rick	An	Rick	Jim	Jorge		Rick Kin	Rink	Rick	A	John M	Jorne	A	John W	John M Rick	John M	Jim	Art	lohn W	Art		Rick	Rick	An	lohn W	Iohn M	Rick	Rick	ohn W	Rick	Jeny	Rick	lohn W	Art	Todd		ohn W	Rick	Rick	Art	ohn M		Rick Kim	ohn M	ohn M	Jim	Rick	Jim	ohn W	Jim	onn w	ohn W	ohn M	W nho	Rick	Art	Rick	Jerry	shin W	Rick	Rick	Rick	111/	Supt Coo

31867 32054 31884	31778 31831 31790	32305 31775	31864 31721	32780 31834	31750 31829 37240	31705	31719 31893	31723 31686	31666 31671	31621 31779	31642	31830 31582	31882 32156	31602 31528	31509	31500	31495 31498	31690	31487	31524	31492	31565 31475	32361	31457 31485	31451 31672	31447 31510	31416	31414	31407	31561 31486 31402	31385 31543	31531 31383	31355 31371	31350	31382	31286	31277 31290	31309 31370	31316 31261	31273 31282	31213	31206 31267	Job No.#
8/27/2019 8/28/2019 9/3/2019 9/5/2019	8/22/2019 + 8/23/2019 8/27/2019	8/15/2019 8/21/2019 8/22/2019	* 8/6/2019 8/8/2019	8/1/2019 8/2/2019 8/5/2019	8/1/2019 8/1/2019	7/30/2019	7/29/2019 7/29/2019	7/18/2019 7/19/2019	7/9/2019	7/3/2019 7/3/2019	7/2/2019	6/20/2019 6/27/2019	6/18/2019	6/10/2019	6/5/2019	6/4/2019 6/5/2019	6/3/2019 6/4/2019	5/31/2019 6/3/2019	5/30/2019 5/30/2019	5/29/2019	5/29/2019	5/23/2019 5/23/2019	5/22/2019	5/21/2019 5/22/2019	5/20/2019 5/20/2019	5/15/2019 5/16/2019	5/10/2019	5/10/2019	5/8/2019 5/8/2019	5/3/2019 5/3/2019 5/7/2019	5/1/2019 5/2/2019	4/30/2019	4/25/2019	4/24/2019	4/17/2019	4/2/2019	3/28/2019 3/28/2019	3/18/2019 3/27/2019	3/18/2019 3/19/2019	3/13/2019 3/13/2019 3/14/2019	3/7/2019	2/26/2019	Date
C.S. Legacy City of San Fernando City of Loma Linda City of Corona	County of San Bernardino Westlake Village LA County Sanitation District	Myers & Sons Construction Churno Construction City of Norco	Peterson Chase City of Stanton	Thomas Nagy Construction GM Grading Carmol Partners	Lewis Management City of Athambra California Professional Engineering	City of Laguna Niguel Los Angeles County Department of	Pavement Recycling Systems, Inc. Brightview Landscape	Park West Rescom Giantech Construction Inc.	City of Irvine Landsea/Murow CM	City of Colton Sema Construction	City of Clarentonic City of Hemet	City of Downey	Hal Hayes Construction James W. Fowler Co.	City of Lake Elsinore Exclusive Towing	County of Orange	City of Chino Hills	City of Moreno Valley City of Rancho Cucamonga	J. Francis City of Palm Springs	RV CUINCEE City of Dana Point RSB Group Inc.	Riverside Construction	City of Westminster	City of Bellflower	City of Crange	City of Fountain Valley Caltrans	V. Lopez Jr & Sons/Dept. Veteran	Eastern Municipal Water District Guy F. Atkinson	City of Santa Fe Springs Griffith Co.	J & M Concrete	City of San Clemente Boys Republic	City of Compton City of Long Beach County of Ventura	Los Angeles Engineering Lennar Homes	City of Chino OC Asphalt	City of San Bernardino	City of Simi Valley Hernet Unified School District	Caltrans	City of Pomona City of Huntington Beach	City of San Marino City of South Gate	City of Orange City of Santa Ana	City of Lake Forest City of Lancaster	City of Irvine Caltrans	CEM Construction Corp/Baldwin P	Duke Realty March Joint Powers Authority	Agency / Owner
Verdugo Street Heautrication Project Clenoaks Blvd. Street Resurfacing and Highway Safety Pavement Rehabilitation at Beliatre St., Taylor St., Street Mantenance & Rehabilitation 2017-22 (rebid)	CSA 70, R4/ Road Sturry Seal Annual Street Resurtacing FY 19-20 Asphalt CAP Summer 2019	Route 15 Contract No. 08-1F1424 Route 57 Vine Avenue, Dnthwood PI, Half Moon Ct	Roule 91,110 07-331604 2019 Citywide Street Resurtacing	(PLR) 5500 Sepulveda Blvd - Culver City Perns Ottsite Expo Asphalt	FY 17-18 SB1 Street Reha	Alicia Parkway Artenal Pavement Reconstruction (Sustainable) (RNDJOC6547 Pavement Reconstruction (Sustainable)	District 5 Area 1 C	Disind 1 West Novel Segment 2 57 Wheeler Avenue	idewa	믿껇	2018-19 Slurry Seal Project, CIP No. 5688 Contract for local Street Improvements Project R-7153	Runway 18-36, Taxiway A - French Valley Airport FY 2018/19 Situry Seal Protei District 3 CIP No. 19-12 Control And Seal Protein Best dama Protein	Chino Creek Levee Asphalt Repaying Montezuma/Mid City Pipeline- San Diego	Lincoln Street Pavement Rehabilitation & Striping Towing Yard Street Improvements	John Wayne Airport- Pavement Maintenance & Repair Pavement Rehabilitation Program - Citywide - Rancho	Rolling Ruge Drive Pavement Rehab.	FY 18/19 Major Artenal Rehab.	08-1J204 Route 15,91,215 Runway Cores - Palm Springs Airport	Annual Roadway Resultacing Project FY 2018/2019 (05-1H6404) Rte#210 EB Highland Ave Off-Ramp	08-1J4104 Roule 71 08-1J4104 Roule 71 08-1H3404 Procest Slab and Curb Ramo Replacement	Bolsa Avenue Bolsa Avenue Local Street Preventative Maintenance FY 2018-19	Eucalyptic Service Street Improvements 2019-20 Pavement Management Program System 4	Joc Pavement Maint-Cowan Heights- FY 19-20 Firestone Boulevard Street Improvement Project	Newnope Street Frenato. A resurtating Route 15, 74, 79 Contract No. 06-13-5604 2019 Pavement Management Protect (REVIVE 25)	(NCA) Asphalt Road Repair & Seal	Asphalt Paving Services at Temecula Valley Regional Route 60//10	Sanla Fe Springs Rd. Improvement South Gate Manholes	Disneyland Syborn Parking Lot	22	Annual Contract for Major & Secondary Highway Pavement Resurfacing Yerba Bluena Area	Mt San Anionio College Field	El Prado Road Reconstruction Baker Ranch	Pavement Rehab 10 Locations Old Topanga Rd Improvemet Project	Minor Street Renab SV 19-08 Playoround Asphalt Removal & Reconstruction	Callrans (27-000000) Route 10 manual Callrans (12-0R2604) Route 90	Sifeet and Alley neriaumation improvements Residential Ovenay Maintenance Zone 6 Contrans (7.3004604) Houle 1 - Malibii	Street Renabilitation Program Circle Park Driveway Project	Annual Pavement Maintenance various Locations First and Raitt	Citywide Roadway Improvement 2018 Pavement Management Program (RE VIVE 25)	Irvine Center/Odyssey Subsidence Repair Roule 5 (12-0R2704)	Walnut Creek Nature Park Improvements	24960 San Michele Koad Van Buren Phase 3 Street Improvements	Project Title
\$ 77,710.40 \$ 2.399,784.00 \$ 248,969.00 \$ 6,244,244.00	\$ 63,193.74 \$ 1,110,900.31 \$ 12,432.00	\$ 1,256,166,00 \$ 63,245,00 \$ 409,970,00	\$ 97,487.00 \$ 1,206,869.00	\$ 36,672.00 \$ 1,133,983.00 \$ 41.023.00	\$ 2,682,820.50 \$ 164,000.00	\$ 2,348,777.00 \$ 5,100,000.00 \$ 544.000.00	\$ 878,583.34 \$ 186,000.00	\$ 138,726.00 \$ 86,265.00	\$ 1,233,233.00 \$ 969,000.00	\$ 176,766.00 \$ 120,821.40	\$ 815,575.00 \$ 40,000,000.00	\$ 2.046,047.00 \$ 313,425.87 \$ 84 844.00	\$ 162,233.56 \$ 1,355,924.86	\$ 833,360.25 \$ 27,292.00	\$ 3,914,178.00 \$ 855.333.00	\$ 4,700,000.00 \$ 991,000.00 \$ 4 434 390 49	4,430,000,00 4,1,309,989,00	\$ 74,726.00 \$ 5,773.37	\$ 2,025,451.00 \$ 132,500.00	\$ 394 015 00	\$ 1,123,923.00 \$ 1,716.649.00	\$ 606,436.00 \$ 1,414,770.00	\$ 2,584,747.69 \$ 1.648.493.00	\$ 1,337,770,00 \$ 3,655,135,00 \$ 3,696,389,42	\$ 221,433.00 \$ 4 527 770 00	\$ 295,657.98 \$ 5,019,753.00	\$ 2,011,700.00 \$ 47,840.00	\$ 90,300.00 \$ 86,349.88	\$ 384,055.00 \$ 90,000.00	\$ 10,000,000.00 \$ 3,919,808.95	\$ 385,000,00 \$ 510,510,00	\$ 2,392,367.80 \$ 80,626.00	\$ 4,383,952.00 \$ 1,585,842.00	\$ 510,124.25 \$ 136,999.00	\$ 3,878,948.00 \$ 3,787.500.00	\$ 3,546,889.00 \$ 800 300 00	\$ 1,111,700.00 \$ 268,576.00	\$ 799,096.00	\$ 4,988,350.00 \$ 2,720,103.65 \$ 5,360,007.00	\$ 41,158.00	\$ 78,430.00 \$ 1,377,700.00	\$ 5,650 000.00 \$ 13.112.00	
120 5,900 1,200 29,809	2,550 50	9,400 198 3,450	403	80 2,880 100	15,524 20	5.700	47 000	425	2,000	682 860	120 75,000	400	1,420 0	5,800 160	5,000 6,100	7,300 , 19.710	1 000 1 000	0.83	2,320 610	500	6,655 2,500	190 12,900	5,630	5,000 5,000	820 820	2,225 24,100 3 700	\$ 9,500.00 0	00	2,120 \$ 1,200.00	25,000 15,000	4,700	1,000	18,400 7,800	3,650 1,080	23,000	27,795	100	810	5,000 47 440	0 32,800	188 11,200	15,000	aŭe
		67 0 0		2,000 D	50 D	15 D			700	356 D	5,000 D		0 Day/	0 000	1,060 D	350 D	100		1,200 D		370 Di 620 Bo	115 Da	350 Da	a 1 2	500 D		0 600 Nig	00		60 D	n 150	095	2,400 Da		300 Nig	335 Da	514 Da	100 Da	305 Da		60 Da	2,000 Da	Concrete Day/Nig
ay 80 Working Days ay 15 Working Days ay 60 Working Days	ay 30 working Days ay 35 Working Days ay 15 Working Days	Wor	Nor	ay 2 Working Days ay ay	ay 65 Working Days ay	ay di storang bays 1 Year 30 Days	ay 200 working bays	ay sou Days	ay too working bays	ay 90 Working Days ht 250 Working Days		ay 100 Calender Days ay 30 Working Days av 14 Working Days	Night 640 Working Days	ay 45 Working Days ay	ht 365 Calendar Days ay 60 Working Days	ay 50 Working Days ay 120 Working Days	ay 90 Working Days ay 365 Calendar Days	ht 122 Working Days	Wor	Wor	Nort	Worl	Cale	th 65 Working Days	Blei	y 30 Working Days ht 850 Working Days w 30 Working Days	ht 280 Working Days		y 35 Working Days	y 365 Days y 75 Working Days	y 20 days v 180 Working Days	ς Υ Υ	y 120 Working Days y 40 Working Days	X X	X	2 6	y 30 Working Days			None 110 Working Days 110 Working Days	90 Calander Days	180 Days	
Maurice Jerry Gomon	Gordon	Edward	Edward	Augustine Greg Greg	Gordon	Jerry Miguel	Miguel	Augustine	Miguel	Augustine	Brian Jerry	Brian Maurice	Gordon	Greg	Jim Maurice	Maurice	Edward	Gordon	Greg Edward	Jim Edward	Jim Maurice	Gordon Edward	Gordon	Jim Brian	Augustine	Augustine Jim Edward	Gordon	Gordon	Maurice	Jeny Edward	Miguel	Maurice	Edward	Edward	Jim Cody	Maurice Maurice	Augustine	Jim Maurice	Brian	Jim g	Augustine	Greg	Greg
John M Jeny	John M	Jeny	Doug	John M	John M	Jim	Rick	Jim	Jim	John W Art	John W	Jim	Art	John W	John W	John W	John M	John W	Art	A A	Rick	Jim	Rick	John W John W	John W Rick	John M	Darren	Todd	John W	John M	John M	Art	John W	John W	Doug	Doug	John M	John M	John W Doug	Rick	John W	John W Rick	John W
Kim Ted	Ted		Ted	Ted	Ted	Deonn	Mindi		Kim	Xim	Kim	Kim	Sm	Kim	Kim	Kim	Ted	Kin h	Kim		Kim		Kim	Kim	A A	Ted		H 22	Kim	Ted	Ted	2	E d A	Kim	Kim	Ted	Kim	Ted Tim	Kim	Kim	Kim	Kim	

32770 32480	32442 32445 32551 32547	32372 32367 32382	32336 32350 32526	32466 32262	32316 32335 32349	32351	32359 32643	32309 32345	32277 32331 32339	32315	32557 32288	32337 32274	32328	32243	32312	32286	32242	32554	32259 32507	32253 32249	32167 32171	32172	32143 32141	32087	32074 32251	32056	32260 32053	32092	32022 32148	32147 32225	31969 37083	32031	32086 32159	32212 31954	31900 31908	31977	31899 31897 31897	31976	32037 31862	31844 31916	31890 31895	Job No.#
4/14/2020 4/14/2020 4/14/2020 4/16/2020	4/17/2020 4/14/2020 4/14/2020 4/14/2020	4/1/2020 4/2/2020 4/2/2020	3/20/2020 3/26/2020 3/31/2020	3/19/2020 3/20/2020	3/19/2020 3/19/2020	3/17/2020	3/5/2020 3/9/2020	3/4/2020 3/5/2020	3/2/2020 3/2/2020 3/3/2020	2/27/2020	2/19/2020 2/20/2020	2/13/2020 2/18/2020	2/11/2020	2/3/2020	2/1/2020	1/23/2020	1/15/2020	1/9/2020	1/7/2020	1/6/2020	12/19/2019	12/18/2019	12/11/2019	12/5/2019	12/2/2019	11/21/2019	11/21/2019	11/12/2019	11/12/2019	11/4/2019 11/5/2019	10/23/2019	10/17/2019	10/11/2019	10/2/2019	10/1/2019	9/24/2019 9/24/2019	9/23/2019 9/24/2019 9/24/2019	9/19/2019	9/17/2019 9/18/2019 0/48/2019	9/12/2019 9/17/2019	9/10/2019 9/10/2019	Date
County of Los Angeles County of Los Angeles County of Los Angeles City of Newport Beach	City of Santa Ana City of Santa Ana California Professional Engineerin County of Los Angeles	City of Jurupa Valley City of Victorville City of Loma Linda	Telichert City of Cancho Cucamonga City of Rancho Cucamonga	City of Compton Bosco Constructors	American Civil Contractors City of Menifee City of Chino Hills	City of Anaheim Sturgeon Electric	City of Norco Crosstown Electrical Data, Inc.	City of Norco Pulte Homes Company	City of San Marino City of Temple City	City of Simi Valley Department of Transportation	Peterson-Chase City of Ontario	Riverside Construction Company, City of Rancho Santa Margarita	City of Paramount City of Huntington Beach	City of Camarillo Crescenta Valley Water District	City of San Jacinto	City of Chino Hulls	City of Torrance	Stephen Doreck County of Ventura	Belco Elecnor Group	County of Orange City of Menifee	JB Paving & Engineering Pardee Homes	City of Westminster County of Orange	Tolar Manufacturing Inc. Pardee Homes	County of San Bernardino Transpo Suket Construction	City of Montebello	City of El Monte	City of Brea	City of El Monte	City of Lynwood City of Desert Hot Springs	City of Invindale Pavement Coatings	City of Santa Ana	City of Chino Hills	City of Riverside Ortiz Enterprises Inc.	City of Santa Ana	County of San Bernardino Fullmer Construction	Commerce Colony	Duke reality Calpro Max/City of La Verne Kaiser Permanente	City of Orange	Powell Construction, Inc. City of Santa Ana	Caltrans	Leonida Builders Inc. Leonida Builders Inc.	Agency / Owner
Dei All Project 660-300-00 Ladera Heights 6990-800-00 RMDUCC6680 Pavement Preservation (Seal Coals), Carneo Highlands	Henninger Neighbornood Keskidenual Sirett Repair Local Siret Preventative Maintenance NGCIV of Curlahy ATP Cycle 2 Project RMDJOC65/9 Pavement Preservation (Seal Coats),	Granite Hill Drive Pavement Renabilitation Third Avenue Road Improvement Pavement Renab on Barton Road	(07-31204) Kie Zarity Property Monory France Bayberry Unive and Valle Visa Drive Project FY 15-20 Local Slurry Seal Pavement Rehabilitation Crestiview Drive Pavement Improvement Project	Annual Residential Street Rehabilitation-Phase 1 (09-315504) Ric#118 MVP	Rte. #110 Place High Friction Sufface Treatment Ethanac Road & Sherman Road Street Resuffacing 2019-2020 Street Improvement Project ST 200001	Master Agreement for Sluny Seal and Crack Seal (08-384234) Rte #10 Install Fiber Obtic Cable System	City of Newport Beach - Traffic Signal Upgrade Pothole Reoair Services	Hamner Avenue Street Rehabilitation West Haven Cascade Offsile Street Rehabilitation	FY 2019 Street Rehabilitation Program Project Las Tunas Blvd Pavement Rehabilitation Phase 1,	F T 2019-20 militor sitests neridenmanuti riogram, Route 215 from PM R40.3 to PM 43.1 Confract 08-	2020 Spring Pavement Rehabilitation Project	FY 19-20 Annual Residential Slurry Seal	Neighborhood Street Resurfacing on Various City Graham, Slater, Newland and Atlanta Rehabilitation	Final Paving on Pennsylvania Avenue	Sanderson Avenue Salely Improvements Project, EI Toro Building	Pipeline Avenue Pavement Rehabilitation Project No. Slurry Seal Project FY 19/20	Residential Street Rehabilitation - Area A	Malbu Yerba Buena Road Resuffacing	City of Burbank - Midtown Commencal Traffic Signal	CCPW Fruit Street - Pave CIP 20-10 Andalusia/Belcanto Street Resurtacing	VVWD - Sluny Wilson Street Improvements	Citywide Overlay JOC Maintenance & Facilities Slumy & Paving Services	Parking Lot Slumy Highland Springs Avenue Street Improvements	Montclair ADA Ramps & Sidewalk Cow camp and street Improvement	Holifield Parking Lot Improvements Slurry Seal and Pavement Resurfacing - Phase 2	Ramona Blvd & Valley Blvd, Intersection Memil Avenue Street Improvements	Asphalt Grind & Overlay	Surry Seal & Pavement Resurfacing Project - Phase 1	Palm Drive Street Lighting and Safely Improvement	2019 Resurfacing Project:Longden Avenue From Live 2020 Pavement Management Program (Neighborhood	Unstol Street and Edinger Avenue Class II Bike Lanes Bristol Street Rehabilitation	Pine Avenue Pavement Rehabilitation Project, Project SR-2101 ane Addition	Route 5 Contract No. 12-0/C014 City of Burbank - Traffic Responsive Signal System	Edinger Avenue Rehabilitation	Chino_Philipelphia Street	Archibald Street Improvements Loraine Avenue Street Rehabilitation - Palm Drive to	Regional Commuter Bicycle Gap Closure Project Normandie N. Parking Lot (Harbor City	CDEG FY 18-19 Maple Neighborhood, Sacramento Perris & Nandrina Paving Project	Edinger Protected Bike Lanes Califans 12-0P0104 Floule 39	Roule /9 08-1F6904	McSweeny Farms - Phase 2 - Hemet	Project Title
\$ 987,576,79 \$ 2,942,683,89 \$ 4,800,000,00 \$ 2,425,694,00 \$ 6,324,158,90	\$ 1,987,588.00 \$ 154,680.00 \$ 4,200,000.00	\$ 999,777.00 \$ 1,790,000.00 \$ 768,677.00	\$ 514,220,10 \$ 637,229,00 \$ 196,232,00 \$ 646,098,00	\$ 5,295,068.00 \$75,275.00	\$ 1,276,858.70 \$ 1,276,845.68 \$ 1,093,145.00	\$ 225.651.17	\$ 112,540.00 \$ \$1650.00 per hr	\$ 649,000.00	\$ 2,109,419.00 \$ 644,444.00	\$ 240,000.00 \$ 159 929 32	\$ 2,197,669.00 \$ 2,197,669.00	\$ 2,169,978.46 \$ 368,168.88	\$ 1,238,777.00 \$ 5,151,955.00	\$ 681,901.50 \$ 82,620.00	\$ 773,226.06 \$ 403,775.05	\$ 219,894.00 \$ 1,897,897.00	\$ 2,133,840.00 \$ 109,407.00	\$ 2,298,467.40 \$ 329,765.00	\$ 272,800.00 \$ 1 921 565 50	\$ 314,579.24 \$ 1,009,844.00 \$ 377 819 00	\$ 1,154,144.00 \$ 1,154,144.00	\$ 1,131,621.00 \$ 1,500,000.00	\$ 38,070.00 \$ 6,891,770.93	\$ 940,699.00 \$ 4,400,000.00	\$ 133,352.00 \$ 3,462,905.50	\$ 2,997,428.00 \$ 1,459,459.00	\$ 33,410.00 \$ 116,565.00	\$ 1,325,747.00 \$ 221.517.00	\$ 2,099,222.00 \$ 769 827 00	\$ 330,995.00	\$ 607,839.99 \$ 639,608.00	\$ 192,444.00 \$ 6,349,608.00	\$ 4,915,852.50 \$ 133,880.00	\$ 688,956,00 \$ 13 138 339 25	\$ 1,278,376.38 \$ 655,000.00 \$ 2,053,713.50	\$ 1,949,000.00 \$ 1,438,622.00	\$ 238,584.00 \$ 40,070.00	\$ 536,244.00 \$ 168,384,50	\$ 1,663,906.00 \$ 134,025.00	\$ 7,642,529.00 \$ 89.590.19	\$ 113,342.00 \$ 37,052.00 7 740 880 00	
4480 10261 8000 35.900	3570 100	8000 6260	4400 2,000	18920 250 450	/90 3,292 11550	220	850	0 000,c	12600 4880	1100	15100	000,02	5380 25881	3,068 325	0 1955	1600 1840	7800 1056	6,632 3100	20	5580 1500	5390	0	12230	560 45000	3000	2,025 4,500	111 780	2000	5790 7330	3,200 3,200	1,742	920 69,400	45,300 20	2,150 43,228	4,223 1,035 3 840	3,500 10,250	750 70	1,820 1,175	3,190 40	42,000	1,419 315 8.000	AC Ionnage
440 0 Zin n n n n	60 50 50	200 0000000000000000000000000000000000	180 D	0 N N					100 D	0 150 Ni	340 D		420 D 1495 D	083		00	0 ⁸⁴⁴	8	190 D	410 Day 0	740 Day 8	0 Day 8	1530 Da	1500 Da	305 000	1,100 Da 1,400 Da	10 0 D Nij	0 285 Da	0 0 Da		30 126 Da	0 Day &	70 Nig	100 Da	242 Da 0 Da 1.700 Da	3,000 Day		0 Da	707 Day	0 0 Nigh		Concrete Day/N
hay hay hay 80 Working Days haht 50 Working Days	ay 90 Working Days ay 10 Working Days	ay 30 Working Days bay 70 Working Days bay 40 Working Days	ay 40 Working Days ay 60 Working Days	aht 500 Working Days aht 500 Working Days	ay 60 Working Days ay 40 Working Days	ay 150 Working Days	ay 10 Working Days ay 365 Working Days	av 20 Working Days	ay 60 Working Days 21 Working Days	ght 30 Working Days ay 10 Working Days	ay 40 Working Days av 50 Working Days	ay 30 Working Days	ay 40 working Days ay 105 Working Days	ay 25 working Days ay 30 Working Days	ay 90 Working Days ay 40 Working Days	ay 20 Working Days ay 60 Working Days	ay 120 Working Days ay 60 Working Days	ay 80 Working Days ay	ay 15 Working Days ay 165 Working Days	ay 40 Working Days ht 250 Working Days	Ay Ay Note 90 Calander Days	Nite 365 Calendar Days	ay 10 working Days	y 225 Working Days	y 60 Working Days	y 120 Working Days 85 Working Days	ht 1 Working Day y 30 Working Days	y 45 Working Days	y 85 Working Days	y 60 Working Days	y 90 Working Days	y 20 Working Days Nite 840 Working Days	ht 1110 Working Days y 15 Working Days	y 90 Working Days 200 Working Days	y 120 Working Days	45 Working Days	y 10 Working Days	y 60 Calendar Days y	king Days		2 Working Days	_
Kim Brian Jim Edward	Jim Brian	Maurice Augustine Maurice Jim	Maurice Brian Edward	Gordon Edward Edward	Edward	Edward	Maurice Augustine	Miguel	Maurice Maurice	Jim Augustine	Maurice Edward	Jim	Jim	Augustine	Gordon	Kim	Augustine	Edward Gordon	Maurice Edward	Maurice	Gordon	Gordon	Greg	Miguel	Gordon	Augustine	Augustine Augustine	Gordon Jim	Maurice Greg	Maurice	Jim	Gordon	Jim Maurice	Jim	Miguel	Maurice	Augustine	Greg	Augustine	Jim Edward	Augustine .	Auronieting
John M Darren Rick John W	Rick John M Darren	John W Rick	John W John W	Art Doug	John W	John W	John M	Jim John W	John M	John W Jerry	John W John M	An	Doug		Rick	Rick	John M	John M Art	John M Rick	John W Art	John W Rick	Rick	John W	Rick		i u u	Rick	A Jin	John W Rick	Doug	Rick	Art	Art John M	Rick John W	Jim			John W	John M	Art V	John W	iohn W
Gio Gio	Gio	Mindie Gio	Mindie Mindie	Deonne	Mindie	Mindle	Deanne	Gio	Deonne	<u>6 6</u>	Mindie	Mindie	Deonne	Mindie	Gio	Mindle	Ted	Deonne	Deonne Gio	Gio	Mindie	Mindie	Ted	Mindia	Mindie	Mindie	Mindie	Ted	Mindie	Ted	Mindle	Mindie	Mindie	Mindle	Kim Mindie	Kim	Ted	ą	Mindle Ted	Kim	Ted	Kim

10/16 -10/19 10/19 10/19 10/19 10/19	913 9/29/ 937 9/29/ 020 9/29/ 947 10/8/ 947 -10/14/ 961 -10/14/ 964 10/15/ 972 10/15/ 266 10/15/ 266 10/15/	047 9/15/ 3/76 9/16/ 8/76 9/17/ 9/17/ 9/17/ 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/36 9/17/ 1/37 9/16/ 1/37 9/12/ 1/37 9/12/	7781 8/19/2 867 8/19/2 7779 8/21/2 7789 8/21/2 8/2 9/2 9/2 9/2 9/2 9/2 9/2 9/2 9/2 9/2 9	9396 8/1/20 846 8/2/20 827 8/20 827 8/20 827 8/20 827 8/10 827 8/10 8	74 B/17/22 74 B/17/22 75 B/17/22 76 B/17/22 76 B/18/22 76 B/18/22 77 B/18/22 78 B/26/22 79 B/18/22 71/20/22 B/26/22 71/12 B/26/22 71/12 B/18/22 71/14 B/18/22 71/14 B/18/22 71/28/22 B/18/22 71/28/22 B/17/22 71/14/22 B/17/22 7/29/23 T/22/22 7/20/23 T/22/22 7/28/23 T/22/22 7/28/23 T/22/22 7/28/23	12 5/7/2002 12 5/7/2002 13 5/7/2002 14 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 15 5/7/2002 16 5/7/2002 17 6/3/2002 16 6/4/2002 17 6/3/2002 17 6/3/2002 17 6/3/2002 17 6/3/2002 16 6/4/2002 17 6/3/2002 17 6/3/2002 18 6/3/2002 19 6/3/2002 10 6/4/2002 10 6/4/2002 10 6/4/2002 10 6/4/2002 10 6/4/2002 10 6/4/2002 10	0.# Late 44222/200 844229/200 844229/200 844229/200 844429/200 844429/200 8445/200 8445/200 8445/200 8445/200 8445/200
2020 Belco 2020 Ferrei 2020 SC 0 2020 Leonio 2020 KB H 2020 KB H	2020 City o 2020 City o	2020 City ol 2020 City ol 2020 Murow 2020 Belco 2020 Belco 2020 San B 2020 Town 2020 Lands 2020 City o 2020 City o	2020 City of 20220 City of 20220 City of 20220 City of 2020 City of 020 City o	City of City o	0220 Delos e 0220 City of 0220 City of <th>Calify of Calify of Calify</th> <th>20 City of V 20 Caltrans 20 County of 20 County of 20 City of V 20 City of V 20 City of A 20 City of A 20 City of A</th>	Calify of Calify	20 City of V 20 Caltrans 20 County of 20 County of 20 City of V 20 City of V 20 City of A 20 City of A 20 City of A
o Elecnor Group eira Construction Jontano Nata Builders Homes	ly of Pornona y of Pornona tranic International Airport y of Norce y of Seal Beach y of Seal Beach y of Carson y of Carson y of Carson	I figlewood I figlewood Elector Group Elector Group Elector Group County of Yucca Valley of Yucca Valley va Homes va Homes va Homes	of Temple City of Wille Park of Menifee of Torrance e Pipeline of Rancho Cucamonga of Raincho Cucamonga wa CM wa CM	Vicitia Linda Santa Fe Springs Clanta Valley Water Agency Inglewood e Costruction of Crange e County Santiation District Costa Mesa Costa Costa Mesa Costa Costa Mesa Costa Costa Mesa Costa Mesa Costa Costa Mesa Costa Costa Mesa Costa Costa Costa Costa Mesa Costa Costa Costa Costa Costa Mesa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa Costa	Elector Group Elector Group Harnet Chine Hills San Dimas San Dimas Alkinson Wejo Walnut Alkinson Corange San Clemente Gendrora San Clemente Gendrora Construction Const Meso District Const Services District Comm Services District	of Corange Peaadena Elecaror Group Elecaror Group Elecaror Andre Sierra Madre Perns Sierra Madre Perns Sierra Madre Fortana Delsgn Bullders/Anaheim Ortario Octario Octario Cottario Co	Vestminster Vestminster Riten Water District Arricho Santa Marganta Vrange Vrange Vrange Of Grange
Paim Springs - Tahyuitz Canyon Improvements Lyttle Creek Street Improvements Eucalyptus Avenue Street Improvements Allessandro Alley Improvements - Phase 1 Wood Rd & Lurin Ave Street Improvements Tract18028 West Haven Officiale Street Improvements	Major Sireel Rehabilitation - 2015 Metric Gall-Project Nuringe Sireel and Hancock Avenue Rehabilitation - Amazon Repairs Ver US Second Sireel Widening PY 19-21 Annual Street Resultaning Program - Bolsa PY 20-21 Annual Street Resultaning Program Project CIP Alley Rehabilitation Project Carbon Annual Overlay Program & Annual Concrete Replacen Santa Ana - Erdigi SI At Hazard Signal Modification	2019-2019 CDH2 Ward 5 since Street and Aley Improvements Underson Way Univer CRy - Traffic Signal Left Broadway Improvements & Traffic Eucalyptus Avenue Street Impro- Eucalyptus Avenue Street Impro- 2020 CDBG Local Street Impro- 2020 Payement Feabilitation	Las Tunas Hivi Favement Rehabilia Fy 2019-2020 Annua Street Rehabili Fublic Works Maintenance & Operatio Fublic Works Maintenance & Operatio Fublic Repeating a Annual Improvement Capital Improvement Project No. 16-20 Foothil Boulevard Pavement Rehabili Boselina Hoad Improvements Baselina Hoad Improvements RetEID Prine Tree Wind Power Plant A	Farmont Blvd 400 FT SIO / Los Nietos Koad Street Impi Ridge Route Koad Pavemer Citly Parking Lot - 1300 S. (Back Panking Lot - 1300 S. (Abarton Manhole Hamilton Street & Santa An Collwhole Slurry Seal Frojecti University Drive El Toro Road Mission Viejo Permanent Trench Hesuita 2010-21 Canyon View - Gni FY 202-21 Canyon View - Gni FY 202-21 Canyon View - Gni	Corry of Clanicale - North Verdugo T. S. Projeć 2019-2020 Pavement Rehabilitation Phases Canyon Hills Koat Pavement Rehabilitation Phases Canyon Hills Koat Pavement Rehabilitation Phases Allex Reconstruction - Alley P - Cataract to Monie Vista Allex Partway. Jeronimo Roda and Maguente Valaud, Amar Road Street Rehabilitation from Nogales 12-DK0244 Route 5 Covern Heights Overlay 2020-2021 Applial Keplacement At Vanous Locations Septiveta Street Rehabilitation from Nogales 12-DK0244 Route 5 Covern Heights Overlay 2020-2021 Applial Keplacement At Vanous Locations Septiveta Street Rehabilitation Covers Ave Chent Usa Die Lago Streets Project Dear Street Ingroverment Project - Hots Baker St., City DIA - Taxway C Improvement Overlay and Report Io Catle Prino	Merrill and Hyan S Overlay Merrill and Hyan S Corelay Resultant of Corange Grove Aven. Cry of Pains Spinos, - Traftic Spinos Interstant, 15 Placettila Ave Inter Interstant, 15 Placettila Ave Inter Interstant, 15 Placettila Ave Inter Valley Bivli & Anthray Loi Improv Stera Visit Park Fahvig Loi Improv Stera Visit Park Fahvig Loi Improv Stera Visit Park Fahvig Loi Improv Prz 2019-20 Atenia Roadway Keta Valley Bivli & Anthray Retabilitation 1 Prz 2019-20 Atenia Roadway Keta Valley Bivli & Anthray Retabilitation Radia Ave Witteria Roadway Keta Valley Bivli & Anthray Retabilitation Resultancy Project on Paios Veter Parkaria Roadway Ketabilitation Resultancy Brodet on Paios Veter Parkaria (Strate Roadway Ketabilitation Result 215 3 & 0.0 Col. 1) Koute 15 (5. Roade 215 3 & 0.0 Col. 1) Koute 15 (5.	Westminster Bivd 1:2-QR80A: Route 5 Asphalt Roadway & Parking Loi Restoration La Sierra Ave Reconstruction and Siurry Seal Project Road Maintenance and Rehabilitation Improvement Annual Siurry Seal at Venbuiltation Annual Siurry Seal at Venbuiltation Rossmoor Collectors Grind & Overlay
\$ 1129,000,00 \$ 1197,573,500 \$ 1,230,000,00 \$ 105,225,00 1ts \$ 475,000,00 1ts \$ 1,079,000,00	- 5, 154, 356, 174 - 5 110,005,00 S 110,005,00 698, 776,00 Sa 5 199,522,00 Sa 205,870,455 140,948,00 Sa 14,442,375,00 74,103,00 N 74,103,00 74,103,00	S 2/2/2/28.00 Vite S 2/14/150.00 On S 9/4,000.00 S 63,225.00 50,225.00 S 63,225.00 50,000.00 S 50,000.00 52,000.00 S 52,000.00 52,000.00 2 S 216,140.00 2/20 S 1,316,573.03	S 1,445,888,00 S 5,466,00 S 5,268,466,00 S 5,268,200 S 3,687,032,00 S 7,54,143,250,00 S 1,843,250,00 S 1,844,350,00 S 1,844,350,000 S 1,944,350,000 S 1	10 \$ 113,472,00 5 2,834,444,00 5 5 725,000,00 5 5 725,720,00 6 5 725,720,00 7 5 72,587,00 7 5 7,73,740,00 5 5 1,316,022,00 7 5 1,316,041,00 6 5 2,51,456,00 6 5 2,51,456,00 6 5 2,51,456,00 6 5 2,51,456,00 6 5 2,51,452,00 6 5 2,51,452,00 6 5 1,076,228,00 5 5 1,076,228,00 6	\$ 1175,950,000 \$ 1198,000,000 \$ 106,000,000 \$ 2,343,950,000 \$ 2,343,950,000 \$ 2,343,950,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 3,002,000,000 \$ 4,70,920,000 \$ 4,70,920,000 \$ 4,70,920,000 \$ 4,126,940,000,000 \$ 4,126,940,000,000	S 1,481,822,12 S 1,481,822,12 S 4,290,8175,00 S 4,290,8175,00 S 4,290,8170,00 S 1,182,975,50 S 1,182,975,50 S 1,182,975,50 S 2,329,789,00 S 2,329,789,00 S 2,329,789,00 S 2,329,789,00 S 2,329,789,00 S 2,249,742,00 S 2,249,742	\$ 1,875,883,00 \$ 2,81,000,00 \$ 2,81,000,00 \$ 2,849,956,00 \$ 4412,137,00 \$ 317,737,708,84 \$ 1,545,798,84 \$ 1,545,798,84 \$ 1,545,798,84 \$ 1,545,798,84
100 3200 1025 1650	33,800 9380 675 900 31 200 4556 20	12580 2000 20 20 20 20 20 20 20 2700 2700	7620 9262 350 20919 200 9300 520 7000	1750 1750 145 1743 350 3830 3788 4026 9640 9640 518 518 0 0 8,400	1440 8300 350 19820 34580 2200 34580 2200 18300 5315 2580 4400 5315 2580 4400 1980 1980 1980 1980 1980	12400 18945 22250 2016 2016 2016 2016 2016 2010 2010 1025 15000 1145 1445 1145 1145 1145 1145 11	10300 30 2081 2081 2480 410 410 13021 12468
2000 D D D D D D D D D D D D D D D D D D	170 0 0 196 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	(u) , , → Uh -	126 126 126 127 127 127 127 127 127 127 127 127 127	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	100 289 0 289	1854 Day 380 386 Day 24 387 Day 24 388 Day 24 388 Day 24 388 Day 34 390 Day 34 30 Day 34 31 Day 34 32 Day 34 33 Day 34 34 Day 34 35 Day 34 36 Day 34 316 Day 34 316 Night 32 316 Night 34	12 Night 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
y 20 Working Days y 70 Working Days y 70 Working Days y 4 Working Days y 20 Working Days y 60 Working Days	y 100 - 200 working Days y 35 Working Days y 500 - 120 Working Days y 25 Working Days y 25 Working Days y 15 Working Days y 60 Working Days	Y 120 Working Days Y 60 Working Days Y 60 Working Days V Working Jays V Vorking Days V 40 Working Days V	Y Y	4 / Working Days 15 Working Days 16 Working Days 20 Working Days 20 Working Days 20 Working Days 210 Working Days 120 Working Days 210 Working Days 210 Working Days 230 Working Days 24 Working Days 24 Working Days 24 Working Days 25 Working Days 26 Working Days 26 Working Days 27 Jonething Days 28 Working Days 29 Working Days 20 Working Days	40 Working Days 25 Working Days 30 Working Days 50 Working Days 50 Working Days 41 750 Working Days 317 Calender Day 317 Calender Day 317 Calender Days 41 60 Working Days 41 60 Working Days 41 60 Working Days 41 60 Working Days 41 750 Working Days 41 80 Working Days 41 80 Working Days 41 80 Working Days 41 90 Working Days 41 90 Working Days 41 90 Working Days 41 90 Working Days	A Coloridate Days	60 Working Days 30 Working Days 30 Working Days 30 Working Days 50 Working Days 60 Working Days 22 5 Working Days 22 5 Working Days
)ays)ays ays)ays	5502_2most		Augus Augus Augus Augus Bria	Maurice: Augustir Gordor Jim Gordor Jim Gordor Jim Brian Brian Brian	Augusti Augusti Kim Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Gordo Augusti Augusti	Miguei Gorden - Augustine Gorden Augustine Maurise Mau	Jim Augustin Gordon Jim Brian Brian Gordor
Miguel Miguel Miguel Miguel	aurice ordon dward gustine Gustine gustine ordon ordon	an man an a	n el tine			Jim Bandari John W John W John W Band John W John W John W John W John W	

33439	33639	33497	33465	33442	33582	33421	33590	33396	33562	33432	33535	33637	33521	11000	11174	10536	33388	33380	33333	34521	34963	33354	33340	33757	33325	33653	33349	33272	33851	33338	33287	33283	33318	33247	33262	33259	33255	33066	33242	33235	33512 33269	33225	34406	34281	33903	33302	33254 33196	33194	30100	33175	33386	33224	3336/	33230	33141	33260	32999	33331	33069	33292	33065	33091 33042	33197	33007	33056	32992	Job No.#
4/16/202	4/15/202	4/14/2021	4/14/202	4/13/202	4/8/2021	4/8/2021	- 4/7/2021	4/7/2021	4/5/2021	4/5/2021	4/2/2021	4/1/2021	3/31/2021	3/23/2021	3/18/2021	3/11/2021	3/11/2021	3/10/2021	3/5/2021	3/4/2021	3/2/2021	3/1/2021	3/1/2021	2/25/2021	2/25/2021	2/23/2021	2/23/2021	2/23/2021	2/18/2021	2/18/2021	2/17/2021	2/17/2021	2/16/2021	2/15/2021	2/10/2021	2/9/2021	2/8/2021	2/5/2021	2/4/2021	2/1/2021	1/26/2021	1/20/2021	1/19/2021	1/19/2021	1/19/2021	1/15/2021	1/14/2021	1/12/2021	12021011	12/28/2020	12/22/2020	12/15/2020	12/14/2020	12/10/2020	12/10/2020	12/3/2020	12/3/2020	17/19/2020	11/16/2020	11/4/2020	11/4/2020	10/28/2020	10/27/2020	10/26/2020	10/22/2020	10/21/2020	Date
1 City of Long Beach	7		1 City of Garden Grove	J & M Conc Contractors	City of Anaheim	AMES Construction	City of Inglewood	City of Long Beach	City of Banning	City Buena Park	Lennar Homes	Matt Construction	Belco Elecnor Group	City of Hesperia	City of San Bernardino	Lennar Homes	County of San Bernardino	City of westitilister	City of Long Beach	Belco Elecnor Group	Belco Elecnor Group	City of Diverside	Otimans	Crosstown Electrical Data, Inc.	City of Santa Ana	Crusty of Riverside Transportation	City of Huntington Beach	City of Long Beach	Leonida Builders, Inc.	Santa Clarita Valley Water Agency	Belco Elecnor Group	City of Villa Park	HZS Engineering/City of LA	Pardee Homes Duite Homes Company	Crosstown Electrical Data, Inc.	City of Fullerton	City of Long Beach	City of Long Beach	City of El Monte	City of Oxnard	City of Jurupa Valley	City of Glendale	County of Orange	County of Orange	County of Orange	Ontario International Airport Autho	City of Long Beach	City of Long Beach	around an even such as	California Professional Engineering	Lennar Homes	City of Buena Park	City of Westminster	City of Riverside	County of Orange	City of Yorha Linda	OHL USA	Myers & Sons Construction Churno Construction	City of Temecula	City of Santa Ana	City of Victorville City of Santa Ana	City of Cypress	Belco Elecnor Group	Lewis Operating Corp. Monte Companies / KB Homes	City of Carson	Crosstown Electrical Data, Inc.	Agency / Owner
Dist. 3 Channel Dr. (PCH to 7th St.) R-7153	Route 91, 15 08-1L6804	. 8	Arterial Street Rehabilitation	LAWA ITFW - Los Angeles Airport	Anaheim Island Phase 2 Rehabilitation Project RCP202	08-0E3304 Route 60	El Evado and Other Roads	Carson St. B/T West City Littlits to Clain Avents	Ramsey Street and Hathaway Street Inipitventients	2020-2021 Annual Slurry Seal Project	Off-Site Street Improvements - Tract Map 20092, El Ra	LA Country Club Parking Rehab	Traffic Signal Installations and Modifications	FY 2020-21 CDBG Street Improvements	Seal)		Beech Avenue (Phase I)	MSWC Parking Lot #5	Ward Street Improvements	San Gabriel - Instersection Safety Improvements	HSIP-Cycle & Olympic Blvd-City of Los Angeles	2019/2020 Arterial & Minor Phase I	Duke Rider	Catrans - 07-4V1404 Route 213 Big	Flower St. Rehabilitation from McFadden Avenue to 1st	ity of Norwalk Autoba of Riverside Transportation North Indian Canyon Drive Widening Project Phase 2	Local Streets Rehabilitation - Zone 27 East of Gard	Criestiut Ave. Ocean to proceeding to ano			Anaheim - Katella Ave Widening Trench Repair	FY 2020-2021 Slurry Seal Project	Sanborn Avenue Reconstruction		Atwell Meadowline Way Street Improvements	Orangethorpe Avenue Street Improventients Frujew	Newport Ave Coronado Ave.	Third Street B/T Alamitos & Junipero Ave. R-7131	Ramona Blvd Street Resurfacing Project	Downtown Village Parking Lot Rehabilitation		FY 20/21 Pavement Rehabilitation	Joc for Slumy and Paying Services-Facilities-MA-080-	Channel Repair Fence Repair	Prima Deschecha North Access Road Resurfacing	2020-07 Citywide Street Improvements	I Long Beach Lomina Ave B/T Adderely Dr & Rosebay St. R-7153	7153 Residential Street Resurfacing Improvements CDBG Pr 3	GreenBrier Ave B/T Spring St. & Mezzanine Way R-	California Professional Engineering Palmidate - Familiario unio a contractory of Riverside Ramona Express Resurfacing (Rider Street to Warren 2	French Valley - Offsile Street Improvements	Route 71 07-210624	COBG 20-21 Improvements	Florida Ave Water Repairs	Coyote Canyon Landfill	FY21-22 Manhole and Valve Box Adjustment \$	Route 101 07-303/04	07-288304_RTE#2,60,164,210	avement Rehab Program - Citywide West Side \$	south Main Street Corridor os Angeles - On Call Traffic Signal Project \$	Bristol Street Protected Bike Lanes	Cypress Arterial Rehab \$	Hialto - Left Tum Signal Improvements HSIP 8 \$ Adams Park Parking Lot Improvements \$	Underwood Tract 29835-2 Offsite Street Improvements \$	223rd Street Improvement	ehabili	Same Currenting - Traffic Signal Project \$
\$ 159,348.00	\$ 760,722.07	\$ 1,400,400.00 \$ 364.200.00	\$ 3,185,281.00	A 49	2 \$ 128,128.00	\$ 2,166,367.60	\$ 1,107,679.35	\$ 6,850,739.50	s 1.997.357.97	269 E \$	A 4	\$ 094,170.00 * 1755 756 00	* 60/ 170 00	\$ 458,770.00	\$ 549,390,00	\$ 4,590,000.00	\$ 599,601.85	\$ 181,282.00	\$ 2,696,290.00	\$ 690,696.00	\$ 317,516.45	69	69 1	s 2,377,225.00	\$ 305,598.00	\$ 1,998,488.24	\$ 1,051,330.00	\$ 2,614,115.00	\$ 122,532.00	 4 105 915.00 	4 75 000.00	\$ 84,300.00	\$ 46,407.00	\$ 2,795,795.00	\$ 483,056.55	\$ 178,200.00	\$ 605,236.00	\$ 1,813,7/9.49 e 605 458 67	\$ 2,949,717.80	\$ 197,500.00	\$ 1,148,333.00 \$ 4 174.871.23	\$ 838,000.00	\$ 755,412.22 \$ 180 746 00	\$ 171,685.86	\$ 454,878.00 \$ 118.823.92	\$ 678,501.50	\$ 823,810,10 \$ 11,475.00	\$ 138,472.00	\$ 1,173,779.33	\$ 7,916,616.59	\$ 918,000.00 \$ 152,246.00	\$ 1,947,425.00	\$ 345,792.00 \$ 599.864.00	24,240.00	5 2,681,359.00	69,524.78	763,753.80	83 800 85	1,711,230.62	242,635.00	1,967,436.00	279,009.00	67,767.00	2,189,000.00	1,671,391.68	811,311.00	176,748.00
958	1062		12994	9000	543	21900	8,175	10670	7150			6000	5000	10	2675	0000	3,530	1500	15300	1690	2010	16367	24000	3000	00	9,355	10700	25000	13	1035	120	20	775	16000	2500	\$	4500	683	11860	750	16,360	4800	550	0	0	4520	1523 30	90	2586	54,010	30	19260	3800	150	9200	135	7190	4320	19750	60	0 0	535	18 4 700	28	1311	6800 7317	
		•	20	700	-	0	Ĩ	1175		600	0	1200	•	5 c	-	0000	T		725		90	941	2000	2500	45			•		0	0	•	-	3000	250	110	100	_		75	982	50	40	0	•	119	•	•	-	0	70 0		98	30	1000				230 Ni	n Davin	000		34 0 D	8	++	520 Day	10 Day
Day		Night	-		Dav	Night		Day	Day	Day	Day	Day	Day	Dav	Dav	Dav	Day	Day	Day	Day	Day	Day	Day	Day .	Day	Day	Day	Day 6	Day (Day 1	Day	Day	Dav	Day 1	Day	Day	Day 3	Day 9	Day 6	Day 4	Day 9	Day 5	Day 4	Day 36	Day 3	Day 60	Day 10	Jay 3	Day	ignt bu	Day	ight 72	bay 30)av ∠ 30	lay 10	ay 540	ght 400	ght 550	Ξ.	y	ay 12 ay 220	ay 20	ay 25 ay 30	Ý		- 17	
30 Working Days	60 Working Days	95 Working Days	40 Working Days	100 Working Days	ofner Bunuloss 77	340 Working Days	60 Working Days	200 Working Days	60 Working Days	180 Working Days		110 Working Days	90 Working Days		60 Calendar Days	60 Calendar Days	110 Working Days	30 Working Days	80 Working Days	60 Working Days	200 Salaliani - J-	65 Calendar Days	160 Working Days	120 Working Days	to storing	40 Working Days	40 Working Days	30 Working Days	60 Working Days	20 Working Days	15 Working Days		to Working Days	274 Working Days	30 Working Days		15 Working Days	10 Working Days	D Working Days	0 Working Lays	0 Working Days	0 Working Days	D Working Days	0 Working Days 5 Calendar Days	0 Working Days	3 Months	10 Working Days	30 Working Days		60 Calendar Days	Dalasdar Dale	ng Days	ng Days	ng Days	ing Days		ng Days	ing Days		ung Days	ng Days	ng Days	25 Working Days 30 Working Days		-	100 Working Days	-
1	Jerry				t		lim	T	T		t	-	-	Maurice	Augustine	_		Edward				0		Miguel		Jim	Edward	JIM	Jeny	Gordon	Augustine	2			Miguel	1	Augustine		- 11	Gordon								Jeny	Jeny	-	Maurice		-	Jim	-+	-+	+	Jim	+ +		1		Edward				
Inde	Jorge	Art		-	Todd	tt	Art	÷	Jorge	John W	Darren	÷		John W	-	John W	-		-	Jorge	John M	M utor	John W	John W	John M	Rick	John W		Jorge	Art	Jorge	Art	Darren	Art	John W	John M	Rick	Jorge	Jorge	Jim		W untor						Jorge	Jorge	-	John M John W			1		Rick	Darren	-					Rick				
			V Gio				00	Deoline	+	Gio		T	Gio	0	1	-		Gio	Gio	-1-		0		-	0	-	6	1	25			Deonne	Gio		<u>G</u>	Gin	Gio	Deonne	Deonne	Gia	Deonne	Gio	Gio	66	<u>.</u>	Gio	Gio	Deanne	Deonne		Gio	Gio	GIO	Deonne	90	<u>6</u>			Deonne	Gio	Deonne	G10	66	Deonne	Gio	Deonne	Glo

34001	33869	33894	33930	33843	33847	33826	33813	33949	33946	33794	33776	34058	33863	34076	33787	33747	33700	33694	33709	20420	33854	33706	33692	33680	33699	33610	33609	33583	33752	33708	34108	33762	33575	BRSEE	33564	33629	33658	33665	33649	33646	33626	33616	33559	33534	33532	33529		34649	34532	33945	33907	33731	33515	33764	33561	33500	33855	33781	33730	33539	33522	33491	33581	33537	33624	Job No.#
9/1/2021	9/1/202	8/30/2021	8/25/202	B/16/202	8/16/202	8/12/2021	8/11/202	8/6/2021	8/5/2021	8/5/2021	8/5/2021	7/29/202	7/28/202	7/27/202	7/22/202	7/20/2021	7/15/2021	7/7/2021	7/1/2021	1102051	7/1/2024	6/28/2021	6/28/2021	6/25/2021	6/22/2021	6/14/2021	6/14/2021	8/14/2021	6/10/2021	6/10/2021	6/8/2021	6/3/2021	6/3/2021	6/1/2021	6/1/2021	5/28/2021	5/27/2021	5/25/2021	5/25/2021	5/20/2021	5/20/2021	5/20/2021	5/20/2021	5/19/2021	5/19/2021	5/19/2021	5/18/2021	5/18/2021	5/18/2021	5/18/2021	5/18/2021	5/13/2021	5/13/2021	5/12/2021	5/11/2021	5/11/2021	5/5/2021	5/5/2021	5/4/2021	5/4/2021	4/28/2021	4/28/2021	4/22/2021	4/22/2021	4/21/2021	Date
 Lewis Operating Corp. City of Gardena 	_			-			1 City of Long Beach			City of			-	1 Lennar Homes	1 City of Anaheim	City of Rancho Mirage	City of La Verne	VCI Construction, INC. / LD	City of West Hollywood	, and the second s	Century Communities	City of Mission Viejo	City of Mission Viejo	City of Westminster	City of Long Beach	City of Long Beach	City of Long Beach	City of Long Beach	Pavement Coatings Inc	City of San Clemente	City of El Monte	City of Fullerton	City of Redondo Beach	City of Cerritos	Century Communes	City of Mission Viejo	City of Norwalk	City of Aliso Viejo	City of Long Beach	City of West Covina	City of Ontario	City of Azusa	City of Agoura Hills	Lewis Operating Corp.	City of Long Beach	Duke Realty	County of Orange	County of Orange	County of Orange	County of Orange	County of Orange	Tri Pointe Homes, Inc.	County of San Bernardino	City of Santa Clarita	City of Bell Gardens	City of Moreno Valley	City of El Monte	City of Riverside	Pavement Coatings Inc	Fullmer Construction	City of Buena Park	Lennar Homes	City of Palos Verde Estates	City of Riverside Ontiz Enterprises Inc.	City of Lake Elsinore	Agency / Owner
Van Ness Avenue and 139th Street Improvement	Moudian Dhace 3 Street Improvements	Street Pavement Maintenance & Reliabilitation 22-010	Rehabilitation and Resurfacing of Euclid Street Floir E	The Meadows - Street Improvements	Various Streets in District 7. R-7153	Pavement Resurfacing - Simi Area, Spec. No. RD22-03	Winslow Ave Between Colorado Ave R-7153	Annual Citywide Sueet Reliabilitation - manufacture	FY 2020-2021 SB 1 Street Renabilitation & Maintenance	Alamitos Ave. Bikeway R-7131-A	ATP Cycle 4: Safe Routes To School Pedestrian Improvement	Mission Bay Drive Street Improvements	Road Maintenance and Rehabilitation Project	Street Improvements - Tract Map 20205 (PA 2) and Tra	State College Boulevard Improvements from Ball Road	Tamarisk Neighborhood Pavement Kenabilitation	2020-21 Hormel/Ramona Grind and Overlay Improvement	2021 Pavement Rehabilitation Project	Mid City, La brea & SMD Fravenient repair regime.	a construction of the second sec	Tessera Tract 33370 Franklin and Auto Center Dr., Lake	Via Escolar Pavenient Renautivers	Los Alisos Boulevard, Marguerite Parkway and Santa Margan	Street Improvements fro Mcfadden Avenue	Ocean Blvd. & 54th StreetR-7131-A	Monterado - Street & Storm Drain Improvements	Sont En Ave R-7131-A	Outer Traffic Circle K-/131-A	2021 Annual Street Maintenance Project	FY2020 Major Street Maintenance FY2021 Slurry Seal I	Active Transportation for El Monte Station and Downtow	Runway Edges Ethilaricement Frojew	Inglewood Ave at Manhattan Beach Bivd Intersection in	Asphalt Improvements in Residential Streets Project #1	Neighborhood Street Improvements on Various City Stn	Pends Blvd Street Improvement	Local Zone Street Renabilitation Flogrant - Finase 1, 20 Apphalt Benetic & Asphalt Overlays of Various St	FY 21-22 Slurry Seal & Rehabilitation Bhase 1 7n	Myrtle Ave. B/T Market St. & South St. R-7153	EI Monte Bike Blvd. and Pavement Rehabilitation	2021 Fall Pavement Renabilitation Project	Residential Resurfacing Project 2021	Glenn Ranch Road Rehabilitation Project	Parkside In-Tract Streets	Dist. 9 - 68th SL, Atlantic Ave to Orange Ave.R-7153	Los Angeles St. & Rivergrade Rd - Irwindale	JOC for Pavement Maintenance F 1 2021-2022	Hidden Ranch	Antonio Parkway	Crind & Pave Old Counthouse	Phase 2 - Panorama Heights Grind & Overlay	Victoria Street Improvements - Fontana	Pavement Rehabilitation for Various Local Streets	Camet Street and Other Roads	Various Residential Street Improvements FY 20-21	Juan Bautista De Anza Multi-Use Trail - Phase 1	Cedar Ave, Lower Azusa Road, City Limit Area	2019/2020 Arrenal & Willford Streets, Frieddown	2021 Street Maintenance Project	Logistics Center Eastvale	Street Pavement Maintenance & Rehabilitation \$	Rancho Diamonte I R. 33393-1 - Figures	Via Campesina Street Improvements #PW-681-20 \$	Route 405 - 07-293604	Collier Ave Pavement Rehab & Striping Project S Overland (Phase 1) Water Main Replacement Project S	Project this
\$ 1,369,920.	\$ 2,517,333.00	\$ 174	67 6 7 -	\$ 1.327	9 6A	6A) 6A	\$ 166	\$ 388,422.80	\$ 5,296,803.32	\$ 2.223,190.0	A 4	л 6 л	4 196 961 00	A 6	A 6	A 4	• •n	\$ 5,232,394.90	\$ 65,915.00	\$ 1,597,729.00	\$ 155,833.00	60 -	69 6	\$ 1,142,100.00	\$ 22,130.00	\$ 779,779.00	\$ 263,505.66	\$ 56,097.92	\$ 526.097.92	\$ 1,884,480.00	\$ 1,887,325.00	\$ 1,785,410.00	\$ 2.568.760.00	\$ 143,341.00 • 024 048 00	\$ 1,348,352.60	\$ 387,715.17	\$ 1,422,777.00	\$ 169.054.00	\$ 130,853.00	\$ 948,744.00	\$ 208,194.00	\$ 4 433 499 00	\$ 1,422,422.00	\$ 804,553.44	\$ 648,732.00 \$ 716 771.76	\$ 220,627,35	\$ 401,734.50	\$ 722,723,35	\$ 1,949,626.83	\$ 60,380.80	\$ 699,440.00	\$ 268,268.00	\$ 1,294,784.00	\$ 396,435.92	8 866.304.45	5 /33,202.00	\$ 2,373,225.00	1,196,190.00	2.795,350.00	2,779,778,00	2,644,044.00	316,316.00	248,888.00	1,010,235.00	252,265.00	1 192 114.05
00 7725	00 1000			50 8710	T		76 709		15			1	1310	I			4404			0 10460	t	0		16400		4000				380		1324	T	672 CZZ		1000		0	⇒ +	3530	450	24877	11010	2425	3500	700	1220	0	7087	130	0	500	4925	3,265	2200	1340	0880	2000	0086	1860	18000	1160	4000	4 280	548	13467
373	7000	25	567	350	2000	2	5		572	983		4050		0	1000	140	25			•	400	0	0	510	100	300					67	0	•	200		2		•	0 0	135	209	2585	500	215	700	100	300	•	0	ω ω	0 12	138	325	0	Ì	200	t	1×		50	t		2000 1	5 0 Z	62	40 IN
Day	Day	Day	Day	Day	Day	Dav	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Dav	Day	Day	Day	Day	Day	Day	Day	day	Day	Day	Day	Day	day	Dav	Day/Night	÷	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day :	Day	Day	Day	Dav		Day	-			Day			Day 1	1	Day B	Day 3	-	AL DIBIN
50 Working Days	100 Working Day	60 Working Days	100 Working Days	30 Working Days	120 Working Days	often Busilo44 04	An Working Days		90 Calander Days	60 Working Days		300 CD	60 Working Days	30 Working Days	240 Working Days	22 Working Days	60 Working Days	on Working Days	an Windsing Dave	35 Working Days	of and building of	5 Working Days	30 Working Days	45 Working Days	30 Working Days	BUINIDAA DC					60 Working Days	435 Working Days	86 Working Days	90 Working Days	30 Calendar Days	40 Working Days	45 Working Days	40 Working Days	30 Working Days	40 Working Days	30 Working Days		30 Working Days	45 Working Days	60 Working Days	20 Working Days	40 Working Days	165 Calendar Days	30 Working Days	21 Working Days	10 Working Days	35 Working Days	20 Working Days	20 Working Days	30 Working Days	10 Working Days	110 Working Days	90 Working Days	00 Working Days			1			35 Working Days	
lim		Augustine			s Miguel		t	Jerry		t	t-		Kim	T	1	1		T	Jeny	Miduito	-1	Miquel	T	z		Auar	Jerry	Jeny	Jerry	Maurice	Kim		1		Kim	Edward	Maunce	Brian	Brian	Jeny	Kim	Maurice	Brian	Augustine	Miguel	Jerry		1		Gordon		Gordon			Gordon	Augustine	Augustine	Gordon	Jim	Maurice	Miguel	Kim	Miguel		Jin Yin	
+		-	Jemy	÷	-		John M	lome	-	Jim	-	ŀ	Rick	-	+	Rick	a John W	+	Jim	John M			Rick	Rick	Doug	Jorge	-lim	Jorge	Jorge	Art	Rick	Jim	0		Rick	Rick	Inhn W	Darren	Darren	Jorge	īā	John W	Jim	John M	Jim	Jorge	Jin	Rick	Rick	Rick	Rick	Rick	Jim	John W	John M	Rick	John W	Jim	John W	John W	Jim	Jeny	Jim	John M	Art	1
	M Denne	N GIO	t	GIO	t	U	< '		GIO			GIO		N GIO	T		N Gio		T	Deonne	- 1	010	ទ	Gio	0							Gio	Deonne	-		Gio					Dis la	Gio		Gio				Gio	Gio	Gio	<u>_</u>	Gio	Gio	Gio	Deonne	Gio	Gio	Gio	Dennie	Gio		00	Gio	Gio		

34552	34374	34268	34267	3425	34220	24200	34249	34437	34568	34195	34171	34562	34291	34216	34172	34465	34100	34347	34248	34200	34155	34141	34164	34134	34439	34614	34550	34481	34218	34116	34163	34074	34070	34065	34144	34119	34131	34024	34023	99007	34438	33981	33980	34344	34166	33967 33979	33969	33950	34175	39990	33938	34126	33992 33924	33956	33911	33975	33898	33868	34059	ACM COP	
2 2/1/2022	4 2/1/2022	ы	╞	H	+	1/15/2022			1/12/2022				1/6/2023	1/6/2022	12/28/202	12/21/2021	20201121	12/16/2021	12/16/202	12/15/2021	12/15/202	12/14/2021	12/10/2021	12/8/2021	12/7/2021	12/7/2021	12/2/2021	20202	12/2/2021	12/2/2021	12/2/2021	11/18/2021	11/18/2021	11/9/2021	10/29/2021	10/28/2021	10/22/2021	10/18/2021	10/18/2021	10/14/2021	10/14/2021	10/11/2021	10/11/2021	10/11/2021	10/7/2021	10/6/2021	10/5/2021	9/29/2021	9/28/2021	9/28/2021	9/24/2021	9/21/2021	9/21/2021	9/16/2021	9/15/2021	9/13/2021	9/13/2021	9/10/2021	9/8/2021		Date
22 Harbor Companies 22 City of Norco	0		2 City of Rancho Santa Margania	~		22 JM Construction inc				2 VLJM, LLC Partrane Fields FI Torp. LLC	1				21 City of Eastvale	Bea	_	A North Fortialla investment Compari-					1 City of Hunungton Beach the of Manhattan Beach		Wright Construction	City of Newport Beach	SRK Engineering		City of El Monte	1 Water District of	City of Long Beach	City of Long Beach		Casa Verdes Townhouse Homeow	Woods								City of Long Beach		Burbank-Glendale-Pasadena Airpo I Lennar Homes	City of Highland		Los Angeles Country Club		sa	City of Riverside 20		City of Long Beach G	Du Nesme				g Beach	Griffith Co. Ma	8 Z	Agency / Owner
08-1M0004 Dales Drive and Parkridge Avenue Street Improvement	Town Center Street Improvements for Community 1 acre	Macarthur Boulevard Resurfacing: Flower Street to Mail	Garney Business Improvements	Foothill Blvg Pavellelit Reliabilitation	Peny St. & Barrett Ave. Street Improvements - Penis	WD-08-22 Street Repair Services Contract No. 3659	Forence Ave Pavement Renaumany in Sector	Residential & Arterial Pavement Improvement	Eight Street Rehabilitation Project	District 2 Marine Way Street Improvements, City of Irvin	Penair Asphalt Main Parking Lot - Camp Pendelton	Coyote Canyon Road Street Improvements	Pacific Blvd., Santa Fe, & Vemon Ave Super Improvements	Pavement Rehab at Nine Locations	Local Streets Rehabilitation-CDBG FY 21-22	2021 Annual Asphalt Concrete Overlay Project (Pro	Palomar, McVicar and Grand Street Signing & Surphilig			Niguel Road (Alta Terra To Highlands Avenue) i around	Paving Repair at Mumeta Ko & Margania Ro-Municia	Local/Residential Street Rehab Phase 1 of Cycle 2	Slurry Seal Project Central Area of Sand Section	County of Riverside Transportation Kancho California Aveau and Annual Contract	Dunlap Bridge	Jamboree Road Pavement Rehabilitation and Reclaime	Loma Linda- California Street Widening	Industrial Streets (Phase 1) Water and Sewer Main	Bluff Top Parl Trail - HB	Skinner Facility Area Paving	Pine Ave., Aquarium Way, & Queens Way	Ramsey & Hathaway Improvements	Dist. 9 - 60th Street between Atlantic to Change Aver. 7-	Casa Verdes Pavement Rehabilitation	Metro Heights (Montebello Hills) - PHASE 1 AND 3 Stre	East Coast Highway and Marganice Account of Parkway	PA-3.2A Street Improvements	A AN Street Between Crienty And Construction-NASCAR Coliseum Paving pro	Woodruff Ave.B/T Palo Verde Ave & Conquista Ave.	Grand Ave. Beween 10th Street & 11th Street	Mckinley Grade Separation - Corona	Dist. 4 Resevior Dr.	Dist. 5 Monlaco Rd. to Veodului Ave. Nr. 1920 Dist. 5 Monlaco Rd. Clark to Tulaln Ave. R-7153	Dist. 5 Olser Ave. & Parkcreast St. R-7153	Tract 19787 - Grand Park Street, "A" Street, Archibaid / \$	Pavement Management Program	Corporate Yard Pavement Rehab	os Angeles Country Club Tennis Lot Asphalt Repair 5	ist. 5 All Streets R-7153	Randolph Avenue and St. Clair Street Industriation at 3	020/2021 SB-1 Street Maintenance Improvements \$	Adope Splings fraction of a structure of the structure of	Grand Prix Race Track R-7131-A	Street Improvements Project Bid No. #N2M21-2		Country Club and Monterey Et Al Grind, Overlay, ARAN &		South Street Marrio to East End R-7153	Main Street Interchange - Lake Elsinore \$		Project Title
69	\$ 224,500	un (m	\$ 4,189,151.00	\$ 135,693.00	\$ 1,689,439.00	\$ 200,000.00	6 9 -	69 4	\$ 7.077	2	\$	69	69 (÷ •	\$ 1,041,470.00	67	67	69	60	6 9 -	60 4 CO	\$ 63,000.00	\$ 673,275.00	\$ 608,710.44	\$ 1,049	\$ 0,900,000		\$ 610,838.90	\$ 395,374.00	\$ 897,024.16	\$ 1,936,977.00	\$ 413,710.75 * 65 184 00	\$ 238,577.90	\$ 717,651.58	\$ 2,675,250.00	\$ 172,969.00	\$ 1,244,244,00	\$ 530,910.00	\$ 457,508.00	\$ 226,312.76 \$ 105.274,45	\$ 3,055,667.90	\$ 1.089.897.00	\$ 821,623.37	\$ 823,807.10	\$ 2,218,218.00 \$ 438 789 40	\$ 2,090,000.00 \$ 1,197,129.65	612,755.00	5 208,141.00	45,000.00	2,828,000.00	4,/34,134.00	395,254.00	1,029,029.00	333,333.33	76,826.00	241,389.77	198,158.80		446,979.00 512,083.30	224,473.00	
	5	10 12000	ULEE 0		0 7890		0 1800			1	1400			45	24.700		T	T	13000	780	3375	150	51100	2523	5,200	150	5110 19950	5510	200	2810	11,150	2630 5	505	1334	9000 840	1300	18972	2680	695	262 197	2	12557	2333	4	9000 854	5644	52000 5299	15	940	14273	40	000	2100	1362 4	+		240	240	1995	921	
	298	2000	300	0000	240	400	0	220	190	100	800	5 63	900	•	1	360	600	4		0	220	0	918	- 10		0	700	• •	-	• 1	153	Jet	ŝ		0	9 0	662	800			+	0				++	100	H		÷	+	+	500		154 0	+	le	Dav	Day	n Dav	
	Night	Day	Day	Dav/Night	day	Day	Day	Day	Day	Day	Dav	Day	Day	Day	Day	Day	Day		Day	-	+	-		Day	ĝ	Day	Day	Day	Day	Day	Day .	Day	Day		Day	Day 1		Day	Day	Day	Day	-	Day	Day	-	. #	-		-			Day 14	-		Day 40	+	2	av	ay	Nite 300	
60 Working Days 21 Working Days	45 Working Day	140 Working Days	60 Working Day	20 Working Day	55 Working Day	45 Working Day	120 Calelinal pays	60 Working Day.	150 Working Day	4 Working Days	160 Working Day	10 Working Days	30 Working Days	45 Working Days	120 Working Days	45 Working Days	60 Working Days		365 Calendar Days	3/0 Working Lays	60 Working Days	25 Working Days	140 Working Days	45 Working Days	14 Days	100 Calendar Days	80 Working Days	75 Working Days		30 Working Days	140 Working Days				25 Working Days	60 Working Days	80 Working Days	75 Working Days				460 Working Days				g Days	45 Working Days	2	15 Working Days	_			120 Working Days		40 Working Days	-				300 Working Days	Mading Dave
ys Edward Kim		7				-		s Maurice		Þ			Kim		4.	-	Maurice		_	Miguel	W.	~			Jim	1		Maurice		Jim	T	TT	Gordon	- 1 -	-		Maurice		Maurice	Jeny	Jeny	Gordon	Jerry	Jerry	Jeny	Miquel	Augustine	Brian	Augustine	Jerry	Kim		Augustine	1	Kim	Jeny Augustine	Maurice	Јепу	Jerry	Gordon	Kim
rd Jeny John W	+-	al Jerry	t			t	Jorge		n John W	1			t	-	John W	-	John W	-		Jim	t	e John vv	+	Darren	Jorge	John W	Rick	A 1	2	Art	Jim VV	Jorge	W udor	Jonge	د		Rick	Rick	Art	Jorge	aûlor	Art	Jorge	abuor	Jorge	John W	Jim	Jenv	Jerry	Jorge	Doug	John W	John W	Jorge	Jim	лонде Лепу		Jorge		Art	
W Gio	Ē	Y	ł		Gio	t		Gio	-	+	+	Gio			1		N Glo	2				Gio	D	+	Deanne					ľ	G		Gio		Deonne		Gio		Gio							Decime	Gio	60	Gio			Gio	Gio								

34565 34600	34547	34510	345	34505	34503	34669	ccate	34524	34516	34480	34487	34486	34484	34483		34495		34657	34464	34462		34461	34532	-	34479	34430	34421	34736	34489	34490	34433	34410	34381	34379	34310	34377	34376	onete	34338	34337	34336	34335	34334	34460	34432	34431	34405	34124	34584	34375	34273	34292	34255	34250	Job No.# 34663	_
		41 - 5/5/2022	t		13 5/1/2022 14 5/1/2022	ł	t	4 4/21/2022		A 4/21/2022			4 4/20/2022		+	4/19/2022	4/14/2022			4/8/2022	1	4/8/2022	4/7/2022	4/5/2022	4/4/2022	4/1/2022	4/1/2022	3/30/2022	3/30/2022	3/24/2022	3/23/2022	3/15/2022	3/14/2022	3/14/2022 3/14/2022	011112022	3/14/2022	3/14/2022	3/10/2022	3/9/2022	22021116	3/7/2022	3/4/2022	3/4/2022	3/2/2022	3/2/2022	3/1/2022	3/1/2022	2/28/2022	2/25/2022	2/17/2022						
022 City of Rancho Santa Maruania 022 City of Aliso Vielo		22 City of Inglewood	1		22 City of Long Beach	<u> </u>	4	22 Ferreira Construction						2 City of Newport Beach City of Loon Reach Water		2 City of Stanton		1_				City of Long Beach	Moote Companies	Caltrans	City of Buena Park	City of Long Beach	City of Long Beach	City of Long Beach	RV Concrete	City of Santa Ana	Meritage Homes	I a Hahra Heights	City of Long Beach	City of Long Beach		City of Long Beach	City of Long Beach	Corner Keystone Const Corp.	City of Westlake Village	Moote Companies	Duke Realty	City of Long Beach	City of Long Beach	City of Long Beach	City of Sierra Madre	Euclid Land Venture, LLC	City of Paramount	City of Long Beach	City of Riverside	Wreck Age Demolition, Inc.	City of Torrance	VLJM, LLC		ation D	Ontario International Airport	A I Owner
	Automated People Movers (AFW), venues	FY 21-22 Street & Alley Improvements	E. San Antonio Drive b/t Long Beach Blvd. & Atlantic Ave. R-	Ath Street between Elm Avenue & Almitos Avenue R-7131A	E. Anaheim Street Atlantic Avenue and Alamitos Avenu E. Anaheim Street Atlantic Avenue and Alamitos Avenue	Anaheim Street between Oregon Avenue & Pacific Aven	Downtown Pavement Rehabilitation	Falloncrest Offsite Street Improvement CFD	Street Reliabilitation - Section - S	Mission Blvd, Pavement Reliab Floject 21-9271	WD08-22 Zone 5 (Orange) Del Amo to 7th/PCH, Redon	WD08-22 Zone 3 (Tellow) FOLL TO Water, Redond	WD08-22 Zone 2 (Green) 405 to PCH, w to Redould	WD08-22 Zone 1 (Red) N to 405 W to Lakewood	Craimer Lit Flugew	1.1	1	Orbis Real Estates/Toscana Squar Riverside UL and Minimum FY 2022-23	Bellflower boulevard between Ganoia Grow and Grow	Ximeno Avenue between 4th Street and Tour Street	Termino Avenue between 3rd Street and 4th Street R-7	New York Street between Atlantic Avenue & Lewis Cover	Palomino Ranch 1st and 2nd Street	Route 15, 215; 08-1M0504	2021-2022 Annual Slurry Seal Project	Wilson Street Improvement Project No. 22-01	Dist. 2 - S/S 11th Street B/T Orange Ave. & Gardenia A	Dist. 6 - 11th Street B/T M.L.K. Jr. Ave. & Orange - Petu	Crenshaw Blvd Rehabilitation	Local Street Preventative Maintenance 1	Sorenstam Drive Street Improvements - Beaumoni, CA	FY 2020-21 Street Improvement Project 1031522-	K1 Speed Race Track-Paving	Dist. 7 - 27th Street between Delta Ave. & Gale Ave.	Dist. 8 - Pacfic Ave, between Del Amo Blvd. & 52nd St	Dist. 8 - Atlantic Avenue between 45th Street and 46th	Dist. 8 - Locust Ave. between Silva St. & Mountain View	Fire Station 31-Seismic Retroll-Relocion on mini-	Westlake Village, FY 21-22 Project	Palomino Off-Site Improvements - Norco	Rider & Harvill Street Improvement - Perris	Dist, 1 - 16th Street Jerween - comments - Fontana	Dist. 8 - Country Club Dr. b/t San Anothio & Facilie Ave.	Dist. 7 - 37th Street b/l Country Club Dr. & Pacific Ave.	Market Street Corridor Improvement Project R-7177	Merrill Avenue Street Widening 2021-22 Street Improvement Project	Neighborhood St Improvement on Various City Streets	Atlantic Ave. between four a customer of Repair Asphalt Road 53 Area to San Mateo Rd	2	Demolition & Parking Lot Improv	te 39	AC Repairs Loop - and to		1-15 Interim Corridor Operations Project and Related Wi	Taxilane G scv 2021-2022 Slumy Seal Project	Project Title
\$ 1,302,773.03 \$ 985,312.00	• ••	ся е уп у	5 C	49	€ 9 €		. 4			69 -	60 60	44	69 6	A 4A	64	\$ 237,300.00	ł,	5,1	\$	64 4	A 4	n	69		a	\$ 1,061,160.00 \$ 484,908.05	69 4	sti \$ 900,000.00 , c 457.736.58	\$	49	59 (N	n 4	• 6 9	\$ 257,370.99	. 4		* **	44		\$ 1,025,336.20	\$ 585,850.00 \$ 2,399,483.11		\$ 467,176.91	20.669°C 5	\$ 7,394,311.00	\$ 584,442.00	\$ 915,915.00	\$ 1,926,760.00		\$ 115,511.00	\$ 4,044,788.00 \$ 65,351.00	\$ 65,725.00	\$ 1,659,760.00	1		135 633.25
TT	498,210.00 2513	Ì	T	ľ			I		100 100 500		12.00 12550	0.00	0.00	0.00	0.00	0.00 750	Ì	T	5.00 4000		2.62 47			Ť		00 2000	h	969 859 85	T	Ē		Ì	10 4112			5	- α ω		600	Ī	5500			3552	170	1620	4600	11600	30	220	21300	DUL	10200	7030	120	510
3000	3	127	146	25 3	(10	0	8	ō '	ļ			l		H						ŀ		_		~			5	+	UC8	0	400	800	40 0	_	t	7	t	+	0	8	006	150			1 TEL	1423	80	440	3	10	0 0	-	o 20		0 3	0 Day
200					ļ			560	- 1-	1180						0	+	>	2200		$\left \right $			0	o z	0			+	+	÷		-	Day	Day	2	Day	Day	Day	18 Day	+	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day	Day Night	Day
12		Day/Night 400 Working Days	5 98	Day	Day	Day	Day	-	Day 40 Working Days	Day & Nite		Day	Day	Day	Dav	_	Day 60 Working Days	Dav 45 Working	Day 45 Working Lays	+	Day	Day	Day	7500 80 Working Days	Night 60 Working Days	Day 30 Working Days	ហ្គ		Day 100 100 0	Night 90 Working Days	t	-	-	ty 15 Working Days	2 4	(Y Y		4 Working Days		Ľ	60 Working Days	-			240 Working Days	40 Working Days	40 Working Days	120 Working Day	21 Working Days	4 Working Days	80 Working Days	120 Calelidat Days	90 Working Days	30 Working Days 105 Working Days	-
Working Days 0 Working Das		ng Days	Working Days					g Days	g Days	e con) Days			1		-	1		Laya	5	1			Days	Days	Days	ays	+			lays	t	+		H				_		1		1		ti	1	1				AL	10-1		Jim		Brian
2		Jim	Bob	Jerry	Jeny	Jeny	Jerry	Gordon	Miguel	Gordor	Maurice	Kim	Kim	Kim	Kim	Kim	Jim	Jim	Gordon	Minuel	Jeny	Jerry	Auar	Miguel	Jim	Brian	Kim	Jerry	Jerry	Gordon		Miguel	Maurice	Maurice	Jerry	Jerry	Jerry	Jeny	Jerry			-	Miguel	Jerry	Jerry	Kim	Maurice	Maurice	Istine	Kim J	-	1		-	-	+
CIBL &		H	-	1.	Jorge	-		-	Jim	H		Jorge	Joine	ahor	Jorge		Rick	1	H	÷	entor	Jorge	abigo	John W		Rick	Doug	Jorge	Jorge	John M	Ad	John VV	Rick	John W	Jorge	Jorge	Jorge	Jorge	Jorge	Jim II	Jeny	John W	Jim	Jorge	Jorge	0	Jim	Rick	Jeny	Jorge	Jim ohn W	-	-	Јепу	-	Darren
D Gio	nen	\rightarrow	ug N/a	-+-	17	-	Deonne	-	+	H	0	e Deonne	-	e Deonne	+		Deonne	t	Gio	-	Deonne	-		Deonne		GIO	Deonne	1	I	Deonne		Gio	GIO							Gio	Deonne					Deonne	Gio	Gio	9 Gi		Gio	Deonne	Deonne	Gio	Gio	Deating

			71.00	4	\$ 126,107,057.68		Apparent Low Total			
			147,902.00	A 67	\$ 61,353,188.36		Month Total			
			-							
							New Valley Construction- 2022		9/27/2022	
Day	ç	P	ł	2760	\$ 633,145.00	.v. m	E. Riverside Drive & Hamner Avenue Street Improveme		9/15/2022	-
Day 130 Working Days	Q	4300		15000	\$ 11,097,080.00	1	HB Police Helipan Behab FY 26/27 and 30/31 - Local Streets	City of Huntington Beach	7/23/2022	TOVYC
	2 2	5		1120	393,120.00	Street Light & Lince Open	Phase A Street Traffic Signal, Street Light a ripping	City of Kivelaide	9/8/2022	
Day 30 Working Days		230		37000	22,378,378.00	Improvements Phase 2 - 6	2019-20 SB1 Maint & Traffic Improvements Phase 2 - 5	City of Long Beach	9/1/2022	34829
Day 130 Working Days		t		12865	4,311,788.00	Road b/t Pavo Ave. & Wi a	Dist. 4 Studebaker E. Service Road b/t Pavo Ave. & We	City of Long Beach	9/1/2022	34828
-	Da	ł		3388	1 740 855.64	De Forest Avenue & Jaym \$	Dist. 4 Kilroy Alipolit way	City of Long Beach	9/1/2022	34826
Day	Da			3470	751,689.42	tedondo Ave. & Spring St \$	Dist. 3 Appian Way bit Solicito Di. C & Spring St	City of Long Beach	2202/1/8	34825
Day	Da	-	+	1100	291,281.27	& Aimonu Ave. 15 7 153 \$	E. 4th Street bit Cerritos Ave. & Aimonu Ave. 17153	City of Long Beach	9/1/2022	34824
Dav			+	817	631,299.96	Street & 7th Street R-7131B S	Temple Avenue between 4th Street & 7th Street R-7131	City of Long Beach	9/1/2022	34823
Day			t	820	549,140.98	baker Road & Stevely AV S	Martine Road between Studebaker Road & Stevely Av	Skanska	9/1/2022	
Day	ay			160	2,000,000.00	Valley 5	Bond Job - Citymac - Moreno Valley	City of Moreno Valley	9/1/2022	
Day/Night 345 Working Days	Z		0	23838	4,000,002.14	14	6030 JUC Paying	County of Ventura	8/18/2022	
	Day	4	35	17717	2,000,000.00	\$	California Professional Engineering Citrus Ave at Chase Road Trains Signation	California Professional Engine	2202/07/1	
Day	Day.	+		179	223,258.00	1	Northeast Anaheim Colony (sabina) Nerginani Project	KB HUILIES	7/28/2022	34882
Dav	Dav	-	5 0	8000	1,146,000.00	_	Tract 20157 Street, Siging & Striping Light Introdemonent	City of Norco	7/27/2022	34742
+	Day	t	600	3000	1,069,069.00	ortions of Broken Feature	Shadow Canyon Sunset Ct & Portions of Broken Feature	City of Murrieta	7/20/2022	
Day 35 Working Days	Jay	20		2,390	624.145.00		Munieta Hot Springs Road	Riverside Construction	7/19/2022	74R00
Day/Night 75 Working Days	Nig		270	16000	403,721.00	- 69	Terracina Tract social Endine	KB Homes	7/14/2022	34729
-	¥	Day	•	3540	3,060,000.00	re Drive, Dryden Street (\$	Pavement Kenaumanum i in Pavement, Dryden Street	City of Temecula	200010111	34/33
	۲,	- L	1200	11000	3,629,219.00	1 1	2022 Arterial Roadway Project	City of Placentia	6/30/2022	34702
	ð.	D	590	30210	5,449,254.20		Pavement Rehabiliation Program - Misaucon	Could of Temerula	6/30/2022	34689
+		t	20	10000	4,302,151.55		Chino & Montclair Area Various Roads Overlay View/ Pato	Green Giarit Lanusca v	6/29/2022	
85 Working Days		Day	200	19,650	5,639,575.88	ab-Santa Fe Sprinks *	Little Lake Park Parking Lot Rehab-Santa Fe Spring	City of Mission Vielo	6/28/2022	34686
4 Working Days		U	•	1968	211,546.00		Asphalt Repairs and Asphalt Overlay Project	City of Long Beach	6/24/2022	34676
45 Working Days		Day	0	14100	0 542 229.00	Ļ	OC Church Lot Company Superior Pavement Markings	Golden State Paving		34677
		Day			20,834.00		Pacific Drive Element y Conductor	Golden State Paving	00100000	34648
1 Working Day		Day	0		26,605.00	Ð	MarchLife Street Renabilitation	March11LC		34724
1 Working Day		Day	0 10	4800	1,062,591.65	1416	Weir Canyon Road Rehabilitation ituiti South City	City of Anaheim	Į,	34636
40 Working Days		Dav	5	9233	2,305,993.90	Sus Locations	Parking Lot Improvement at Various Locations	Caltrans	1	34704
		Day	0	5,780	1,672,149.00		Route 710 07-0W0704	City of Monterey Park		34616
on Calander Days	-			15200	4,338,152.00	arious Locations	2021-22 Street Rehabilitation at Various Locations	Duke Realty		34637
Inn Working Days	-	Day	650	44368	7.294,219.00	Ļ	Oleandor & Slover Fontana	City of Huntington Beach		34524
an Working Days	-	Day	100	500	256.081.50	a G	Spilling Succi and -	City of San Juan Capistrano		34619
40 Working Da		Day	1856	16730	5.945,346.20	ADA Improvements + *	Spring Street and El Camino Real ADA Improvements	City of Compton		34799
160 Working Days		Day	33	231	270.925.00	1	Annual Residential Street Rehabilitation-Phase 28	City of Torrance		24666
an Calendar Days		Day	1012	22050	A 219.065.00	Carson St.	Wission Drop,	City of Pomona		34010
180 Working Days		Night	0	350	145.840.00	hiladelphia Street Re S	Residentian Story	City of Fullerton	1	34032
40 Working Davs		Day	523	14,400	A 119 411 00	1.1	Neighblinde Clarry Seal & Miscellaneous Rehabilitation F	City of La Mirada	1	34511
en Working Days		Day	282	138	704.080.00	9 64	Citywide Paventon Seal Area 3	City of Moreno Valley	22	D Nom
45 Working Days		Day		938	700 151 00	¹ rogram FY 2021-22 \$		Agency / Owner	Date	
150 Working Lays		Day	2,100	71.000			Project Title			



C. LIST OF COMPLETED PROJECTS - LAST THREE YEARS

[**Duplicate Page if needed for listing additional completed projects.**]

Please include only those projects which are similar enough to demonstrate Bidder's ability to perform the required Work.

Description of	Period of	Cost of Bidder's	Contact Name
Bidder's Work	Performance	Work	& Phone
"S	ee Attach	ed"	
	Bidder's Work	Bidder's Work Performance	

2021 <u>PAST WORK REFERENCES</u>

Colony Commerce C/O Caprock Partners 1300 Dove Street Suite 200 Newport Beach, CA 92660 Contact: Eric Nutter (949) 428-1400 Ext. 209 enutter@moote.com

à

Lennar Homes 25 Enterprise #300 Aliso Viejo, CA 92656 Contact: Diane Hannon (949)349-8000 Diane.hannon@lennar.com

City of Norco 2870 Clark Ave. Norco, AC 92860 Contact: Todd Shank (951) 270-5603 Todd.shank@norco.ca.us

Los Angeles Department of Water and Power 111 North Hope Street, L-43 Los Angeles, Ca 90012 Contact: Joelle Morisseau (213) 367-0123 Joelle.morisseau@LADWP.com

City of Dana Point 33282 Golden Lantern Dana Point, CA 92629 Contact: Scott Fisher (949) 248-3577 sfisher@DanaPoint.org

City of Corona 400 South Vicentia Corona, CA 92852 Contact: Barry Ghaemi (951) 736-2400 bghaemi@Coronaca.gov. Archibald St. Improvements Contract Amount: \$1,949,000.00 Start: 12/2019 Completed: 12/2021

Merrill & Haven Street Improvement Contract Amount: \$1,481,832.15 Start: 6/2020 Completed: 12/2021

Wayne Makin Park Slurry Seal Project Contract Amount: \$52,725.89 Start: 10/2021 Completed: 12/2021

Pine Tree Power Plant Access Road Repair Improvements Contract Amount: \$810,400.00 Start: 5/2021 Completed: 7/2021

Slurry Seal Project 19/20 Contract Amount: \$1,897,897.00 Start: 04/2020 Completed: 05/2021

Street Pavement Maintenance & Rehabilitation Project No. 2020.01 Contract Amount: \$3,471,178.00 Start: 6/2021 Completed: 1/2022

City of Anaheim 200 S. Anaheim Boulevard Anaheim, CA 92805 Contact: Jose Cortez (714) 765-5039 jcortez@anaheim.net

.

County of Orange 601 North Ross Street Santa Ana, CA 92701 Contact: Stephen Clayton (714) 995-0206 <u>Stephen.clayton@ocpw.ocgov.com</u>

City of Norwalk 12700 Norwalk Blvd. Norwalk, CA 90650 Glen W. C. Kau (562) 929-5723 gkau@norwalkca.gov

City of Garden Grove 11222 Acacia Pkwy Garden Grove, CA 92840 Navin Maru (714) 741-5180 <u>nmaru@ggcity.org</u> State College Boulevard Improvement from Ball Road to SR 91 Freeway Contract Amount: \$484,848.00 Start: 8/2021 Complete: 4/2022

Rossmoor Collectors Grind & Overlay Contract Amount: \$ 2,148,320.90 Start: 4/2021 Complete: 12/2021

Local Streets Rehabilitation Zone 27 East of Gard – No. 7925.3 Contract Amount: \$1,051,330.00 Start: 6/2021 Completed: 12/2021

Arterial STS. Rehabilitation Contract Amount: \$3,185,281.00 Start: 6/2022 Complete: 12/2021

City of Victorville 14343 Civic Drive Victorville CA. 92393 Contact: Bruce Miller 760-955-5085 bmiller@victorvilleca.gov Third Avenue Road Improvements Contract Amount: \$1,790,000.00 Start Date: 5/2020 End Date: 10/2020

Orange County Cemetery District 25751 Trabuco Rd. Lake Forest CA. 92630 Contact: Jim Mickartz 949-450-1088 <u>mickartzarch@gmail.com</u> El Toro Memorial Park Curb & Dr. Project Contract Amount: \$416,999.99 Start Date: 08/2020 End Date: 11/2020

City of Alhambra 111 S. 1st Street Alhambra, CA. 91801 Contact: Robert Bias 626-580-5000 rbias@cityofalhambra.org

City of Ontario 303 E. B Street Ontario, CA. 91764 Contact: Ariana Kern 909-395-2129 <u>akern@ontarioca.gov</u>

City of Loma Linda 25541 Barton Road Loma Linda, CA. 92354 Contact: T. Jarb Thaipejr 909-799-4400 <u>ithaipejar@lomalinda-ca.gov</u>

City of Jurupa Valley 8920 Limonite Avenue Jurupa Valley, CA. 92509 Contact: Chase Keys 951-332-6464 ckeys@jurupavalley.org 2020 HUD Street Improvements Project Contract Amount: \$300,433.00 Start Date: 06/2020 End Date: 10/2020

2020 Fall Pavement Rehabilitation Project Contract Amount: \$2,499,333.00 Start Date: 07/2020 End Date: 12/2020

Pavement Rehabilitation –Barton Road Contract Amount: \$768,677.00 Start Date: 04/2020 End Date: 12/2020

Granite Hill Drive Pavement Rehabilitation Contract Amount: \$999,777.00 Start Date: 04/2020 End Date: 10/2020

City of Camarillo 601 Carmen Drive Camarillo, CA 93010 Contact: Thang Tran (805) 388-5345 ttran@cityofcamarillo.org

County of Ventura 800 S. Victoria Avenue, #1600 Ventura, CA 93009 Contact: Matt Maechler (805) 477-1911 matthew.maechler@ventura.org

City of Westminster 8200 Westminster Boulevard Westminster, CA 92683 Contact: Theresa Tran (714) 548-3460 ttran@westminster.ca.gov

City of Newport Beach 100 Civic Center Drive Newport Beach, CA 92660 Contact: Patricia Kharazmi (949) 644-3344 pkharazmi@newportbeachca.gov

City of Huntington Beach 2000 Main Street Huntington Beach, CA 92648 Contact: Joe Fuentes (714) 536-5259 ifuentes@surfcity-hb.org

County of Orange 601 N. Ross Street, 4th Floor Santa Ana, CA 92701 Contact: Albert Rodriguez albert.rodriguez@ocpw.ocgov.com Earl Joseph Drive Paving Contract Amount: \$681,901.50 Start Date: 06/2020 End Date: 07/2020

Yerba Buena Rd. (South) Pavement Resurfacing Contract Amount: \$2,298,467.40 Start Date: 03/2020 End Date: 06/2020

Citywide Overlay Street Improvements Contract Amount: \$1,131,621 Start Date: 02/2020 End Date: 06/2020

Cameo Highlands Street Reconstruction Contract Amount: \$2,425,694.00 Start Date: 07/2020 End Time: 11/2020

Arterial Rehabilitation of Graham St, Slater Ave, Newland St and Atlanta Ave Contract Amount: \$5,181,955.00 Start Date: 05/2020 End Date: 11/2020

JOC Pavement Maintenance Contract Amount: \$2,584,747.69 Start Date: 07/2020 End Date: 08/2020

City of Orange 300 E. Chapman Avenue Orange, CA 92886 Contact: Martin Varona (714) 744-5563 <u>mvarona@cityoforange.org</u> Annuai Slurry Seal FY 19-20 Contract Amount: \$377,737.78 Start Date: 06/2020 End Date: 12/2020

City of Norco 2870 Clark Avenue Norco, CA 92860 Contact: Sam Nelson (951) 270-5607 <u>snelson@ci.norco.ca.us</u> FY 2019-2020 Slurry Seal Project Contract Amount: \$147,708.97 Start Date: 06/2020 End Date: 12/2020

City of Compton 205 S. Willowbrook Avenue Compton, CA 90220 Contact: Brittany Duhn (Z & K Consultants) bduhn@zandkconsultants.com

.

Annual Residential Street Rehab – Phase 1 Contract Amount: \$5,295,068.00 Start Date: 05/2020 End Date: 11/2020

City of Simi Valley 2929 Tapo Canyon Rd. Simi Valley, CA 93063 Contact: Sarah Sheshebor (805)583-6792 <u>sshesheb@simivalley.org</u>

County of Ventura 501 Poli Street Ventura, CA 93001 Contact: Christopher Solis (805) 654-2054 <u>chris.solis@ventura.org</u> Simi Valley Minor Street Rehabilitation Contract Amount: \$510,124.25 Start Date: 07/2019 End Date: 08/2019

Yerba Buena Area Resurfacing Project Contract Amount: \$3,919,808.95 Start Date: 06/2019 End Date: 12/2019

City of Stanton 7800 Katella Avenue Stanton, CA. 90680 Contact: Guillermo Perez (714) 890-4204 <u>gperez@ci.stanton.ca.us</u>

City of Compton 205 S. Willowbrook Avenue Compton, CA. 90220 Contact: John Strictland (310) 605-5505 jstrictland@comptoncity.org

City of San Clemente 910 Calle Negocio San Clemente, CA. 92673 Contact: Darra Koger (949) 361-3138 kogerD@san-clemente.org

City of South Gate 8650 California Avenue South Gate, CA. 90280 Contact: John Rico (323) 563-9594 irico@sogate.org 2019 Citywide Street Resurfacing Contract Amount: \$1,206,869.00 Start Date: 10/2019 End Date: 12/2019

Road Repair Service (Pothole Repair) Contract Amount: \$1,019,100.00 Start Date: 08/2019 End Date: 11/2019

Street Rehabilitation for S. Avenue LA Esperanza Contract Amount: \$384,055.00 Start Date: 09/2019 End Date: 10/2019

Circle Park Driveway Project Contract Amount: \$268,576.00 Start Date: 06/2019 End Date: 09/2019

Pardee Homes 1250 Corona Pointe Court, Ste. 600 Corona, CA. 92879 Contact: Nick Lasher (951) 428-4442 nick.lasher@pardeehomes.com

City of Fontana 8353 Sierra Avenue Fontana, CA. 92335 Contact: Kimberly Young (909) 350-7632 kyoung@fontana.org Railroad Canyon Widening Contract Amount: \$5,062,746.00 Start Date: 11/2018 End Time: 08/2019

Citrus Avenue Improvements Contract Amount: \$502,730.00 Start Date: 08/2018 End Date: 10/2019

DR Horton 2280 Wardlow Circle Ste. 100 Corona, CA. 92880 Contact: Keith Alex (951) 830-5872 kalex@drhorton.com

City of Ontario 2201 Dupont Dr. #300 Irvine, CA. 92612 Contact: Kavous Emami (909) 628-6234 Singlton Road Contract Amount: \$1,684,000.00 Start Date: 07/2018 End Date: 12/2019

Eucalyptus Street Improvements Contract Amount: \$1,580,580.00 Start Date: 3/2018 End Date: 10/2019

Irvine Community Development Company 550 Newport Center Dr. Ste. 550 B2 Newport Beach, CA. 92660 Contact: Mike Morse (949) 720-2560

City of Downey 11111 Brookshire Avenue Downey, CA. 90241 Contact: Desi Gutierrez, (562) 904-7110 dgutierr@downeyca.org Portola Springs PA-6 Enclave 5B Phase1, 2 Contract Amount: \$2,055,055.00 Start Date: 09/2018 End Date: 12/2019

FY 18/19 Slurry Seal Project Contract Amount: \$313,425.87 Start Date: 06/2019 End Date: 12/2019

City of Chino PO Box 667 Chino, CA. 91708 Contact: Dustin Postovoit (909) 334-3415 apostovoit@cityofchino.org

City of Lancaster 44933 Fern Avenue Lancaster, CA. 93534 Contact: Greg Wilson (661) 570-8003 gwilson@cityoflancasterca.org Slurry Seal Maintenance Work Contract Amount: \$372,805.00 Start Date: 1/2019 End Date: 12/2019

2018 Pavement Management Program Contract Amount: \$2,720,103.65 Start Date: 3/2019 End Date: 12/2019

City of Colton 650 N. La Cadena Dr. Colton, CA. 92324 Contact: Victor Ortiz (909) 370-5099 vortiz@coltonca.gov

City of Cathedral City 68700 Ave Lalo Guerrero Cathedral City, CA. 92234 Contact: John A. Corella (760) 770-0349 icorella@cathedralcity.gov

City of San Clemente 910 Calle Negocio San Clemente, CA. 92673 Contact: Gary Voborsky (949) 361-6132 voborskyg@san-clemente.org FY 18-19 Asphalt Paving Project Contract Amount: \$1,377,700.00 Start Date: 3/2019 End Date: 11/2019

Ortega Road Widening Contract Amount: \$459,998.00 Start Date: 2/2019 End Date: 12/2019

Arterial Street Pavement Maintenance Contract Amount: \$1,187,187.00 Start Date: 3/2019 End Date: 7/2019



D. EXPERIENCE AND TECHNICAL QUALIFICATIONS QUESTIONNAIRE

Personnel:

The Bidder shall identify the key personnel to be assigned to this project in a management, construction supervision or engineering capacity.

1. List each person's job title, name and percent of time to be allocated to this project:

Gordon Kline, Project Manager - 10%	
Jim Harnetiaux - Superintendent - 50%	
Art Ramirez - Paving Foreman - 100%	

2. Summarize each person's specialized education:

Agtec Pointman Training Asphalt Techology

3. List each person's years of construction experience relevant to the project:

14 years

38 years

36 years

4. Summarize such experience:

Construction Background in Various Public & Private Works Projects.

Bidder agrees that personnel named in this Bid will remain on this Project until completion of all relevant Work, unless substituted by personnel of equivalent experience and qualifications approved in advance by the City.

INFORMATION REQUIRED OF BIDDERS

Gordon Kline (951)453-4635

.

.

Work History	2014-Current	All American /	\sphalt	Corona, CA
	Project Manager, Esti			
		nerete and slurry opera		
	 Responsible for organ 	nizing personnel, equip	oment and materials for sl	urry projects.
	 Responsible for proje 	ct management		
	 Handled customer inc 	quiries and complaints.		
	2013-2014	Riverside Cons	truction	Riverside, CA
	Project Manager			
	 Handled all aspects of 	f current jobs		
	 Maintain relationship 	s with employees on al	ll levels	
	2011-2013	All American Aspha	ılı C	orona, CA
	PM/Superintendent		_	
	 Worked specifically c 	on largest contracts held	d by All American Aspha	1t
	•Managed multiple cor			
	2008-2011	ICE Engineering	Rowland I	leights, CA
	Owner/Estimator			ingino, cri
	 Estimated potential jo 	bs daily		
	•Maintain any and all o			
Education	1992-1996		Arlington High School,	Riverside CA
	 High School Diplon 	a	iningion right deliver,	Kivelane, CA
Additional Information				
	 Attended various educ 	ational classes relating	to the construction indus	stry
	•Works closely with all possible	employees to ensure t	he most productive and s	afe work environment

James Harnetiaux

Work History

.

2005-PresentAll American AsphaltCorona, CAArea Superintendent-•Responsible for all aspects of Construction activity (grading, concrete and paving) in area of Southern CA assigned. This includes:

- -Scheduling of all Construction Activity
- -Responsible for achieving production goals
- -Product Quality
- -Ordering of manpower, equipment and materials
- -Safety of company personnel
- -Communication with customers and agencies

1993-2005 All American Asphalt Corona, CA Concrete Superintendent

- •Responsible for all aspects of concrete construction for the company. This included:
- -Scheduling of concrete crews throughout Southern California
- -Implementation of new areas of work such as Rapid Set concrete construction on numerous Caltrans projects in Southern California
- -Quality control of the concrete work for the company
- -Crew Safety
- -Responsible for achieving production goals for the Concrete Division

1984-1993 All American Asphalt Corona, CA

Concrete Foreman

- •Responsible for the production of a 14-man concrete crew. This included:
- -Reading of plans and specs for correct and accurate placement of the product -Scheduling of material and manpower for the operation of curb machine and
- hand placement of product
- -Quality
- -Safety

Education

1971-1975

• High School Diploma

Mater Dei High School, Santa Ana, CA

P.O. Box 2229, Corona, CA 92878-2229

Art Ramirez

* 🐨

Work History

P	988-Present Paving Superintendent	All American Asphalt	Corona, CA
•	Managed daily operation	ons for paving.	
•	Responsible for proper	placement of asphalt materials.	
1	980 1988		
0	perating Engineer		
•	Responsible for daily n including paving mach	naintenance and operation of various hea ines.	vy machinery,
19	978-1980	Guy F. Atkinson	California
0	perating Engineer		California
•	Responsible for daily m including paving machi	naintenance and operation of various hear mes.	vy machinery,
19	76-1978	R.J. Noble	Orange, CA
0	perating Engineer		Orange, CA
•	Responsible for daily m including paving machi	aintenance and operation of various heav nes.	/y machinery,



Additional Bidder's Statements:

If the Bidder feels that there is additional information which has not been included in the questionnaire above, and which would contribute to the qualification review, it may add that information in a statement here or on an attached sheet, appropriately marked:

N/A

E. VERIFICATION AND EXECUTION

These Bid Forms shall be executed only by a duly authorized official of the Bidder: I declare under penalty of perjury under the laws of the State of California that the foregoing information is true and correct:

Name of Bidder	All American Asphalt	
Signature	\diamond	
Name and Title	Michael Farkas, Secretary	
Dated	9-30-2022	



Pennsylvania Avenue Widening CIP 2017-009

NON-COLLUSION AFFIDAVIT CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

Michael Farkas _____, being first duly sworn, deposes and says that he is Ι. of <u>All American Asphalt</u> the party making the attached bid; that the bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation; that the bid is genuine and not collusive or sham; that the bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that the bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract of anyone interested in the proposed contract; that all statements contained in the bid are true; and, further, that the bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid, and will not pay, any fee to any corporation, partnership, company association, organization, bid depository, or to any member or agent thereof to effectuate a collusive or sham bid.

I certify (or declare) under penalty of perjury under the laws of the State of California that the foregoing is true and correct.

Name of Bidder	All American Asphalt
Signature	
Name and Title	Michael Farkas, Secretary
Dated	9-30-2022

CALIFORNIA JURAT

.

GOV CODE § 8202

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California

County ofRiverside	Subscribed and sworn to (or affirmed) before me on this <u>30th</u> day of <u>September</u> , <u>2022,</u> Date
	By (1) Michael Farkas
B. ROYSTER Notary Public - California Riverside County Commission # 2260352	Name of Signer Proved to me on the basis of satisfactory evidence be the person who appeared before me (.) (,)
My Comm. Expires Oct 26, 2022	(and
	(2) Name of Signer
	Proved to me on the basis of satisfactory evidence
	be the person who appeared before me.)
Signa	ature blanster
Place Notary Seal Above	Signature of Notary Public
Though the information below is not required by law, it may valuable to person relying on the document and could preve fraudulent removal and reattachment of this form to another	y prove vent
Further Description of Any Attached Document	
Title or Type of Document <u>Non-Collusion Affidavit</u>	RIGHT THUMBPRINT OF SIGNER RIGHT THUMBPRINT OF SIGNER Top of thumb here Top of thumb here
Document Date: <u>9-30-2022</u> Number of Pages: <u>1</u>	_
Signer(s) Other Than Named Above: <u>None</u>	-



Pennsylvania Avenue Widening CIP 2017-009

BID BOND

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

The makers of this bond are,

All American Asphalt

as Principal, and

Fidelity and Deposit Company of Maryland

, as Surety

and are held and firmly bound unto the City of Beaumont, hereinafter called the City, in the penal sum of TEN PERCENT (10%) OF THE TOTAL BID PRICE of the Principal submitted to CITY for the work described below, for the payment of which sum in lawful money of the United States, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH that whereas the Principal has submitted the accompanying bid dated <u>October 3</u>, 2022, for

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

If the Principal does not withdraw its bid within the time specified in the Contract Documents; and if the Principal is awarded the Contract and provides all documents to the City as required by the Contract Documents; then this obligation shall be null and void. Otherwise, this bond will remain in full force and effect.

Surety, for value received, hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the Contract Documents shall in affect its obligation under this bond, and Surety does hereby waive notice of any such changes.

In the event a lawsuit is brought upon this bond by the City and judgment is recovered, the Surety shall pay all litigation expenses incurred by the City in such suit, including reasonable attorneys' fees, court costs, expert witness fees and expenses.



Pennsylvania Avenue Widening CIP 2017-009

IN WITNESS WHEREOF, the above-bound parties have executed this instrument under their several seals this <u>22nd</u> day of <u>September</u>, 20<u>22</u>, the name and corporate seal of each corporation.

(Corporate Seal)

(Corporate Seal)

All American Asphalt Principal By MICHHEL FARKAS SECLETARY

Title

Fidelity and Deposit Company of Maryland Surety

1000 By

Rebecca Haas-Bates

Attorney-in-Fact

(Attach Attorney-in-Fact Certificate)

Title Attorney-in-Fact

CALIFORNIA ALL-PURPOSE ACKNOWLEDGEMENT

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

County of Ri	verside	_											
On <u>September</u>	r 30, 2022	befo	re me,	B. Royster, Notary Here Insert name and Title of th	Public, ne Officer								
personally appeared			Mic Name(s	nael Farkas of Signer (d									
B. ROYST Notary Public - Riverside C Commission # My Comm. Expires	California County 2260352	who pers and his/ h sign of wl I cer Calif	who proved to me on the basis of satisfactory evidence to be person(s) whose name(s) is/are subscribed to the within instrum and acknowledged to me that he/she/they executed the same his/her/their authorized capacity(ies), and that by his/her/th signature(s) on the instrument the person(s), or the entity upon bel of which the person(s) acted, executed the instrument. I certify under PENALTY OF PERJURY under the laws of the State California that the forgoing paragraph is true and correct. WITNESS my hand and official seal.										
Place Notary Sea	I Above	Signa	Signature B. Advanture Signature of Notary Public										
				ay prove valuable to person rel									
		fraudulent remov		achment of this form to anothe									
Description of Attac	hed Docum	: fraudulent remov ent	al and reatt		r document.								
Description of Attac	ment	fraudulent remov ent Bid	Bond –	achment of this form to anothe	r document.								
Description of Attac Title or Type of Docur Document Date:	ment Septe:	fraudulent remov ent Bid mber 22, 202	Bond – 2	achment of this form to anothe	ar document.								
Description of Attac Title or Type of Docur Document Date: Signer(s) Other Than Capacity(ies) Claime	ment Septe Named Abo ed by Signer	r(s)	Bond – 2	Achment of this form to anothe <u>City of Beaumont</u> Number of Pages:	ar document.								
Description of Attac Title or Type of Docur Document Date: Signer(s) Other Than Capacity(ies) Claime Signer's Name:	ment Septe Named Abo ed by Signer	r(s)	Bond – 2	Achment of this form to anothe <u>City of Beaumont</u> Number of Pages:	ar document.								
Description of Attac Title or Type of Docur Document Date: Signer(s) Other Than Capacity(ies) Claime Signer's Name:	ment Septe Named Abo ed by Signer Michae	rfraudulent remov ent <u>Bid</u> mber 22, 202 ve: <u>Reb</u> r(s) el Farkas	Bond – 2 becca Ha	Achment of this form to anothe <u>City of Beaumont</u> <u>Number of Pages:</u> <u>as-Bates, Attorney-in-</u> Signer's Name: <u>Individual</u>	3 Fact								
Description of Attac Title or Type of Docur Document Date: Signer(s) Other Than Capacity(ies) Claime Signer's Name: Individual X Corporate Officer –	hed Documer mentSepte: Named Abor ed by Signer Michae - Title(s):	rfraudulent remov ent <u>Bid</u> mber 22, 202 ve: <u>Reb</u> r(s) el Farkas	Bond – 2 becca Ha	Achment of this form to anothe <u>City of Beaumont</u> Number of Pages: as-Bates, Attorney-in-] Signer's Name: □ Individual □ Corporate Officer — Title	3								
Description of Attac Title or Type of Docum Document Date: Signer(s) Other Than Capacity(ies) Claime Signer's Name: Individual X Corporate Officer – Partner II II Limited	hed Documer mentSepte: Named Abor ed by Signer Michae - Title(s):	rfraudulent remov ent <u>Bid</u> mber 22, 202 ve: <u>Reb</u> r(s) el Farkas	Bond – 2 Decca Ha	Achment of this form to anothe <u>City of Beaumont</u> Number of Pages: as-Bates, Attorney-in-] Signer's Name: □ Individual □ Corporate Officer — Title □ Partner □ □ Limited □ Ge	3								
Description of Attac Title or Type of Docur Document Date: Signer(s) Other Than Capacity(ies) Claime Signer's Name: Individual X Corporate Officer –	hed Documer mentSepte: Named Abor ed by Signer Michae - Title(s):	rfraudulent remov ent <u>Bid</u> mber 22, 202 ve: <u>Reb</u> ve: <u>Reb</u> r(s) el Farkas <u>Corp. Secreta</u>	Bond — 2 becca Ha	Achment of this form to anothe <u>City of Beaumont</u> Number of Pages: as-Bates, Attorney-in-] Signer's Name: Individual Corporate Officer — Title Partner □ □ Limited □ Ge Attorney in Fact	3 Fact eneral RIGHT THUMBPRIN								
Description of Attac Title or Type of Docur Document Date: Signer(s) Other Than Capacity(ies) Claime Signer's Name: Individual X Corporate Officer – Partner 🗆 Limited Attorney in Fact	hed Docum ment Septe: Named Abor ed by Signer Michae - Title(s): d □ General	rfraudulent remov ent <u>Bid</u> mber 22, 202 ve: <u>Reb</u> r(s) el Farkas <u>Corp. Secreta</u>	Bond — 2 becca Ha	Achment of this form to anothe <u>City of Beaumont</u> Number of Pages: as-Bates, Attorney-in-] Signer's Name: □ Individual □ Corporate Officer — Title □ Partner □ □ Limited □ Ge	3 Fact eneral RIGHT THUMBPRIN OF SIGNER								

٦

J



Pennsylvania Avenue Widening CIP 2017-009

STATE OF CAL	IFORNIA)	
) ss).
CITY OF)	
On this	day of	, in the year 2019, before me,
		, a Notary Public in and for said state, personally
appeared		, known to me to be the person
whose name is s	subscribed to t	he within instrument as the Attorney-In-Fact of the
(Surety) acknow	ledged to me t	that he subscribed the name of the
	_	(Surety) thereto and his own name as Attorney-In-
Fact.		

Notary Public in and for said State

(SEAL)

Commission	expires:	

NOTE: A copy of the Power-of-Attorney to local representatives of the bonding company must be attached hereto.

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT

A notary public or othe document to which this	r officer completing this certificate verifies only the identity of the individual who signed the certificate is attached, and not the truthfulness, accuracy, or validity of that document.
State of California)
County of Orange	
On09/22/2022	before me, L. Gomez, Notary Public
Date	Here Insert Name and Title of the Officer
personally appeared	Rebecca Haas-Bates
	Name(s) of Signer(s)

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(ies), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

> I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

Signature

K. Homer Signature of Notary Public

Place Notary Seal Above

L. GOMEZ Notary Public - California Orange County

Commission # 2413682

Wy Comm. Expires Aug 23, 2026

OPTIONAL -

Though this section is optional, completing this information can deter alteration of the document or fraudulent reattachment of this form to an unintended document.

Document Date:09/22/2022
Named Above: All American Asphalt
Signer's Name:
Corporate Officer - Title(s):
Partner — Limited General
Individual Attorney in Fact
Trustee Guardian or Conservator
Other:
Signer Is Representing:

©2014 National Notary Association · www.NationalNotary.org · 1-800-US NOTARY (1-800-876-6827) Item #5907

EXTRACT FROM BY-LAWS OF THE COMPANIES

"Article V, Section 8, <u>Attorneys-in-Fact</u>. The Chief Executive Officer, the President, or any Executive Vice President or Vice President may, by written instrument under the attested corporate seal, appoint attorneys-in-fact with authority to execute bonds, policies, recognizances, stipulations, undertakings, or other like instruments on behalf of the Company, and may authorize any officer or any such attorney-in-fact to affix the corporate seal thereto; and may with or without cause modify of revoke any such appointment or authority at any time."

CERTIFICATE

I, the undersigned, Secretary of the ZURICH AMERICAN INSURANCE COMPANY, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND, do hereby certify that the foregoing Power of Attorney is still in full force and effect on the date of this certificate; and I do further certify that Article V, Section 8, of the By-Laws of the Companies is still in force.

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the ZURICH AMERICAN INSURANCE COMPANY at a meeting duly called and held on the 15th day of December 1998.

RESOLVED: "That the signature of the President or a Vice President and the attesting signature of a Secretary or an Assistant Secretary and the Seal of the Company may be affixed by facsimile on any Power of Attorney...Any such Power or any certificate thereof bearing such facsimile signature and seal shall be valid and binding on the Company."

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at a meeting duly called and held on the 5th day of May, 1994, and the following resolution of the Board of Directors of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at a meeting duly called and held on the 10th day of May, 1990.

RESOLVED: "That the facsimile or mechanically reproduced seal of the company and facsimile or mechanically reproduced signature of any Vice-President, Secretary, or Assistant Secretary of the Company, whether made heretofore or hereafter, wherever appearing upon a certified copy of any power of attorney issued by the Company, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

IN TESTIMONY WHEREOF, I have hereunto subscribed my name and affixed the corporate seals of the said Companies, this 22nd day of September ______, 2022 _____.



Kun Hodged

Brian M. Hodges Vice President

By:

TO REPORT A CLAIM WITH REGARD TO A SURETY BOND, PLEASE SUBMIT A COMPLETE DESCRIPTION OF THE CLAIM INCLUDING THE PRINCIPAL ON THE BOND, THE BOND NUMBER, AND YOUR CONTACT INFORMATION TO:

Zurich Surety Claims 1299 Zurich Way Schaumburg, IL 60196-1056 www.reportsfclaims@zurichna.com 800-626-4577



Addendum No. 1 RFB 2017-009 Pennsylvania Avenue Widening Project

This addendum is for the purpose of adding, clarifying, or deleting certain information to the construction contract documents as follows:

Notice Inviting Bids

BID OPENING TIME has been changed from 1:15 pm to 11:15am as shown below. There are no other changes to the bid dates and times.

Bid Published: Bids Must Be Received By: Place Of Bid Receipt:

Questions In By: Bid Opening Date: Bid Opening Location: September 9, 2022 October 3, 2022 @ 11:00 A.M. 550 E. Sixth Street (City Hall) Beaumont, CA 92223 September 21, 2022 @ 11:00 A.M. October 3, 2022 @ 11:15 A.M. 550 E. Sixth Street (City Hall), Room 4 Beaumont, CA 92223

Bid Plans

Construction Note 87 on Sheet 14 in the Bid Plans shall be amended to read, "JACK AND BORE 42-INCH **RCP** CULVERT."

Plan Holders List

The current Access Report from Public Purchase will serve as the plan holders list and is attached to this addendum for the bidder's reference. Additional bidders not shown on this list may still access the bid documents on Public Purchase between now and when the bids are due.

Attachments

The following attachments are made a part of this addendum.

Plan Holders List



RFB 2017-009 Pennsylvania Avenue Widening Project

SPHA

Dated: September 28, 2022

By:

Dustin S. Christensen Principal Engineer Public Works

By:

Date Received by Bidder:

9-29-2022

(Bidder's Company Name) (Bidder's Signature) RETARY MIC (Type or Print Name)

Bidder shall include a signed copy of this Addendum No. 1 with the bid proposal.

End of Addendum No. 1

Access Report Agency Bid Number Bid Title

8 8

City of Beaumont (CA) 2017-009 (re-bid) Pennsylvania Avenue Widening (CIP 2017-009) (re-bid)

School Wholesale Supplies LL(2022-09-12 02:49 AM PDT 2022-09-12 02:49 AM PDT Construction Bidboard, Inc. 2022-09-12 09:11 AM PDT 2022-09-23 11:42 AM PDT ConstructConnect 2022-09-10 08:42 AM PDT 2022-09-27 09:11 AM PDT Wayne Enterprises 2022-09-26 07:26 AM PDT 2022-09-27 08:42 AM PDT Dodge Data & Analytics 2022-09-15 07:42 AM PDT 2022-09-23 09:45 AM PDT Dodge Data & Analytics 2022-09-15 07:42 AM PDT 2022-09-15 00:30 AM PDT Beador Construction Company 2022-09-15 07:42 AM PDT 2022-09-15 00:30 AM PDT CMD 2022-09-14 02:36 PM PDT 2022-09-14 00:36 AM PDT JMS 2022-09-14 07:50 PM PDT 2022-09-20 01:56 AM PDT Superior Pavement Markings 2022-09-11 05:54 AM PDT 2022-09-21 01:56 AM PDT Superior Pavement Markings 2022-09-11 05:54 AM PDT 2022-09-10 00:74 AM PDT BidClerk 2022-09-14 07:50 PM PDT 2022-09-14 09:07 AM PDT DVX PAVING COMPANY IN(2022-09-20 10:54 AM PDT 2022-09-21 01:56 AM PDT Radia Landscape, Inc. 2022-09-11 05:52 PM PDT 2022-09-21 01:59 AM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-21 09:25 AM PDT 2022-09-21 09:	Vendor Name	Accessed First Time	Most Recent Access
ConstructConnect 2022-09-15 07:56 AM PDT 2022-09-27 09:11 AM PDT Wayne Enterprises 2022-09-10 08:42 AM PDT 2022-09-27 08:42 AM PDT Crosstown Electrical & Data, In 2022-09-26 07:26 AM PDT 2022-09-27 07:44 AM PDT Dodge Data & Analytics 2022-09-15 07:26 AM PDT 2022-09-13 04:33 AM PDT Beador Construction Company 2022-09-15 07:42 AM PDT 2022-09-13 04:33 AM PDT CMD 2022-09-15 07:26 AM PDT 2022-09-13 04:33 AM PDT Paragon Partners Ltd. 2022-09-14 02:36 PM PDT 2022-09-14 02:43 PM PDT IMS 2022-09-14 07:50 PM PDT 2022-09-20 00:74 AM PDT Superior Pavement Markings 2022-09-10 10:54 AM PDT 2022-09-20 10:56 AM PDT DONYX PAVING COMPANY IN: 2022-09-20 10:54 AM PDT 2022-09-10 00:74 AM PDT 2022-09-10 00:74 AM PDT BidClerk 2022-09-11 05:52 PM PDT 2022-09-11 05:53 PM PDT 2022-09-11 05:53 PM PDT Beaumont-Cherry Valley Wate: 2022-09-13 12:47 AM PDT 2022-09-21 00:25 AM PDT 2022-09-21 00:25 AM PDT AGC Plan Room 2022-09-11 03:14 PM PDT 2022-09-21 00:25 AM PDT 2022-09-21 00:25 AM PDT Adge Data & Analytics 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT <td>School Wholesale Supplies LL</td> <td>.(2022-09-12 02:49 AM PDT</td> <td>2022-09-12 02:49 AM PDT</td>	School Wholesale Supplies LL	.(2022-09-12 02:49 AM PDT	2022-09-12 02:49 AM PDT
Wayne Enterprises 2022-09-10 08:42 AM PDT 2022-09-27 08:42 AM PDT Crosstown Electrical & Data, In 2022-09-26 07:26 AM PDT 2022-09-27 07:44 AM PDT 2022-09-23 09:45 AM PDT Dodge Data & Analytics 2022-09-12 04:13 AM PDT 2022-09-23 09:45 AM PDT 2022-09-23 09:45 AM PDT Beador Construction Company 2022-09-15 07:42 AM PDT 2022-09-23 09:45 AM PDT 2022-09-23 09:45 AM PDT CMD 2022-09-14 02:36 PM PDT 2022-09-15 07:42 AM PDT 2022-09-15 01:30 AM PDT Paragon Partners Ltd. 2022-09-14 02:36 PM PDT 2022-09-14 02:43 PM PDT 2022-09-14 09:07 AM PDT Superior Pavement Markings 2022-09-10 10:54 AM PDT 2022-09-10 0:59 AM PDT 2022-09-11 0:50 AM PDT Superior Pavement Markings 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT 2022-09-11 0:55 AM PDT Superior Pavement Markings 2022-09-19 04:21 PM PDT 2022-09-11 0:55 AM PDT 2022-09-11 0:55 AM PDT Beaumont-Cherry Valley Water 2022-09-19 04:21 PM PDT 2022-09-11 0:55 AM PDT 2022-09-12 0:25 AM PDT 2022-09-11 0:55 AM PDT Roddway Engineering & Const 2022-09-13 12:47 AM PDT 2022-09-21 0:55 AM PDT 2022-09-21 0:55 AM PDT 2022-09-21 0:55 AM PDT All American Asphalt	Construction Bidboard, Inc.	2022-09-12 09:11 AM PDT	2022-09-23 11:42 AM PDT
Crosstown Electrical & Data, In 2022-09-26 07:26 AM PDT 2022-09-27 07:44 AM PDT Dodge Data & Analytics 2022-09-12 04:13 AM PDT 2022-09-13 04:33 AM PDT Beador Construction Company 2022-09-15 07:42 AM PDT 2022-09-23 09:45 AM PDT CMD 2022-09-15 10:30 AM PDT 2022-09-14 02:36 PM PDT Paragon Partners Ltd. 2022-09-12 01:56 AM PDT 2022-09-14 02:36 PM PDT IMS 2022-09-14 07:50 PM PDT 2022-09-14 09:07 AM PDT Superior Pavement Markings 2022-09-14 07:50 PM PDT 2022-09-14 09:07 AM PDT ONYX PAVING COMPANY INI 2022-09-11 05:52 PM PDT 2022-09-11 05:53 PM PDT BidClerk 2022-09-13 10:13 AM PDT 2022-09-22 10:59 AM PDT Marina Landscape, Inc. 2022-09-13 10:13 AM PDT 2022-09-21 00:55 AM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-21 00:25 AM PDT 2022-09-21 00:25 AM PDT AGC Plan Room 2022-09-14 03:07 AM PDT 2022-09-21 00:25 AM PDT 2022-09-21 00:25 AM PDT Adge Data & Analytics 2022-09-14 03:02 PM PDT 2022-09-27 03:14 PM PDT 2022-09-21 00:25 AM PDT Climate Survival Solutions 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT 2022-09-26 07:	ConstructConnect	2022-09-15 07:56 AM PDT	2022-09-27 09:11 AM PDT
Dodge Data & Analytics 2022-09-12 04:13 AM PDT 2022-09-13 04:33 AM PDT Beador Construction Company 2022-09-15 07:42 AM PDT 2022-09-23 09:45 AM PDT CMD 2022-09-15 10:30 AM PDT 2022-09-14 02:36 PM PDT 2022-09-14 02:33 PM PDT Paragon Partners Ltd. 2022-09-14 02:36 PM PDT 2022-09-12 01:56 AM PDT 2022-09-20 01:56 AM PDT IMS 2022-09-14 07:50 PM PDT 2022-09-20 01:59 AM PDT 2022-09-20 01:59 AM PDT Superior Pavement Markings 2022-09-10 01:54 AM PDT 2022-09-10 01:59 AM PDT BidClerk 2022-09-11 05:52 PM PDT 2022-09-11 05:53 PM PDT Beaumont-Cherry Valley Water 2022-09-13 10:13 AM PDT 2022-09-20 10:55 AM PDT Addway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-21 01:56 PM PDT Addway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-21 01:56 PM PDT Add American Asphalt 2022-09-14 03:02 AM PDT 2022-09-21 09:25 AM PDT Add CPlan Room 2022-09-14 03:02 PM PDT 2022-09-20 10:55 AM PDT Climate Survival Solutions 2022-09-14 03:07 AM PDT 2022-09-20 03:14 PM PDT Climate Survival Solutions 2022-09-14 03:07 AM PDT 2022-09-20 03:14 P	Wayne Enterprises	2022-09-10 08:42 AM PDT	2022-09-27 08:42 AM PDT
Beador Construction Company 2022-09-15 07:42 AM PDT 2022-09-23 09:45 AM PDT CMD 2022-09-15 10:30 AM PDT 2022-09-15 10:30 AM PDT Paragon Partners Ltd. 2022-09-14 02:36 PM PDT 2022-09-14 02:43 PM PDT IMS 2022-09-14 07:50 PM PDT 2022-09-22 03:14 PM PDT Superior Pavement Markings 2022-09-14 07:50 PM PDT 2022-09-22 03:14 PM PDT ONYX PAVING COMPANY IN 2022-09-20 10:54 AM PDT 2022-09-14 09:07 AM PDT BidClerk 2022-09-11 05:52 PM PDT 2022-09-19 12:43 PM PDT Marina Landscape, Inc. 2022-09-13 10:13 AM PDT 2022-09-10 05:53 PM PDT Beaumont-Cherry Valley Wate 2022-09-13 10:13 AM PDT 2022-09-22 10:55 AM PDT Montauk 2022-09-13 12:47 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-27 04:25 PM PDT Dodge Data & Analytics 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Climate Survival Solutions 2022-09-14 03:02 PM PDT 2022-09-27 03:14 PM PDT AGC Plan Room 2022-09-14 03:02 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Vacce	Crosstown Electrical & Data, II	n 2022-09-26 07:26 AM PDT	2022-09-27 07:44 AM PDT
CMD 2022-09-15 10:30 AM PDT 2022-09-15 10:30 AM PDT Paragon Partners Ltd. 2022-09-14 02:36 PM PDT 2022-09-14 02:43 PM PDT IMS 2022-09-12 01:56 AM PDT 2022-09-22 03:14 PM PDT The Bid Lab 2022-09-14 07:50 PM PDT 2022-09-20 03:14 PM PDT Superior Pavement Markings 2022-09-14 09:02 AM PDT 2022-09-20 03:14 PM PDT ONYX PAVING COMPANY IN 2022-09-20 10:54 AM PDT 2022-09-11 05:53 PM PDT 2022-09-19 12:43 PM PDT BidClerk 2022-09-11 05:52 PM PDT 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT Marina Landscape, Inc. 2022-09-13 10:13 AM PDT 2022-09-20 10:55 PM PDT 2022-09-20 10:55 PM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-20 10:55 PM PDT 2022-09-21 09:25 AM PDT Montauk 2022-09-14 12:59 PM PDT 2022-09-21 09:25 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 03:07 AM PDT 2022-09-27 03:14 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT 2022-09-27 08:20 AM PDT Varce Corporation 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT 2022-09-27 08:20 AM PDT <td>Dodge Data & Analytics</td> <td>2022-09-12 04:13 AM PDT</td> <td>2022-09-13 04:33 AM PDT</td>	Dodge Data & Analytics	2022-09-12 04:13 AM PDT	2022-09-13 04:33 AM PDT
Paragon Partners Ltd. 2022-09-14 02:36 PM PDT 2022-09-14 02:43 PM PDT IMS 2022-09-12 01:56 AM PDT 2022-09-12 01:56 AM PDT The Bid Lab 2022-09-14 07:50 PM PDT 2022-09-22 03:14 PM PDT Superior Pavement Markings 2022-09-20 10:54 AM PDT 2022-09-20 01:59 AM PDT ONYX PAVING COMPANY IN(2022-09-20 10:54 AM PDT 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT BidClerk 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT Beaumont-Cherry Valley Water 2022-09-13 10:13 AM PDT 2022-09-20 10:55 AM PDT 2022-09-20 10:55 AM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-20 10:25 AM PDT 2022-09-21 09:25 AM PDT Montauk 2022-09-12 07:30 AM PDT 2022-09-21 09:25 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 03:07 AM PDT 2022-09-27 03:14 PM PDT 2022-09-27 03:14 PM PDT Dodge Data & Analytics 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT 2022-09-27 08:20 AM PDT Limate Survival Solutions 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT 2022-09-27 08:20 AM PDT Limate Survival Solutions 2022-09-15 04:29 PM PDT 202	Beador Construction Company	/ 2022-09-15 07:42 AM PDT	2022-09-23 09:45 AM PDT
IMS 2022-09-12 01:56 AM PDT 2022-09-12 01:56 AM PDT The Bid Lab 2022-09-14 07:50 PM PDT 2022-09-22 03:14 PM PDT Superior Pavement Markings 2022-09-14 09:02 AM PDT 2022-09-20 01:59 AM PDT ONYX PAVING COMPANY IN(2022-09-20 10:54 AM PDT 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT BidClerk 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT Marina Landscape, Inc. 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT 2022-09-20 10:55 AM PDT Beaumont-Cherry Valley Water 2022-09-13 10:13 AM PDT 2022-09-20 10:25 PM PDT 2022-09-21 09:25 AM PDT Montauk 2022-09-14 07:30 AM PDT 2022-09-21 09:25 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 03:02 PM PDT 2022-09-26 07:39 AM PDT 2022-09-26 07:49 AM PDT Dodge Data & Analytics 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT 2022-09-26 07:49 AM PDT Climate Survival Solutions 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT 2022-09-27 08:20 AM PDT Tukmol General Contractor 2022-09-14 03:07 AM PDT 2022-09-17 08:20 AM PDT 2022-09-17 08:20 AM PDT Vance Corporation	CMD	2022-09-15 10:30 AM PDT	2022-09-15 10:30 AM PDT
The Bid Lab 2022-09-14 07:50 PM PDT 2022-09-20 03:14 PM PDT Superior Pavement Markings 2022-09-14 09:02 AM PDT 2022-09-14 09:07 AM PDT ONYX PAVING COMPANY IN 2022-09-20 10:54 AM PDT 2022-09-14 09:07 AM PDT 2022-09-14 09:07 AM PDT BidClerk 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT Marina Landscape, Inc. 2022-09-11 05:52 PM PDT 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT Beaumont-Cherry Valley Water 2022-09-13 10:13 AM PDT 2022-09-20 10:59 AM PDT 2022-09-21 09:25 AM PDT Montauk 2022-09-13 12:47 AM PDT 2022-09-21 09:25 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-20 03:14 PM PDT 2022-09-27 03:14 PM PDT Dodge Data & Analytics 2022-09-11 06:52 AM PDT 2022-09-26 07:49 AM PDT 2022-09-26 07:49 AM PDT Limate Survival Solutions 2022-09-14 03:07 AM PDT 2022-09-27 08:20 AM PDT 2022-09-27 08:20 AM PDT Lardy and Harper, Inc 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT 2022-09-27 08:20 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-19 08:47 AM PDT 2022-09-15 08:51 AM PDT	Paragon Partners Ltd.	2022-09-14 02:36 PM PDT	2022-09-14 02:43 PM PDT
Superior Pavement Markings 2022-09-14 09:02 AM PDT 2022-09-14 09:07 AM PDT ONYX PAVING COMPANY IN(2022-09-20 10:54 AM PDT 2022-09-14 09:07 AM PDT BidClerk 2022-09-19 12:43 PM PDT 2022-09-20 10:59 AM PDT Marina Landscape, Inc. 2022-09-19 05:52 PM PDT 2022-09-19 05:53 PM PDT Beaumont-Cherry Valley Water 2022-09-19 04:21 PM PDT 2022-09-20 10:55 AM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-27 04:25 PM PDT 2022-09-20 10:55 AM PDT Montauk 2022-09-12 07:30 AM PDT 2022-09-21 09:25 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-11 06:52 AM PDT 2022-09-20 10:56 AM PDT 2022-09-20 10:25 AM PDT Dodge Data & Analytics 2022-09-11 06:52 AM PDT 2022-09-20 09:26 12:52 PM PDT Climate Survival Solutions 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT Vance Corporation 2022-09-19 08:47 AM PDT 2022-09-27 08:20 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-27 04:31 PM PDT	IMS	2022-09-12 01:56 AM PDT	2022-09-12 01:56 AM PDT
ONYX PAVING COMPANY IN(2022-09-20 10:54 AM PDT 2022-09-20 10:59 AM PDT BidClerk 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT Marina Landscape, Inc. 2022-09-11 05:52 PM PDT 2022-09-19 04:21 PM PDT Beaumont-Cherry Valley Water 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT Roadway Engineering & Const: 2022-09-13 10:13 AM PDT 2022-09-20 10:59 AM PDT 2022-09-19 04:21 PM PDT Montauk 2022-09-13 12:47 AM PDT 2022-09-20 04:25 PM PDT 2022-09-22 09:26 PM PDT AGC Plan Room 2022-09-14 07:30 AM PDT 2022-09-20 09:25 AM PDT 2022-09-27 03:14 PM PDT Dodge Data & Analytics 2022-09-14 03:02 PM PDT 2022-09-27 03:14 PM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT 2022-09-27 08:20 AM PDT Vance Corporation 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT 2022-09-27 04:31 PM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-27 04:31 PM PDT 2022-09-27 04:31 PM PDT Valace Corporation 2022-09-12 09:12 A	The Bid Lab	2022-09-14 07:50 PM PDT	2022-09-22 03:14 PM PDT
BidClerk 2022-09-19 12:43 PM PDT 2022-09-19 12:43 PM PDT Marina Landscape, Inc. 2022-09-11 05:52 PM PDT 2022-09-19 04:21 PM PDT Beaumont-Cherry Valley Water 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-27 04:25 PM PDT Montauk 2022-09-12 07:30 AM PDT 2022-09-22 11:06 PM PDT All American Asphalt 2022-09-14 12:59 PM PDT 2022-09-21 09:25 AM PDT Dodge Data & Analytics 2022-09-10 03:14 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Pavement Recycling Systems 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-27 04:31 PM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:	Superior Pavement Markings	2022-09-14 09:02 AM PDT	2022-09-14 09:07 AM PDT
Marina Landscape, Inc. 2022-09-11 05:52 PM PDT 2022-09-11 05:53 PM PDT Beaumont-Cherry Valley Water 2022-09-19 04:21 PM PDT 2022-09-11 05:53 PM PDT Roadway Engineering & Const: 2022-09-13 10:13 AM PDT 2022-09-27 04:25 PM PDT Montauk 2022-09-13 12:47 AM PDT 2022-09-22 11:06 PM PDT All American Asphalt 2022-09-14 12:59 PM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-27 03:14 PM PDT Dodge Data & Analytics 2022-09-11 06:52 AM PDT 2022-09-26 12:52 PM PDT Climate Survival Solutions 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-12 07:40 AM PDT 2022-09-14 03:07 AM PDT Pavement Recycling Systems 2022-09-12 07:40 AM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	ONYX PAVING COMPANY IN	(2022-09-20 10:54 AM PDT	2022-09-20 10:59 AM PDT
Beaumont-Cherry Valley Water 2022-09-19 04:21 PM PDT 2022-09-19 04:21 PM PDT Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-27 04:25 PM PDT Montauk 2022-09-13 12:47 AM PDT 2022-09-22 11:06 PM PDT All American Asphalt 2022-09-12 07:30 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-27 03:14 PM PDT Dodge Data & Analytics 2022-09-10 03:14 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-14 03:02 PM PDT 2022-09-26 12:52 PM PDT Hardy and Harper, Inc 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT Tukmol General Contractor 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Pavement Recycling Systems 2022-09-19 08:47 AM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	BidClerk	2022-09-19 12:43 PM PDT	2022-09-19 12:43 PM PDT
Roadway Engineering & Const 2022-09-13 10:13 AM PDT 2022-09-27 04:25 PM PDT Montauk 2022-09-13 12:47 AM PDT 2022-09-22 11:06 PM PDT All American Asphalt 2022-09-12 07:30 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-27 03:14 PM PDT Dodge Data & Analytics 2022-09-11 06:52 AM PDT 2022-09-26 12:52 PM PDT Climate Survival Solutions 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-14 03:07 AM PDT 2022-09-27 08:20 AM PDT Tukmol General Contractor 2022-09-19 08:47 AM PDT 2022-09-27 08:20 AM PDT Pavement Recycling Systems 2022-09-15 04:28 PM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-14 03:41 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Marina Landscape, Inc.	2022-09-11 05:52 PM PDT	2022-09-11 05:53 PM PDT
Montauk2022-09-13 12:47 AM PDT2022-09-22 11:06 PM PDTAll American Asphalt2022-09-12 07:30 AM PDT2022-09-21 09:25 AM PDTAGC Plan Room2022-09-14 12:59 PM PDT2022-09-21 09:25 AM PDTDodge Data & Analytics2022-09-10 03:14 PM PDT2022-09-27 03:14 PM PDTClimate Survival Solutions2022-09-11 06:52 AM PDT2022-09-26 12:52 PM PDTHardy and Harper, Inc2022-09-14 03:02 PM PDT2022-09-26 07:49 AM PDTTukmol General Contractor2022-09-12 07:40 AM PDT2022-09-27 08:20 AM PDTPavement Recycling Systems2022-09-12 07:40 AM PDT2022-09-19 08:47 AM PDTCalmex Engineering, Inc.2022-09-15 04:28 PM PDT2022-09-19 08:47 AM PDTVance Corporation2022-09-15 04:28 PM PDT2022-09-15 04:29 PM PDTMatich Corporation2022-09-14 10:41 AM PDT2022-09-15 08:54 AM PDTMatich Corporation2022-09-12 09:12 AM PDT2022-09-12 09:18 AM PDTVilla Landscape Products2022-09-22 10:58 AM PDT2022-09-22 10:58 AM PDT	Beaumont-Cherry Valley Wate	2022-09-19 04:21 PM PDT	2022-09-19 04:21 PM PDT
All American Asphalt 2022-09-12 07:30 AM PDT 2022-09-21 09:25 AM PDT AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-21 09:25 AM PDT Dodge Data & Analytics 2022-09-10 03:14 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-11 06:52 AM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Tukmol General Contractor 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Pavement Recycling Systems 2022-09-19 08:47 AM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT Vance Corporation 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Roadway Engineering & Const	2022-09-13 10:13 AM PDT	2022-09-27 04:25 PM PDT
AGC Plan Room 2022-09-14 12:59 PM PDT 2022-09-14 01:06 PM PDT Dodge Data & Analytics 2022-09-10 03:14 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-11 06:52 AM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Tukmol General Contractor 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Pavement Recycling Systems 2022-09-19 08:47 AM PDT 2022-09-27 08:20 AM PDT Calmex Engineering, Inc. 2022-09-15 04:28 PM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT MsL Electric, Inc 2022-09-14 10:41 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Montauk	2022-09-13 12:47 AM PDT	2022-09-22 11:06 PM PDT
Dodge Data & Analytics 2022-09-10 03:14 PM PDT 2022-09-27 03:14 PM PDT Climate Survival Solutions 2022-09-11 06:52 AM PDT 2022-09-26 07:49 AM PDT Hardy and Harper, Inc 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Tukmol General Contractor 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Pavement Recycling Systems 2022-09-19 08:47 AM PDT 2022-09-27 08:20 AM PDT Calmex Engineering, Inc. 2022-09-19 08:47 AM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT MSL Electric, Inc 2022-09-14 10:41 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	All American Asphalt	2022-09-12 07:30 AM PDT	2022-09-21 09:25 AM PDT
Climate Survival Solutions 2022-09-11 06:52 AM PDT 2022-09-26 12:52 PM PDT Hardy and Harper, Inc 2022-09-14 03:02 PM PDT 2022-09-26 07:49 AM PDT Tukmol General Contractor 2022-09-14 03:07 AM PDT 2022-09-26 07:49 AM PDT Pavement Recycling Systems 2022-09-12 07:40 AM PDT 2022-09-27 08:20 AM PDT Calmex Engineering, Inc. 2022-09-15 04:28 PM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT MSL Electric, Inc 2022-09-14 10:41 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	AGC Plan Room	2022-09-14 12:59 PM PDT	2022-09-14 01:06 PM PDT
Hardy and Harper, Inc2022-09-14 03:02 PM PDT2022-09-26 07:49 AM PDTTukmol General Contractor2022-09-14 03:07 AM PDT2022-09-14 03:07 AM PDTPavement Recycling Systems2022-09-12 07:40 AM PDT2022-09-27 08:20 AM PDTCalmex Engineering, Inc.2022-09-19 08:47 AM PDT2022-09-19 08:47 AM PDTVance Corporation2022-09-15 04:28 PM PDT2022-09-15 04:29 PM PDTMSL Electric, Inc2022-09-15 08:51 AM PDT2022-09-15 08:54 AM PDTMatich Corporation2022-09-14 10:41 AM PDT2022-09-27 04:31 PM PDTFALCON Engineering Services2022-09-12 09:12 AM PDT2022-09-12 09:18 AM PDTVilla Landscape Products2022-09-22 10:58 AM PDT2022-09-22 10:58 AM PDT	Dodge Data & Analytics	2022-09-10 03:14 PM PDT	2022-09-27 03:14 PM PDT
Tukmol General Contractor2022-09-14 03:07 AM PDT2022-09-14 03:07 AM PDTPavement Recycling Systems2022-09-12 07:40 AM PDT2022-09-27 08:20 AM PDTCalmex Engineering, Inc.2022-09-19 08:47 AM PDT2022-09-19 08:47 AM PDTVance Corporation2022-09-15 04:28 PM PDT2022-09-15 04:29 PM PDTMSL Electric, Inc2022-09-15 08:51 AM PDT2022-09-15 08:54 AM PDTMatich Corporation2022-09-14 10:41 AM PDT2022-09-27 04:31 PM PDTFALCON Engineering Services2022-09-12 09:12 AM PDT2022-09-12 09:18 AM PDTVilla Landscape Products2022-09-22 10:58 AM PDT2022-09-22 10:58 AM PDT	Climate Survival Solutions	2022-09-11 06:52 AM PDT	2022-09-26 12:52 PM PDT
Tukmol General Contractor2022-09-14 03:07 AM PDT2022-09-14 03:07 AM PDTPavement Recycling Systems2022-09-12 07:40 AM PDT2022-09-27 08:20 AM PDTCalmex Engineering, Inc.2022-09-19 08:47 AM PDT2022-09-19 08:47 AM PDTVance Corporation2022-09-15 04:28 PM PDT2022-09-15 04:29 PM PDTMSL Electric, Inc2022-09-15 08:51 AM PDT2022-09-15 08:54 AM PDTMatich Corporation2022-09-14 10:41 AM PDT2022-09-27 04:31 PM PDTFALCON Engineering Services2022-09-12 09:12 AM PDT2022-09-12 09:18 AM PDTVilla Landscape Products2022-09-22 10:58 AM PDT2022-09-22 10:58 AM PDT	Hardy and Harper, Inc	2022-09-14 03:02 PM PDT	2022-09-26 07:49 AM PDT
Calmex Engineering, Inc. 2022-09-19 08:47 AM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT MSL Electric, Inc 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-14 10:41 AM PDT 2022-09-27 04:31 PM PDT FALCON Engineering Services 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT		2022-09-14 03:07 AM PDT	2022-09-14 03:07 AM PDT
Calmex Engineering, Inc. 2022-09-19 08:47 AM PDT 2022-09-19 08:47 AM PDT Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT MSL Electric, Inc 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-14 10:41 AM PDT 2022-09-27 04:31 PM PDT FALCON Engineering Services 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Pavement Recycling Systems	2022-09-12 07:40 AM PDT	2022-09-27 08:20 AM PDT
Vance Corporation 2022-09-15 04:28 PM PDT 2022-09-15 04:29 PM PDT MSL Electric, Inc 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-14 10:41 AM PDT 2022-09-27 04:31 PM PDT FALCON Engineering Services 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Calmex Engineering, Inc.	2022-09-19 08:47 AM PDT	2022-09-19 08:47 AM PDT
MSL Electric, Inc 2022-09-15 08:51 AM PDT 2022-09-15 08:54 AM PDT Matich Corporation 2022-09-14 10:41 AM PDT 2022-09-27 04:31 PM PDT FALCON Engineering Services 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Vance Corporation	2022-09-15 04:28 PM PDT	
Matich Corporation 2022-09-14 10:41 AM PDT 2022-09-27 04:31 PM PDT FALCON Engineering Services 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT 2022-09-22 10:58 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	MSL Electric, Inc	2022-09-15 08:51 AM PDT	
FALCON Engineering Services 2022-09-12 09:12 AM PDT 2022-09-12 09:18 AM PDT Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	Matich Corporation	2022-09-14 10:41 AM PDT	
Villa Landscape Products 2022-09-22 10:58 AM PDT 2022-09-22 10:58 AM PDT	•		

27286 7/1/2016 City of Inglewood Century Bix4. Mobily Ingrovement Project 2746 7/1/2016 Fired Name Elydan Reservic Improvement Project 2746 7/1/2016 Fired Name Elydan Reservic Improvement Project 27452 1/1/2016 Fired Name Elydan Reservic Improvement Project 27452 1/1/2016 Fired Name Anton Parkway from Barrance to Technology 27453 1/1/2016 Fired Name District 4 Ane 3 A Pusan 28407 1/2/2016 Fired Name District 4 Ane 3 A Pusan 28437 6/1/2016 Perform District 4 Ane 3 A Pusan 28437 6/1/2016 Centration Termsocial Carry Bit 4 El Hermano-Corona 28437 0/1/2016 Centration Termsocial Carry Bit 4 El Hermano-Corona 28437 0/1/2/2016 City 6 Nowaki Termsocial Carry Bit 4 El Hermano-Corona 28449 1/1/2/2016 City 6 Nowaki Termsocial Carry Bit 4 El Hermano-Corona 28459 1/1/2/2/16 Cotty 6 Nowaki Termsocial Carry Bit 4 El Hermano-Corona 28459 1/1/2/2/16 Cotty 6 Nowaki	Bid Amount	Date Agency / Owner Project Title		Concrete Day/Nigh	Contract Time	Р. М.	Supt	Coor Completed	Dirt Removal	Concrete Removal Grin	dings Cont. Rec.	Date of Letter	Sent Back	Via	
2216 7/15/2015 City of nature Explain Reservoir Improvements Project 2316 9/15/2015 City of nature Industry Explaines Conter Reservoir Improvements Project 2316 9/15/2015 City of nature Industry Explaines Conter Reservoir Improvements 2317 1/12/2016 Five Point Communities Alton Parkwy from Barrance to Technology 2318 9/12/2016 City of Communities Diaring 4 Area 3 & Pursan 2318 9/12/2016 City of Communities Diaring 4 Area 3 & Pursan 2333 9/12/2016 City of Communities Burnan Brow Fisher Barbare 2333 9/12/2016 City of Communities Burnan Brow Fisher Barbare 2333 9/12/2016 City of Communities Burnan Brow Fisher Barbare 2333 9/12/2016 City of Communities Burnan Brow Fisher Barbare 2333 9/12/2016 City and Park Fisher Pursan 2333 9/12/2016 City and Park Fisher Pursan 2333 9/12/2016 City and Park Fisher Pursan 2333 9/12/2016 City and Park Fisher	\$ 9,333,052.8 \$ 18,118,000.0	12/5/2013 County of Orange/Sukut La Pata Gap Closure 7/1/2015 City of Indewood Century Blvd, Mobility Improvement Project	117,000	12,142 Day & Nite	2 Years 400 Working	Brett Ron	Art Jim	99.0% 99.0%			5/22/2014 8/4/2015		8/5/2015		
2781 10/15/2016 Akinson 07.1193/J4, Route 10 27832 11/2016 Fire Point Communities Ridge Valley & Cafeno 27946 21/2016 Fire Point Communities Data Grap 2 27946 21/2016 Fire Point Communities Disreyway - Anahoim 28114 4/202016 Fire Point Communities Disreyway - Anahoim 28119 71/2016 Chain Organization Tr. 1593/1933/19453/19454/1946 28119 91/2016 Chain Organization Tr. 2593/1933/19454/1946 28119 91/2016 Contranto Europain Biord Computer Street Company Action Contractor 28131 01/2016 Los Angeles Tre 1593/1933/19454/1946 28141 101/2016 St. Ontario Park Flace II 28142 101/2016 St. Ontario Park Flace II 28143 101/2016 Foremost Companies Terramor Intad 28144 101/2017 Fore Point Communities Bartano Intad 28145 11/2017 Fore Point Communities Bartano Intad 28146 11/2017 F	\$ 712,675.0	7/15/2015 Hardy & Harper Elysian Rreservoir Improvements Project	0	0 Day		Cody	Randy	99.0%							
2782 1/1/2016 Five Point Communities Altop Parway from Barrana to Technology 2783 2/20205 Five Point Communities Altop Parway from Barrana to Technology 2784 2/20205 Five Point Communities Disrice Yarway from Barrana to Technology 2814 5/20205 Five Point Communities Disrice Yarway from Barrana to Technology 2815 Five Point Communities W Fi C Project Figurera Cordor StreetScape Improvements 2813 9/12/2015 Lex Angeles Burbanne Bivd S Higwara Control StreetScape Improvements 2813 9/12/2016 Foremosi Companies Ternescal Campon R4 & El Herman - Corona 2813 9/12/2016 Calk Angeles Burbanne Bivd S Higwara Tom Studebaker R 2814 1/12/2016 Ciku Construction Olind Alpha Landill 2815 1/12/2016 Ciku Construction Olind Alpha Landill 2816 1/12/2016 Ciku Construction Olind Alpha Landill 2817 1/12/2016 Ciku Construction Olind Alpha Landill 2818 1/12/2016 Ciku Construction Olind Alpha Landill 2819 1	\$ 18,784,000.0		9,410	14,059 Day	250 Working	Ron	Jim	99.0%			9/15/2015		9/22/2015		
2765 1/4/2016 Five Point Communities D4 Gong 2 2744 3/102016 Chinn Devicement Cerp. Tr. 1440 Since Lington 2844 3/102016 Chinn Devicement Cerp. Tr. 1440 Since Lington 2845 Since Lington District A Area 3 & Presson District A Area 3 & Presson 2845 Firl 2016 Chin O Ensave Devicement Tr. 1840 Since Lington 2845 Firl 2016 Chin O Ensave Devicement Tr. 1840 Since Lington 2845 Firl 2016 Chin O Ensave Devicement Tr. 1840 Since Lington 2845 Firl 2016 Chin Chin O Ensave Devicement Cerp Park Fills I Lington Control Cerp Park Fills I Lington 2845 Firl 2016 Chin Chin Cerp Park Fills I Lington Control Cerp Park Fills I Lington 2845 Firl 2016 Crist O Finlance Firl 2016 Crist O Firl 2016 2845 Firl 2016 Crist O Finlance Firl 2016 Contart Hills No Since Lington Finlance 2845 Firl 2017 Corp Contart Hills No Since Lington Finlance Firl 2017 2846 Firl 2017 Firl 2016 Corp Contart Hills No Since Lington	\$ 9,349,470.1 \$ 779,916.0		135,000 4,585	0 Night 650 Day	5 Years 50	8rett Michele	Art Rick	80.0% 99.0%						-	-
2946 3/10/2016 Chino Development Corp. Tr. 16480 Street Improvements 2011 4/25/2016 First Point Communities District 4 Area 3 & Pusian 2019 First Point Communities District 4 Area 3 & Pusian 2019 First Point Communities Burbans Rev 3 Hayvenhurst 2019 First Point Companies Burbans Rev 3 Hayvenhurst 2011 Foremosi Companies Terrescal Campon Rd & El Hermano - Corona 2011 Foremosi Companies Terrescal Campon Rd & El Hermano - Corona 2011 Foremosi Companies Terrescal Campon Rd & El Hermano - Corona 2011 Foremosi Companies Terrescal Campon Rd & El Hermano - Corona 2011 Foremosi Companies Terrescal Campon Rd & El Hermano - Corona 2011 Foremosi Companies Terrescal Campon Rd & El Hermano - Corona 2012 Foremosi Companies Olicida Alpha Landini 2013 Foremosi Communities Olicida Alpha Landini 2014 Foremosi Communities Olicida Alpha Landini 2014 Foremosi Communities Orchard Hillin No Sincet Improvements 2014 Foremosi Communi	\$ 2,414,828.1	1/4/2016 Five Point Communites Alton Parkway from Barranca to Technology	6,000	1,000 Day	120	Michele	Rick	99,0%							
3/25/2016 Filalion Disneyway - Anaheim 2817 4/25/2016 Fila Point Communities Disneyway - Anaheim 2818 5/11/2016 Chy of Los Angeles My FIG Project-Filjuaria 2000 2818 5/12/2016 Powel Constructions Ter SMAGHA Rode 5 28287 9/12/2016 Los Angeles Burbank Bivd A May Chail Constructions 28287 9/12/2016 Chailamic Group Herninge Lak Dr A Mocal Bivd - Monifee 28391 10/12/2016 Chailamic Group Herninge Lak Bord A Mocal Bivd - Monifee 28491 10/12/2016 Chick Alpha Lambia Corchard Hills Backbone 28491 10/12/2016 Chick Alpha Lambia Olinda Alpha Lambia 28492 11/12/2017 ICDC Orchard Hills N3 Street Improvements 28493 11/12/2017 ICDC Orchard Hills N3 Street Improvements 28494 11/12/2017 ICDC Orchard Hills N3 Street Improvements 28495 11/12/2017 ICDC Orchard Hills N3 Street Improvements 28496 11/12/2017 ICDC Orchard Hills N3 Street Improvements <t< td=""><td>\$ 1,378,087.0 \$ 1,646,289.0</td><td></td><td>6,500 4,000</td><td>500 Day 1,000 Day</td><td>60 Days 90 Working</td><td>Michele Miguel</td><td>Rick Jerry</td><td>99.0% 99.0%</td><td></td><td></td><td></td><td>1</td><td></td><td>_</td><td>_</td></t<>	\$ 1,378,087.0 \$ 1,646,289.0		6,500 4,000	500 Day 1,000 Day	60 Days 90 Working	Michele Miguel	Rick Jerry	99.0% 99.0%				1		_	_
2017 4/25/2018 Five Point Communities My Fiel Project-Figurea Condror Streetscape Improver, 7: 1953/01930/14340 2333 9/14/2018 China Pressrue Development Tr. 1953/01933/014340 2333 9/14/2018 Foremost Companies Euroant Bior S Hayonnard A E H Herman - Corona 2333 9/14/2018 Foremost Companies Fernescal Canyon Rd & EH Herman - Corona 2344 10/12/016 SL Ontario Park Flace II 2345 9/14/2018 SL Ontario Park Flace II 2345 9/14/2018 SL Ontario Ontario Hill B Bickborn 2345 10/12/016 SL Ontario Ontario Hill Bickborn 2346 11/12/2017 Cold Construction Ontario Hill Bickborn 2343 11/12/2017 COC Orchard Hill SN Street Improvements 23440 11/12/2017 ICDC Orchard Hill SN Street Improvements 23451 11/12/2017 ICDC Orchard Hill SN Street Improvements 23452 11/12/2017 ICDC Orchard Hill SN Street Improvements 23453 12/22/201 Cuty F Aktinson 07/252/62/A A	\$ 1,646,289.0		3,650	Day Day	2 years	Brett	Rick	99.0%						-	
28199 77/12018 Chino Preserve Development Tr. 19838/19837/98237/98237/8480 28371 69/2016 Los Angeles Burbank Bird A Hayrow 14 hard 28331 69/120216 Los Angeles Burbank Bird A Hayrow 14 hard 28445 10/12016 EL Ontano Park Flince II Burbank Bird A Hayrow 14 hard 28457 10/122016 City of Norvak Rehabiliation of Alondra Boulevoard from Studebaker Richt 28458 10/122016 City of Norvak Rehabiliation of Alondra Boulevoard from Studebaker Richt 28459 10/122016 City of Norvak Rehabiliation of Alondra Boulevoard from Studebaker Richt 28451 11/122016 City of Norvak Rehabiliation of Alondra Boulevoard 28451 11/122017 City of Cong Orchard Hills NS Street Improvements 28452 11/12017 Flore Data Companies Barrance from Alon to Marine Way 28453 11/12017 City of Long Beach Annual Street Improvements 28454 61/12017 City of Long Beach Annual Street Improvements 28456 61/12017 Lives Operating Merinis Alondra Street Improve	\$ 1,192,000.0	1/25/2016 Five Point Communites District 4 Area 3 & Pusan	7,000	1,200 Day	75 Days	Michele	Rick	99.0%							
28/11 8/0/2016 Powell Constructors 12/0/M496 Route 5 28/33 9/14/2018 Foremost Companies Termescal Canyon Rd & El Hermano - Corona 28/31 9/14/2018 Calatanico Croup Harringic Lakes Dr A Mocal Blod - Menifee 28/31 9/14/2018 Calatanico Croup Harringic Lakes Dr A Mocal Blod - Menifee 28/31 10/12/2016 City of Nowak Rehabilitation of Alondra Budeward from Studebaker R: 28/32 11/12/2016 City of Nowak Rehabilitation of Alondra Budeward from Studebaker R: 28/32 11/12/2016 City of Nowak Contand Hile N3 Street Improvements 28/33 11/12/2017 ICDC Orchard Hile N3 Street Improvements 28/34 11/2/2017 ICDC Orchard Hile N3 Street Improvements 28/34 12/2/2017 Lows Operating Trains Are Arking La Improvements 28/34 <t< td=""><td>ver \$ 11,806,000.0 \$ 831,551.4</td><td></td><td>3,671 2,500</td><td>1,542 Day 600 Day</td><td>200 Working 8 DayP</td><td>Gordon Miguel</td><td>Doug Jerry</td><td>99.0% 99.0%</td><td></td><td></td><td>8/4/2016</td><td></td><td>8/10/2016</td><td></td><td>_</td></t<>	ver \$ 11,806,000.0 \$ 831,551.4		3,671 2,500	1,542 Day 600 Day	200 Working 8 DayP	Gordon Miguel	Doug Jerry	99.0% 99.0%			8/4/2016		8/10/2016		_
22227 9/14/2018 Foremost Companies Termescal Canyon Rd & El Hermano - Corona 22434 9/14/2018 Califanic Group Hernikage Lakes DF Mocali Bird - Moralife 22445 10/12/2016 Cirk of Norwak Rehabiliation of Alcondra Boulevand from Studebaker Ri 22439 11/12/2016 Cirk of Norwak Rehabiliation of Alcondra Boulevand from Studebaker Ri 22338 11/12/2016 Cirk of Norwak Rehabiliation of Alcondra Boulevand from Studebaker Ri 22338 11/12/2017 Filter Origit Companies Barranze from Alcon to Marine Way 22344 11/12/2017 Filter Origit Companies Barranze from Alcon to Marine Way 22345 11/12/2017 Filter Origit Companies Orchard Hills N3 Street Improvements 22346 11/19/2017 ICDC Orchard Hills N3 Street Improvements 22345 222/2017 Guy F. Alkinem OrziSSC44 Rouls Reinsance A Lindon Street Improvements 23456 41/12/2017 Leve -Hillwood Renissance A Lindon Street Improvements Resis and Alfania 23456 71/12/2017 Evel of Orchard Hills N3 Street Improvements Remissance A Lindon Street Improvements	\$ 343,872.5		4,440	0 Day/Night	325 Working Days	Brett	Art	99.0%							-
2333 0/14/2018 Calatantic Croup Heritage Lakes Dr & Mocall Bud - Menifee 24465 10/12/2018 Current Park Place II 23457 10/12/2018 Current Park Place II 23459 11/02/2018 Current Current 23459 11/02/2016 Foremost Companies Termore Infract 23450 11/02/2017 Five Point Communities Barrance from Alton to Marine Way 23451 11/02/2017 Five Point Communities Barrance from Alton to Marine Way 23452 11/02/2017 Five Point Communities Barrance from Alton to Marine Way 23452 11/02/2017 Five Point Communities Barrance from Alton to Marine Way 23452 11/02/2017 Five Point Communities Orchard Hills N3 Street Improvements 23456 11/02/2017 Five Point Communities Orchard Hills N3 Street Improvements 23456 11/02/2017 Cip Co Communities Orchard Hills N3 Street Improvements 23456 11/02/2017 Cip of Costa Mesa Terwinke Park Parking Lot Improvements 23456 11/02/2017 Lewis Op	\$ 1,397,636.0		40	430 Day	595 Calendar Days	Gordon	John M	99.0%			6/20/2017	6/2/2017	6/20/2017		6
2445 101/2016 EL Ordanio Park Flace II 24517 101/2016 ICCC Orchard Hills Backbone 24519 101/2016 ICCC Orchard Hills Backbone 24519 117/2016 Orchard Hills Backbone Orchard Hills Backbone 24519 117/2016 Foremod Companies Terranne Intrad 24519 117/2017 ICCC Orchard Hills N3 Street Improvements 24500 117/82017 ICCC Orchard Hills N3 Street Improvements 24501 117/82017 ICCC Orchard Hills N3 Street Improvements 24502 117/82017 ICCC Orchard Hills N3 Street Improvements 24503 117/82017 ICCC Orchard Hills N3 Street Improvements 24504 117/82017 ICDC Orchard Hills N3 Street Improvements 24505 41/12017 ICIC Orchard Hills N3 Street Improvements 24506 41/12017 Long Costa Resta Gin 24604 41/42017 Landsea Holdings Tr. 15353 Street Improvements 24605 41/12017 Londis Orchard Hills N3 Street Impro	\$ 2,232,659.0 \$ 990,249.9		8,500 5,888	1,000 Day 500 Day	95 Days 60 Days	Michele Michele	Jeny Jeny	99.0% 99.0%							-
28689 10*/14/2016 IC/C Orchard Hills Backbone 28881 11/8/2016 Sutur Construction Olinda Alpha Landfil 28883 11/8/2016 Formand Companias Terranor Infract 28884 12/8/2016 Formand Companias Terranor Infract 28895 11/8/2017 ICCC Orchard Hills N3 Street Improvements 28905 11/8/2017 ICCC Orchard Hills N3 Street Improvements 29905 41/1/2017 CDC of Cost Mass Terwisk Park Planking Lol Improvements 29906 41/1/2017 Lock Cost Cost Cost Cost Cost Cost Cost Cost	\$ 995,212.2	10/1/2016 SL Ontario Park Place II	3,500	500 Day	120 Working Days	Miguel	Jim	98.0%							-
29891 11/22016 OHL OC 405 Partners 29328 11/22016 Foremost Companies Terramor Infract 29328 11/22017 Foremost Companies Terramor Infract 29339 11/22017 Foremost Companies Terramor Infract 29391 11/22017 FODC Orchard Hills NS Street Improvements 29393 11/92017 ICDC Orchard Hills NS Street Improvements 29394 11/92017 ICDC Orchard Hills NS Street Improvements 29496 11/92017 ICDC Orchard Hills NS Street Improvements 29496 11/92017 ICDC Orchard Hills NS Street Improvements 29496 41/42017 Lewis Altimon 07-252624 Route 5 29401 41/42017 Lewis Altimon Reits Clein 29403 6/52017 Reverside Const.1017 Of Clein Reverside Const.1017 29404 41/42017 Lawis Operating Mediaa Street Improvements 29405 41/42017 Lawis Operating Mediaa Street Improvements 29404 71/42017 Parkee Hones </td <td></td> <td></td> <td>5,222</td> <td>172 Day</td> <td>60 Working Days</td> <td>Jerry</td> <td>Rick</td> <td>99.0%</td> <td></td> <td></td> <td></td> <td>-</td> <td></td> <td></td> <td>4</td>			5,222	172 Day	60 Working Days	Jerry	Rick	99.0%				-			4
23328 11/82/016 Sukut Construction Olinda Alpha Landfill 23456 12/12/016 Foremost Companies Terramor Infract Marine Way 23451 11/82/017 Flove Point Communities Barrance from Alton to Marine Way 23451 11/82/017 ICDC Orchard Hills NS Street Improvements 23452 11/82/017 ICDC Orchard Hills NS Street Improvements 23453 11/82/017 ICDC Orchard Hills NS Street Improvements 23454 11/82/017 ICDC Orchard Hills NS Street Improvements 23452 31/22/017 City of Costa Mesa Tewinkle Park Parking Lot Improvements 23452 41/12/017 City of Costa Mesa Tewinkle Park Parking Lot Improvements 23453 6/6/2017 Speecher Development Retal Gien 23454 6/6/2017 Riverside Const-City of Corona Cajalco /1-15 Interchange Improvements 23454 7/12/017 Lewis Operating AD Ramp Replacement 23454 7/12/017 Lewis Operating AD Ramp Replacement 23454 7/12/2017 Lewis Operating D	\$ 2,220,000.0 \$ 32,330,151.8		14,000 373,000	Day Day	120 Working Days	Miguel Brett	Rick Doug	99.0%							
2874 1/1/2017 Five Point Communites Baranca from Alton to Marine Way 28901 1/192017 ICDC Orchard Hills NS Street Improvements 28902 1/192017 ICDC Orchard Hills NS Street Improvements 28903 1/192017 ICDC Orchard Hills NS Street Improvements 28904 1/192017 ICDC Orchard Hills NS Street Improvements 28905 1/192017 ICDC Orchard Hills NS Street Improvements 28906 1/192017 ICDC Orchard Hills NS Street Improvements 28906 1/12017 City of Long Beach Annual Street Improvements 29904 1/12017 City of Costa Mesa Tewinkle Park Parking Lol Improvements 29905 4/14/2017 Laws-I-dihond Renissance & Linden Street Improvements 29906 4/14/2017 Laws-I-dihond Renissance & Linden Street Improvements 29907 1/1/2017 Reves Operating AD Ramp Replacement 29908 1/1/2017 Parkee Comparing AD Ramp Replacement 29909 1/1/2017 Parkees Rescom D4 MaB 29917 1/1/2017 Parkees Rescom D4 MaB 29942 1/1/2017 Parkees Rescom D4 MaB 29942017 Harrivs A Harrer Upper St	\$ 1,269,635.0	11/8/2016 Sukut Construction Olinda Alpha Landfill	6,500	0 Day	240 Working Days	Miguel	Rick	99.0%			7/3/2017	5/4/2017	7/11/2017	Fedex	
28801 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28903 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28904 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28905 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28905 1/18/2017 ICDF Atlinson Orchard Hills N3 Street Improvements 29905 4/12/2017 City of Ocsta Meesa Tewrikle Park Parking Lot Improvements 29905 4/12/2017 Laws-Hilwood Renissance & Linden Street Improvements 29906 4/12/2017 Laws-Hilwood Renissance & Linden Street Improvements 29905 4/12/2017 Laws-Hilwood Renissance & Linden Street Improvements 29906 4/12/2017 Lewis Holdings Tr. 15353 Street Improvements 29907 Harde Homes Menifee Holgins Transportation 29908 Harde Homes Menifee Holgins Transportation 29907 Harde Kescon D4 MBB Transportation Park Pace Pa 2 St Improvements 29917 Divaride K Harger	\$ 1,815,000.0		6,000 4,000	650 Day 500 Day	95 Days 90 Days	Michele Michele	Jerry Rick	99.0% 99.0%							
28903 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28904 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28905 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28905 1/18/2017 ICDr of Long Each Annual Street Improvements R-7084 29052 4/12/2017 City of Long Each Annual Street Improvements R-7084 29050 4/12/2017 City of Long Each Annual Street Improvements R-7084 29050 4/12/2017 Lewis Operating Meridian Street Improvements 29151 5/12/2017 Rewish Econs Calaco / 1-15 Interchange Improvements 29463 6/6/2017 Riverside ConstCity of Corona Calaco / 1-15 Interchange Improvement 29464 7/12/2017 Lewis Operating ADA Remp Replacement 1 29464 7/12/2017 Parkeescom O-4 MBB 28464 7/12/2017 29464 7/12/2017 Parkeescom O-4 MBB 28464 7/12/2017 Each Street Improvements 29454 9/12/2017 Canstreet Resord Fairk Places PL Sth	\$ 2,609,295.0 \$ 452,169.8		2,650	7,000 Day	240 Working Days	Miguel	Rick	99.0%							
28804 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28805 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28805 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28905 4/1/2017 Ciby of Costa Mesa Terwinkle Park Parking LoI Improvements 28905 4/1/2017 Landsea Holdings Tr. 15333 Street Improvements 28905 4/1/2017 Landsea Holdings Tr. 15333 Street Improvements 28905 4/1/2017 Landsea Holdings Tr. 15333 Street Improvements 28905 6/1/2017 Selker Dovelopment Reals Cien Cajato / 1-15 Interchange Improvement 28905 6/1/2017 Christopher Development Tr. 19938 Park Place 2 2242 28944 7/14/2017 Parke Reacom D4 MBB 2842 29/14/2017 28945 7/14/2017 Parke Reacom D4 MBB Cajato / 1-5 Intervonge Improvements 28945 7/14/2017 Parke Reacom D4 MBB Cajato / 1-5 Intervonge Improvements 28945 7/14/2017 Parke Hangor Cajato / 1-5 In	\$ 947,322.6		2,505	Day		Miguel	Rick	99.0%							_
28905 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28906 1/18/2017 ICDC Orchard Hills N3 Street Improvements 28905 4/12/2017 ICD of Long Beach Annual Street Improvements R-7094 28002 4/12/2017 City of Long Beach Annual Street Improvements R-7094 28004 4/14/2017 Landsa Holdings Tr. 1533 Street Improvements 28004 4/14/2017 Landsa Holdings Tr. 1533 Street Improvements 28005 4/14/2017 Lawis-Hillwood Reals Gian Improvements 28006 4/14/2017 Lawis-Development Reals Gian Improvements 28007 6/4/2017 Riverside Const.City of Corona Cale MoClave Way 28017 7/12/2017 Lawis Operating ADA Remp Replacement 28048 7/12/2017 Parkee Scorn Dof MBB 28049 7/11/2017 Parkee Rescorn Dof MBB 28042 17/12/2017 Parkee Rescorn Dof MBB 28042 17/12/2017 Farkescorn Dof MBB 28044 10/22/2017 <t< td=""><td>\$ 443,778.7 \$ 638,421.4</td><td></td><td>2,100 1,510</td><td>Day Day</td><td></td><td>Miguel Miguel</td><td>Rick Rick</td><td>99.0% 99.0%</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	\$ 443,778.7 \$ 638,421.4		2,100 1,510	Day Day		Miguel Miguel	Rick Rick	99.0% 99.0%							
29255 3/22/2017 Guy F, Atkinson 07-252524 Roule 5 29052 4/1/2017 City of Long Beach Annual Street Improvements R-7084 29083 4/11/2017 City of Long Beach Annual Street Improvements 29040 4/14/2017 Lewis Allwood Renissance & Linden Street Improvements 29040 4/14/2017 Lewis Operating Renissance & Linden Street Improvements 29433 6/2/2017 Speker Development Reata Gien Cajalco 1-15 Interchange Improvement 29443 6/2/2017 Niterside Const.City of Const AC Cap McCleve Way AD Remp Replacement 29451 7/12/2017 Lewis Operating Pink Place MP 2 St Improvements 29424 29452 7/11/2017 Department of Transportation Park Place MP 2 St Improvements 29448 29454 8/2/2017 Hardy A Harper Colivos PA-39 Off-Site Improvements 29454 29454 8/2/2017 Colivos IV/2017 City of Industry Alloward Amar Road Guardmal 29454 8/2/2/017 Lewis Operating Fink Place Net Street Improvements 29454 <t< td=""><td>\$ 693,366.7</td><td>I/19/2017 ICDC Orchard Hills N3 Street Improvements</td><td>1,180</td><td>Day</td><td></td><td>Miguel</td><td>Rick</td><td>99.0%</td><td></td><td></td><td></td><td></td><td></td><td></td><td>-</td></t<>	\$ 693,366.7	I/19/2017 ICDC Orchard Hills N3 Street Improvements	1,180	Day		Miguel	Rick	99.0%							-
29962 4/1/2017 City of Loga Beach Annual Street Improvements R-7064 29062 4/11/2017 Landsea Holdings Tr. 15333 Street Improvements 29050 4/14/2017 Landsea Holdings Tr. 15333 Street Improvements 29155 6/2/2017 Reversite Construction Ac Cap McOleve Way 29403 6/5/2017 Riversite ConstCity of Corona Cajalco /1-15 Interchange Improvements 29464 6/5/2017 Riversite Corons CA Cap McOleve Way 29464 7/12/2017 Lewis Operating ADA Remp Replacement 29464 7/12/2017 Lewis Operating ADA Remp Replacement 29464 7/12/2017 Parkee Steet Improvements 29464 7/12/2017 Parkee Steet Improvements 29464 7/12/2017 Parkee Steet Improvements 29464 9/4/2017 Parkees Resorn Do /4 MBB 29464 9/4/2017 Deparkees New DSt Steet Improvements 2947 10/13/2017 Sterik Konge Pask Place P1 St St Improvements 2947 10/13/2017 Sterik Konge Pask Place P1 Steet Improvements <	\$ 484,920.2		2,100	Day	COD Mad In Dr.	Miguel	Rick	99.0%			Platast		d 10 1	F-17	_
2982 4/11/2017 City of Costa Mesa Tewinkle Park Parking LoI Improvements 29840 4/14/2017 Lewis-Alliwood Renissance & Linden Street Improvements 29850 4/14/2017 Lewis Operating Meridian Street Improvements 29843 6/5/2017 Speiker Development Reata Clean Cajato / 15 Interchange Improvement 29843 6/6/2017 Riverside Const. City of Corona AC Cap McCleve Way 29844 7/1/2017 SL Ontario AC Cap McCleve Way 29845 7/1/2017 Parkee Homes Menitee Heights 29845 7/1/2017 Parkee Homes Menitee Heights 29845 9/1/2017 Parkee Homes Menitee Heights 29845 9/1/2017 Parkee Homes Role Street Improvements 29845 9/1/2017 ICDC County of Russide Transportation Role Street Improvements 29845 9/2/2017 Hardy & Harper Upper Stone Reservoir Street Improvements 29845 9/1/2017 ICDC County of Russide Transportation Role Street Improvements 29845	\$ 4,600,000.0 \$ 30,000,000.0		46,300 75,000	5,000 Day	520 Working Days 365 Days	Gordon Jerry	Art Jorge	99.0% 99.0%			5/8/2018		5/9/2018	Fed Ex	-
2950 4/14/2017 Lewis-Operating Meridian Street Improvements 29475 5/2/2017 Speiker Development Reata Clein 29483 6/6/2017 Speiker Development Reata Clein 29483 6/6/2017 Streistic Const. City of Corona AC Cap McCleve Way 29484 7/1/2017 SL Ontario AC Cap McCleve Way 29484 7/1/2017 Darks Development Tr. 18998 Park Place 2 29444 7/1/2017 Parkee Homes Menifee Heights 29442 7/1/2017 Parkee Rescorn O4 MBB 29442 St/2017 Lewis Operating Pine Ave. Street Improvements 29442 St/2017 Department of Transportation Route 39 29443 St/2017 Department of Transportation Los Olivos PA-39 Off-Site Improvements 29494 St/2017 Strokoton Rationad Canyon Widening 3042217 Parke Homes Rationad Canyon Widening 3042210 Colura Strokoton San Strokoton 3042217 Lenar Homes San Strokoton Parke Acces Road	\$ 450,002.5	1/11/2017 City of Costa Mesa Tewinkle Park Parking Lot Improvements	390	176 Day	18 Working Days	Maurice	Rick	99.0%							
29175 55/2017 Lewis Operating Meridian Street Improvements 29403 66/2017 Riverside Const. City of Corona Cajalco /1-15 Interchange Improvement 29435 66/2017 Riverside Const. City of Corona Cajalco /1-15 Interchange Improvement 29454 7/1/2017 Lewis Operating AOA Ramp Replacement 29454 7/1/2017 Lewis Operating AOA Ramp Replacement 29454 7/1/2017 Parkvest Rescorn D4 MBB 29532 7/1/2017 Lewis Operating Pine Ave. Street Improvements 29543 9/1/2017 Lewis Operating Pine Ave. Street Improvements 29543 9/1/2017 Lewis Operating Role SP 29543 9/1/2017 ICDC County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29797 10/132017 Suffok Construction Filight Avenue Cedar Street 1.Reocl Lane 29844 10/202017 Icoc Portola Springs Road and Ard Araa Road Guardrail 29845 10/1/202017 Icity of fudustry Alessandro Bird. Guardrail 29846	\$ 1,564,980.1		9,500	800 Day	N/A	Miguel	Rick	99.0%							
29403 6/f/2017 Speiker Development Reata Clen 29463 6/f/2017 SL Ontario Cajato / 1-15 Interohange Improvement 29463 7/f/2017 SL Ontario AC Cap McCleve Way 29451 7/f/2017 Lewis Operating AD A Ram Replacement 29454 7/f/2017 Parkee Homes Menifee Heights 29442 7/f/2017 Parkee Rescom O4 MBB 29442 St/2017 Deves Transport Upper Stone Reservor 29443 St/2017 Devesting Transport Upper Stone Reservor 29444 St/2017 Department of Transportation Route 39 29473 St/2/2017 Countrotion Route 39 29474 St/2/2017 Countrotion Route 39 29471 Difazoti 7 Parke Homes Rationad Canyon Widening 39421 Difazoti 7 Parke Homes Rationad Canyon Widening 39441 Difazoti 7 Parke Homes San Squarke 1A coces Road 29441 Difazoti 7 Parke Homes San Squarke 1A coces Road	\$ 4,630,000.0 \$ 5,277,277.0		25,000 40,000	4,000 Day 3,000 Day	180 Working Days N/A	Miguel Miguel	Jim John W	99.0% 99.0%							
29463 7/1/2017 SL Ontario AC Cap McCleve Way 29517 7/1/2017 Lewis Operating ADA Ram Replacement 29349 7/1/2017 Parkee Homes Menifee Heights 29342 7/1/2017 Parkee Nomes Menifee Heights 29342 7/1/2017 Parkee Rescon D4 MBB 29442 X718/2017 SL Ontario Park Place P1 2 SL Improvements 29443 X8/29/2017 Department of Transportation Roule 39 29593 9/1/2017 County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29594 10/13/2017 Pardee Homes Rairoad Canyon Widening Roule 39 29594 10/13/2017 Pardee Homes San Svaine Improvements- Fontana 29594 10/13/2017 Hardy & Harper Cedar Street & Reed Lane 29594 10/3/2017 Hardy & Harper Cedar Street & Reed Lane 29597 11/6/2017 City of Industry Batawine Park Boulevand and Arma Road Guardrail 29594 11/3/2017 City of Industry Harby A Street Improvements Porgram 29597 11/6/2017 City of Industr	\$ 1,608,291.0	6/5/2017 Speiker Development Reata Glen	12,200	0 Day	120 Days	Michele	Rick	99.0%			8/30/2017		9/8/2017	Emailed	
29517 7/1/2017 Lewis Operating ADA Ramp Replacement 29444 7/6/2017 Pardee Homes Menifee Heights 29342 7/11/2017 Pardee Homes Menifee Heights 29342 7/11/2017 Lewis Operating Pine Ave. Street Improvements 29442 3/29/2017 Hardy & Harper Upper Stone Reservoir 29442 3/20/2017 Hardy & Harper Upper Stone Reservoir 29484 9/6/2017 County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29797 10/13/2017 Stiffolk Construction Rairroad Canyon Widening 299797 10/13/2017 Stiffolk Construction Rairroad Canyon Widening 29944 10/30/2017 Lerons Pardee Homes 29945 10/30/2017 Lerons Pardial Sortings PA-6 Access Road 29946 10/30/2017 City of Industry Balswine Improvements Frogram 29947 11/30/2017 City of Moreno Valley Alessandro Blvd. Street Improvements 29947 11/30/2017 City of Moreno Valley Alessandro Blvd. Street Improvemen	\$ 3,149,197.5		45,500 1,100	0 Day & Nite	496 Working Days	Gordon	Art	99.0% 99.0%			7/17/2017		7/21/2017	Fed Ex	
29444 7/6/2017 Christopher Development Tr. 18999 Park Place 2 29349 7/14/2017 Parkevest Rescom D4 MBB 29342 7/11/2017 Parkevest Rescom D4 MBB 29342 7/18/2017 SL Ontario Park Place Ph 2 SL Improvements 29442 8/29/2017 Department of Transportation Roule 39 29454 9/6/2017 Department of Transportation Los Olivos PA-39 Off-Ste Improvements 29797 10/13/2017 Pardee Homes Railroad Canyon Widening 29361 10/13/2017 Pardee Homes Railroad Canyon Widening 29364 10/13/2017 Pardee Homes San Savaine Improvements-Fontana 29364 10/30/2017 Hardy & Harper Cedar Street & Reed Lane 29364 10/30/2017 City of Industry Batawin Park Boulevard and Amar Road Guardrail 29364 11/30/2017 City of Vocaipa Sh Street Improvements Forgram 29364 11/30/2017 City of Vocaipa Sh Street Improvements Program 29364 11/30/2017 The New Home Company Bedford 29364 11/2018 KB Homes Archibald - Eucalyp	\$ 73,700.0 \$ 75,800.0		1,100	Day 250 Day	N/A	Miguel Miguel	Jim Jerry	99.0%			8/3/2017 7/3/2017		8/3/2017 8/25/2017	Emailed FedEx	
29342 7/11/2017 Parkwest Rescom D4 MBB 29550 7/11/2017 Lewis Operating Pink Ave. Street Improvements 29541 7/11/2017 SL Ontario Park Place Ph 2 St Improvements 29542 8/29/2017 Department of Transportation Route 39 29593 9/14/2017 County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29708 9/27/2017 County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29797 10/13/2017 Suffolk Construction Flight Avenue 29864 10/16/2017 Pardee Hornes Raimod Canyon Widening 29864 10/30/2017 Lengt Homes San Savaine Improvements Fontana 29864 10/30/2017 City of Moreno Valley Alessandro Bivd. Street Improvements Fontana 29864 11/30/2017 City of Moreno Valley Alessandro Bivd. Street Improvements Fontana 29874 12/8/2017 City of Moreno Valley Alessandro Bivd. Street Improvements Fontana 29874 12/8/2017 Derice Canse Or307804 Cold Pane, HMA, JPCP, & Upgrade ADA Ri 29874 12/8/2017 Bride Morene Company Bedf	\$ 153.578.8	7/6/2017 Christopher Development Tr. 18998 Park Place 2	1,100	160 Day	90 Working Days	Miguel	Jim	99.0%			8/10/2017		8/11/2017	Docusign	
29520 7/11/2017 Lewis Operating Pine Ave. Street Improvements 29518 7/11/2017 SL Ontario Park Place Ph 2 St Improvements 29584 9/202017 Hardy & Harper Upper Stone Reservoir 29584 9/202017 Department of Transportation Role 39 29593 9/17/2017 County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29708 9/27/2017 Suffolk Construction Filight Avenue 29797 10/13/2017 Suffolk Construction Filight Avenue 29864 10/13/2017 Lenart Homes San Savaine Timprovements - Fontana 29864 10/30/2017 Lenart Homes San Savaine Timprovements - Fontana 29897 11/3/2017 City of Industry Batswine Tark Boulevard and Amar Road Guardrail 29894 11/3/2017 City of Ocachella Active Transportation Cycle #1 30079 12/13/2017 Peterson Chase O'-307804 Coid Plane, HMA, JPCP, & Upgrade ADA R: 29894 11/2018 Brandymic Homes Archibald - Eucalyptus to Parkview 29898 11/3/2018	\$ 3,609,257.0 \$ 185,375.0		24,170	2,400 Day 200 Day	120 Days 30 Days	Michele Michele	John W Rick	99.0% 99.0%							
29118 7/119/2017 SL Ontario Park Place Ph 2 St Improvements 29142 8/29/2017 Department of Transportation Roule 39 29153 9/14/2017 Department of Transportation Roule 39 29153 9/14/2017 Department of Transportation Climan Springs Road and SH-79 Northbound Ramps 29179 10/13/2017 Pardee Homes Saringe Market A Access Road 29171 10/13/2017 Pardee Homes Saringe Market A Access Road 29174 10/13/2017 Lennar Homes Saringe Market A Access Road 29174 10/13/2017 City of Industry Baldwin Park Boulevard and Amar Road Guardrail 29189 11/16/2017 City of Moreno Valley Alessandro Bivd. Street Improvements Program 2917 11/3/2017 City of Moreno Valley Alessandro Bivd. Street Improvements Program 29174 11/3/2017 City of Coachella Active Transportation Cycle ADA Rc 29173 12/13/2017 The New Home Company Bedford 29174 11/3/2018 Brandywine Homes Arxinalizal - Eucalyptus to Parkview 29184 1/1/2018 Brandywine Homes Alessandro Bivd Easthound Bike Lane Improv	\$ 1,742,442.9	7/18/2017 Lewis Operating Pine Ave. Street Improvements	5,000	500 Day/Night	120 Working Days	Miguel	Jerry	92.0%			8/11/2017		8/29/2017	FedEx	
29844 96//2017 Department of Transportation Roule 39 29708 9/27/2017 County of Riverside Trans. Dept. Gilman Springs Road and SH-79 Northbound Ramps 29797 10/13/2017 Sufok Construction Flight Avenue 30623 10/16/2017 Parclee Homes Rairoad Caryon Widening 29941 10/19/2017 Hardy & Harper Cedar Street & Reed Lane 29844 10/30/2017 Lennar Homes San Savaine Improvements - Fontana 29845 11/30/2017 City of Moreno Valley Alessandro Blvd, Street Improvements - Fontana 29846 11/30/2017 City of Moreno Valley Alessandro Blvd, Street Improvements Program 29847 12/48/2017 City of Caachella Active Transportation Cycle #1 30079 12/13/2017 The New Home Company Bedford 29848 11/12/2018 Brandywine Homes Riverdale 29844 11/12/2018 Foremost Companies Decrtake 29845 12/18/2017 Bring Meresite Trans. Dept. Active Transportation Cycle #1 30055 1/20/2018 Dennis Lorton & Associates 7403 La Tijera Blvd Stretel Improvements 30	\$ 800,965.9	7/19/2017 SL Ontario Park Place Ph 2 St Improvements	4,400	600 Day	120 Working Days	Migue!	Jim	99.0%			8/24/2017		8/25/2017	Emailed	
12953 9/14/2017 ICDic Cic Los Olivos PA-39 Off-Site Improvements 129708 9/27/2017 Suffolk Construction Flight Avenue 30923 10/16/2017 Parkee Homes Rairoad Canyon Widening 30923 10/16/2017 Parkee Homes Rairoad Canyon Widening 29864 10/30/2017 Lenar Homes Sairoad Canyon Widening 29864 10/30/2017 Lenar Homes Sairoad Canyon Widening 29864 10/30/2017 City of Industry Baldwin Park Boulevard and Amar Road Guardrail 29864 11/30/2017 City of Noreno Valley Alessandro Blvd, Street Improvements Program 29874 12/18/2017 Deterson Chase 07-307804 Cold Plane, HMA, JPCP, & Upgrade ADA R 29874 12/18/2017 The New Home Company Bedford 29831 12/18/2017 The New Homes Arcihiald - Eucalyptus to Parkview 29834 11/2018 Brandywine Homes Arcihiald - Eucalyptus to Parkview 29834 11/2018 Brandywine Homes Arcihiald - Eucalyptus to Parkview 29834 11/2018 Brandywine Homes Arcihiald - Eucalyptus to Parkview 29834 1	\$ 27.260.0 \$ 5.871,030.0		32,300	Day 600 Night	270 Working Days	Cody Jim	Randy Doug	99.0% 99.0%						-	_
19797 10/13/2017 Suffoik Construction Flight Avenue 30923 10/16/2017 Pardee Homes Rainrad Canyon Widening 29941 10/13/2017 LCDC Portola Springs PA-6 Access Road 29744 10/30/2017 Lennar Homes San Savaine Improvements - Fontana 29864 10/30/2017 Lennar Homes San Savaine Improvements - Fontana 29875 11/6/2017 City of Moreno Valley Alessandro Bluvd. Street Improvements Program 29946 11/30/2017 City of Moreno Valley Alessandro Bluvd. Street Improvements Program 29946 12/18/2017 City of Accehella Active Transpontation Cycle 41 30079 12/18/2017 The New Home Company Bedford 29936 11/12/018 Brandywine Homes Riverdale 29948 11/2/18/2018 Foremost Companies Deertake 29937 11/8/2018 Foremost Companies Deertake 29937 11/8/2018 Domes Archibald - Eucalyptus to Parkview 29937 11/3/2018 Domes Loron & Associates 74/03 La Tijera Bird Street Improvements 30052 11/2/2018 Domes Loron & Asso	\$ 3,236,106.1	0/14/2017 ICDC Los Olivos PA-39 Off-Site Improvements	2,405			Miguel	Rick	99.0%			9/22/2017			-	9
10023 10/18/2017 Pardee Homes Rairoad Canyon Widening 29961 10/18/2017 ICDC Portola Springes PA-6 Access Road 29864 10/30/2017 Lennar Homes San Savaine Improvements - Fontana 29864 10/30/2017 Lennar Homes San Savaine Improvements - Fontana 29864 11/30/2017 City of Industry Batowin Park Boulevard and Amar Road Guardrall 29945 11/30/2017 City of Moreno Valley Alessandro Bivd, Street Improvements Program 29947 12/6/2017 City of Caachella Active Transportation Cycle #1 30079 12/13/2017 The New Home Company Bedford 29948 12/18/2017 The New Home Company Bedford 29948 11/12/2018 Brandywine Homes Riverdale 29949 11/8/2018 Foremost Companies Deerlake 30051 1/2/3/2018 Orl L Route 110, 405 07-293704 30052 1/2/4/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lane Improvements 30053 1/2/3/2018 Orl L SA R	\$ 589,540.0		930	30 Day	35 Working Days	Maurice	John W	99.0%			12/21/2017	9/27/2017	10/18/2017	FedEx	_
29941 10/19/2017 ICDC Portola Springs PA-6 Access Road 29744 10/30/2017 Hardy & Harper Cedar Street & Reed Lane 29864 10/30/2017 Lennar Homes San Savaine Improvements - Fontana 29864 10/30/2017 City of Industry Baldwin Park Boulevard and Arma Road Guardrail 29827 11/8/2017 City of Moreno Valley Alessandro Bluxd, Street Improvements Program 29974 12/8/2017 City of Acachelia Active Transportation Cycle 41 30079 12/18/2017 Brightwei Landscape D4 Streetscape 30198 12/18/2017 Brightwei Landscape D4 Streetscape 30198 12/18/2017 Brightwei Landscape D4 Streetscape 30198 12/18/2018 Brandywine Homes Riverdale 29948 11/1/2018 KB Homes Archibald - Eucalyptus to Parkview 29949 11/8/2018 Foremost Companies Decrake 30022 1/2/2/2018 Contro & Associates Adol to Tigen Blud Street Improvements 30035 1/3/2/2018 Dennis Lorton & Associates Adol to Tigen Blud Street Improvements 30035 1/3/2/2018	\$ 2,781,175.0 \$ 5,062,746.0	0/13/2017 Suffork Construction Flight Avenue 0/16/2017 Pardee Homes Railroad Canvon Widening	10,000 14,000	Day 1,200 Day	N/A 85 Working Days	Miguel Michele	Doug John W	99.0% 99.0%			10/29/2018		10/30/2018		1
28864 10/30/2017 Lenfar Homes San Savaine Improvements - Fontana 28897 11/8/2017 City of Moreno Valley Alessandro Bivd. Street Improvements 29946 11/30/2017 City of Yucaipa Sth Street Improvements Program 29947 12/8/2017 City of Yucaipa Sth Street Improvements Program 29947 12/8/2017 City of Cacchella Active Transportation Cycle #1 30079 12/18/2017 Brightview Landscape D4 Streetscape 30198 12/18/2017 Brightview Landscape D4 Streetscape 29948 11/1/2018 Brandywine Homes Riverdale 29948 11/1/2018 Ke Homes Archibald - Eucalyptus to Parkview 29959 11/8/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lane Improvements 30055 1/2/3/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lane Improvements 30054 1/3/202018 Folianeering Frainds/Turner Street Improvements 30055 1/3/202018 Folianeering Frainds/Turner Street Improvements 30056 1/3/202018 Folianeering Frainds/Turner Street Improvements	\$ 959,000.0	0/19/2017 ICDC Portola Springs PA-6 Access Road	2,500	120 Day	90	Miguel	Rick	99.0%			TULUILOILOITO		10/30/2018		
29897 11/6/2017 City of Moreno Valley Batkwin Park Boulevard and Arnar Road Guardrail 29946 11/30/2017 City of Moreno Valley Alessandro Bivd. Street Improvements 29947 12/6/2017 City of Caachella Active Transportation Cycle #1 30079 12/13/2017 Peterson Chase OT-307804 Cold Plane, HMA, JPCP, & Upgrade ADA Rt 298481 12/18/2017 The New Home Company Bedford 29926 11/12/2018 Brandywine Homes Riverdale 29937 11/8/2018 KB Homes Archibald - Eucalyptus to Parkview 29936 11/12/2018 Brandywine Homes Riverdale 29947 11/8/2018 Foremost Companies Deerlake 29957 11/8/2018 Comn's of Riverdale Riverdale 29948 11/8/2018 Comis Lorton & Associates 7403 La Tijera Bivd Street Improvements 30055 1/30/2018 Demis Lorton & Associates 7403 La Tijera Bivd Street Improvements 30956 1/30/2018 Filairon West, Inc. 07-202124, Route 710 07-202144, Route 710 30160 2/8/2018 SL Ontario Eucalyptus Tireet Improvements 30240 <td< td=""><td>\$ 12,880.0</td><td></td><td>2,275</td><td>Day</td><td>40 Working Days</td><td>Cody Michele</td><td>Randy Jim</td><td>99.0% 99.0%</td><td></td><td></td><td>11/29/2017</td><td></td><td></td><td></td><td>12/13</td></td<>	\$ 12,880.0		2,275	Day	40 Working Days	Cody Michele	Randy Jim	99.0% 99.0%			11/29/2017				12/13
29922 11/9/2017 City of Vareno Valley Alessandro Bivd, Street Improvements 29944 11/30/2017 City of Caachella Active Transportation Cycle #1 30079 12/13/2017 Peterson Chase 07-307804 Cold Plane, HMA, JPCP, & Upgrade ADA Rr 29831 12/18/2017 Brightview Landscape D4 Streetscape 30193 12/18/2017 The New Home Company Bedford 29826 11/2018 Brandywine Homes Riverdale 29894 11/12/018 K BH Komes Archibald - Eucalyptus to Parkview 29895 11/2018 Foremost Companies Deertake 30055 1/22/32018 Coluty of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lare Improvements 30056 1/24/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lare Improvements 30166 1/30/2018 Falatron West, Inc. 07-202124, Route 710 207-228704 30867 2/4/2018 OHL, USA Route 91, 105, 110, 405 77-28704 308687 2/4/2018 St. Ontario Eucalyptus Street Improvements 30100 2/8/2018 St. Ontario Eucalyptus 287-28704	\$ 508,951.0 \$ 170,611.0		2,275	Day 57 Day	30 Calendar Days	Edward	Jim	99.0%			12/6/2017	12/1/2017	12/11/2017	FedEx	12/1
12974 12/6/2017 City of Coachella Active Transportation Cycle #1 30079 12/18/2017 Peterson Chase 07-307804 Cold Plane, HMA, JPCP, & Upgrade ADA Rr 29831 12/18/2017 Brightview Landscape D4 Streetscape 30198 12/18/2017 Brightview Landscape D4 Streetscape 29826 11/12/018 Brandywine Homes Riverdale 29844 11/12/018 K Romes Archibald - Eucalyptus to Parkview 29897 1/18/2018 Foremost Companies Deertake 30055 1/23/2018 County of Riverside Trans. Dept. Active 110, 405 07-293704 30055 1/24/2018 County of Riverside Trans. Dept. Active 110, 405 07-293704 30056 1/24/2018 Peterson Chase Route 110, 07-2975044 30058 1/32/2018 Felatron West, Inc. 07-202724, Route 710 30100 2/8/2018 SL Omiario Eucalyptus Street Improvements 30100 2/8/2018 SL Omiario Eucalyptus Street Improvements 30124 3/21/2018 Merdian Parkway Barton Koad Street Improvements 30100 2/8/2018 SL Omiario E	\$ 445 821.5	11/9/2017 City of Moreno Valley Alessandro Blvd. Street Improvements	151	58 Day	110 Working Days	Edward	John W	99.0%			2/23/2018	2/23/201B	2/27/2018	FedEx	
30079 12/13/2017 Peterson Chase 07-307804 Cold Plane, HMA, JPCP, & Upgrade ADA R: 29831 12/18/2017 Brightive Landscape D4 Streetscape D4 Streetscape 29932 11/12/018 Brandywine Homes Riverdale 29943 11/12/018 Brandywine Homes Archibald - Eucalyptus to Parkview 29944 11/12/018 KB Homes Archibald - Eucalyptus to Parkview 29957 11/18/2018 Foremost Companies Deertake 30052 11/23/2018 Oth Riscotacies 7403 La Tijera Bivd Street Improvements 30052 11/20/2018 Demis Loron & Associates 7403 La Tijera Bivd Street Improvements 30170 11/30/2018 GMC Engineening Francis/Turner Street Improvements 30170 11/20/2018 Feltron Orth, USA Route 110; 07-2975U4 30289 1/31/2018 Peterson Chase Route 110; 07-2975U4 30280 2/4/2018 Orth, USA Real provements 30140 2/4/2018 SL Omario Eucalyptus Street Improvements 30141 3/6/2018 LACDPW	\$ 962,888.0 \$ 1,354,516.0		1,040	580 Day 180 Day	90 Working Days 130 Calender Days	Maurice Maurice	John W John W	99.0% 99.0%			12/7/2017 1/29/2018	12/7/2017 12/18/2017	12/8/2017	FedEx FedEx	1
30198 12/18/2017 The New Home Company Bedford 29326 11/1/2018 Brandywine Homes Riverdale 29341 11/1/2018 Brandywine Homes Riverdale 29343 11/1/2018 KB Homes Archibald - Eucalyptus to Parkview 29397 1/18/2018 Foremost Companies Deentake 30635 1/23/2018 OHL Route 110, 405 07-293704 30092 1/24/2018 County of Riverside Trans. Dept. Alessandro Blvd Eastbound Bike Lane Improvements 30193 1/30/2018 Dennis Loton & Associates 7403 La Tijera Blvd Street Improvements 30186 1/30/2018 Flatino West, Inc. 07-202124, Route 710 30283 1/31/2018 Peterson Chase Route 110, 10/405 07-285704 30395 2/40/18 OHL, USA Route 91.10, 10/405 07-285704 30966 2/8/2018 SL Ontario Eucalyptus Street Improvements 30140 2/15/2018 Meridian Parkway Barton Road Barton Road 30124 3/6/2018 LACDPW Pine Canyon Road Barton Road <td>Ri \$ 400,013.0</td> <td></td> <td>3,010</td> <td>0 Night</td> <td>80 Working Days</td> <td>Edward</td> <td>Art</td> <td>99.0%</td> <td></td> <td></td> <td>2/14/2018</td> <td>2/9/2018</td> <td>1/4/2018</td> <td>TEULA</td> <td></td>	Ri \$ 400,013.0		3,010	0 Night	80 Working Days	Edward	Art	99.0%			2/14/2018	2/9/2018	1/4/2018	TEULA	
29326 11/1/2018 Brandywine Homes Riverdale 29348 11/1/2018 KB Homes Archibald - Eucalyptus to Parkview 29397 11/8/2018 Foremost Companies Deertake 30635 1/23/2018 OHL Route 110, 405 07-293704 30605 1/24/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lane Improvements 30695 1/24/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lane Improvements 30170 1/30/2018 Patricon West, Inc. 07-202124, Route 710 Route 91, 105, 710, 405 07-288704 30288 1/31/2018 Peterson Chase Route 110, 07-2075044 Route 91, 105, 710, 405 07-288704 30587 2/4/2018 St. Ontario Eucalyptus Street Improvements Storest Improvements 30100 2/8/2018 St. Ontario Merrill Avenue Street Improvements 30124 3/6/2018 LACDPW Pine Canyon Road 30134 3/6/2018 LACDPW Pine Avenue Improvements Stages 1 & 2 30156 3/1/2/2018 Chip Development Corp. Pine Avenue Improvements Stages 1 & 2 30156 3/1/2/2018 Chip Invindale 2017/2018 Resurfacing Project 30156 3/1/2/2018 Chip Development Corp. Pine Avenue Improvements St	\$ 133,722.0		4 500	250 Day	20 Days	Michele	Rick	99.0%							_
19943 11/12/018 KB homes Archibal - Eucalyptus to Parkview 29997 1/18/2018 Foremost Companies Deerlake 30535 1/23/2018 OHL Route 110, 405 07-293704 30022 1/24/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lane Improvements 30170 1/30/2018 Dennis Lorton & Associates 7403 La Tijera Bivd Street Improvements 30170 1/30/2018 Flatino West, Inc. 07-202124, Route 710 30288 1/31/2018 Peterson Chase Route 110, 07-2975U4 30996 2/8/2018 St. Ontario Eucalyptus Street Improvements 30100 2/8/2018 St. Ontario Merrill Avenue Street Improvements 30134 3/6/2018 St. Ontario Merrill Avenue Street Improvements 31266 2/21/2018 County of Orange 2020 Walnut Ave 30134 3/6/2018 LACOPW Pine Canyon Road 30134 3/6/2018 Chip Development Corp. Pine Avenue Improvements Stages 1 & 2 30240 3/13/2018 Brightrivie Landscape Los Olivos	\$ 1,214,417.0 \$ 813,159.0		4,500 1,200	1,000 Day 750 Day	60 Days	Michele Michele	John W Jorge	99.0% 99.0%	-						
39535 1/23/2018 OHL Route 110, 405 07-28704 30025 1/24/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lare Improvements 30095 1/30/2018 County of Riverside Trans. Dept. Alessandro Bivd Eastbound Bike Lare Improvements 30170 1/30/2018 GMC Engineering Francis/Turner Street Improvements 30186 1/30/2018 Flaticon West, Inc. 07-202124, Route 710 30298 1/31/2018 Flaterson Chase Route 110, 07-2975U4 30096 2/4/2018 St. Ontario Eucalyptus Street Improvements 30100 2/4/2018 St. Ontario Eucalyptus Street Improvements 30240 2/15/2018 Meridian Parkway Barton Road Street Improvements 30134 3/6/2018 LACOPW Pine Canyon Road 30134 3/6/2018 Cautry of Orange 2020 Walnut Ave 30254 3/1/1/2018 Cautry of Orange 2020 Walnut Ave 30268 3/1/2018 Cautro for model 2017/2018 Resurfacing Project 30178 3/22/2018 Caltrans 07-3009UA Route 911	\$ 297.052.0	1/1/2018 KB Homes Archibald - Eucalyptus to Parkview	640	200 Day	30 Days	Michele	Jim	99.0%							
30022 1/2/2/2018 County of Riverside Trans. Dept. Alessandro Bivd Earbound Bike Lane Improvements 30095 1/30/2018 Demis Lorton & Associates 7403 La Tijera Bivd Street Improvements 30170 1/30/2018 Demis Lorton & Associates 7403 La Tijera Bivd Street Improvements 30186 1/30/2018 Flairor West, Inc. 07-202124, Route 710 30288 1/31/2018 Peterson Chase Route 110, 07-207504 30857 2/4/2018 SL Ontario Eucalyptus Street Improvements 30100 2/8/2018 SL Ontario Eucalyptus Street Improvements 30126 2/15/2018 Meridian Parkway Barton Road Street Improvements 30136 2/15/2018 Contry of Orange 2020 Walnut Ave 30136 2/15/2018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2 30128 3/1/2/2018 Drink Campon Road 2017/2018 Resurfacing Project 30136 3/1/2/2018 Caltrans (12-00/7/04) Route 91 Ramp Kehabilitation 30137 3/2/2/2018 Deador Construction San Gabnel River Bike Path Gap Long Beäch 3012	\$ 2,139,646.0		13,000	1,500 Day	60 Days	Michele	Jorge Art	99.0% 99.0%			4/04/2018	4/00/0048	54/0040	FEDEV	_
30095 1/30/2018 Dennis Lorton & Associates 74/03 La Tijera Bivd Street Improvements 30170 1/30/2018 Flatiron West, Inc. 07-202124, Route 710 3028 1/31/2018 Flatiron West, Inc. 07-202124, Route 710 3028 1/31/2018 Platiron West, Inc. 07-202124, Route 710 30288 1/31/2018 Platerson Chase Route 110: 07-22875U4 30867 2/4/2018 OHL, USA Route 91, 105, 110, 405 07-286704 30095 2/4/2018 SL Omario Eucalypticus Street Improvements 30100 2/4/2018 SL Omario Merrini Avenue Street Improvements 30240 2/15/2018 Merdian Parkway Barton Road Street Improvements 30134 3/6/2018 LACDPW Pine Canyon Road 30166 3/17/2018 Chirp Development Corp. Pine Avenue Improvements Stages 1 & 2 30166 3/15/2018 Caltrans (12-20/7/04) Route 91 Ramp Fehabilitation 30185 3/22/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach 30185 3/22/2018 Department of Transportation <td>\$ 186,368.0 \$ 1,609,342.5</td> <td></td> <td>1,340 8,394</td> <td>Night 30 Day/Night</td> <td>700 Working Days 63 Calander Days</td> <td>Edward</td> <td>John W</td> <td>99.0%</td> <td></td> <td></td> <td></td> <td>4/23/2018 4/19/2018</td> <td>5/1/2018</td> <td>FEDEX</td> <td>+</td>	\$ 186,368.0 \$ 1,609,342.5		1,340 8,394	Night 30 Day/Night	700 Working Days 63 Calander Days	Edward	John W	99.0%				4/23/2018 4/19/2018	5/1/2018	FEDEX	+
30186 1/30/2018 Flattron West, Inc. 07-202124, Route 710 30288 1/31/2018 Peterson Chase Route 91, 105, 7297504 300587 2/4/2018 OHL, USA Route 91, 105, 710, 405 07288704 300587 2/4/2018 SL Ontario Eucalyptius Street Improvements 30100 2/8/2018 SL Ontario Eucalyptius Street Improvements 30100 2/8/2018 SL Ontario Merrill Avenue Street Improvements 30120 2/8/2018 SL Ontario Merrill Avenue Street Improvements 30134 3/8/2018 ACOPW Pine Camyon Road 30134 3/8/2018 ACOPW Pine Camyon Road 30134 3/8/2018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2 30250 3/13/2018 Grity Invindale 2017/2018 Resurfacing Project 30156 3/14/2018 Caltrans (12-02/7/04) Route 91 Ramp Rehabilitation 30289 4/4/2018 Caltrans 07-30094 Route 110 30289 4/16/2018 Caltrans 07-30094 Route 110 30289 4/16/	\$ 60,582.2	1/30/2018 Dennis Lorton & Associates 7403 La Tijera Blvd Street Improvements	300	0 Day	1 Working Day	Maurice	Art	99.0%				novo o Ililia			
30298 1/31/2018 Peterson Chase Route 110; 07-2975U4 30587 2/4/2018 OHL, USA Route 91, 105, 110, 405 07-28/6704 30096 2/8/2018 SL. Ontario Eucalyptius Street Improvements 30100 2/8/2018 SL. Ontario Eucalyptius Street Improvements 30100 2/15/2018 Meridian Parkway Barton Road Street Improvements 31346 2/15/2018 Meridian Parkway Barton Road Street Improvements 30134 3/6/2018 LACDPW Pline Canyon Road Street Improvements 30134 3/6/2018 LACDPW Pline Canyon Road Street Improvements 30134 3/6/2018 LACDPW Pline Avenue Improvements Stages 1 & 2 Street Improvements 30134 3/6/2018 Chino Development Corp. Pline Avenue Improvements Stages 1 & 2 30185 3/2/1/2018 Caltrans (12-00/7/04) Route 91 Ramp Rehabilitation 30185 3/2/2/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach 30185 3/2/2/2018 Caltrans 07-3009UA Route 91 Ramp Rehabilitation	\$ 16,021.0 \$ 499,025.0	1/30/2018 GMC Engineering Francis/Turner Street Improvements	0 3,447	0 Day 0 Night	1 Working Day 1250 Working Day	Maurice Jim	Darren Art	99.0% 99.0%							
30096 29/2/018 SL Ontario Eucalyptus Street Improvements 30100 2/8/2018 SL Ontario Merrill Avenue Street Improvements 30240 2/15/2018 Meridian Parkway Barton Road Street Improvements 31366 2/21/2018 County of Orange 2020 Walnut Ave 30134 3/6/2018 CAUPD W Prine Canyon Road 30268 3/1/2018 Chino Development Corp. Prine Avenue Improvements Stages 1 & 2 30280 3/1/3/2018 Brightive Landscape Los Olivos 30554 3/1/3/2018 City of Invindale 201/1/2018 Resurfacing Project 30178 3/21/2018 Caltrans (12-00/7/04) Route 91 Hamp Rehabilitation 30185 3/22/2018 Department of Transportation Route 5 12-10/7604 30289 4/4/2018 Chino Development Corp. Tract 19934 Block 4 30289 4/4/2018 Caltrans 07-3009U4 Route 110 30281 A/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30319 -4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether	\$ 22,742.0	1/31/2018 Peterson Chase Route 110; 07-2975U4	38	0 Night	730 Working Day	Jim	Art	99.0%							-
30100 2//8/2018 SL. Ontario Merrill Avenue Street Improvements 30240 2/15/2018 Merdian Parkway Barton Road Street Improvements 31866 2/21/2018 County of Orange 2020 Walnut Ave 30134 3/6/2018 LACDPW Prine Carryon Road 30134 3/6/2018 Chino Development Corp. Prine Avenue Improvements Stages 1 & 2 30268 3/1//2018 Chino Development Corp. Prine Avenue Improvements Stages 1 & 2 30268 3/13/2018 Orize Trenprises Inc. OSO Parkway Bridge - FD2 - County of Orange 30166 3/15/2018 Caltrans (12-00/704) Route 91 Ramp Rehabilitation 30185 3/22/2018 Eador Construction San Gabriel River Bike Path Gap Long Beach 30289 4/4/2018 Chino Development Corp. Tract 19894 Block 4 30289 4/4/2018 Caltrans 07-30904 Route 110 30243 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30319 -4/10/2018 Riverock Real Estate Group Creentside Road Raised Crosswaits 30313 4/25/2018	\$ 408,570.0		1,860	Night Day	250 Working Days	Jim	Art	99.0%							_
30240 2/15/2018 Meridian Parkway Barton Road Street Improvements 31366 2/21/2018 County of Orange 2020 Walnut Ave 30134 3/6/2018 LACDPW Pine Canyon Road 30268 3/17/2018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2 30280 3/13/2018 Brightive Landscape Los Olivos 30594 3/14/2018 Orluz Enterprises Inc. OSO Parkway Bridge - FD2 - County of Drange 30184 3/12/2018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2 30185 3/12/2018 Chin Enterprises Inc. OSO Parkway Bridge - FD2 - County of Drange 30178 3/12/2018 Caltrans (12-02/704) Route 91 Ramp Rehabilitation 30185 3/22/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach 302869 4/4/2018 Chino Development Corp. Tract 1994 Block 4 302829 4/4/2018 Chino Development Corp. Tract 1994 Block 4 302829 4/4/2018 Chino Revelopment Corp. Tract 1994 Block 4 30282 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30314 4/10/2018 City of Santa Clarita Creekside Road Raised Crosswalls 30282 4/17/2018 Ci	\$ 1,580,580.0 \$ 1,112,085.0	2/8/2018 SL Ontario Merril Avenue Street Improvements	11,000 4,000	600 Day 250 Day	120 Working Days 90 Working Days	Miguel Miguel	Jim Jim	99.0% 99.0%							-
30134 30/2018 Chino Development Corp. Pine Canyon Road 30268 3//7/2018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2 30260 3/13/2018 Brightview Landscape Los Olivos 30594 3/14/2018 Oritiz Enterprises Inc. OSO Parkway Bridge - FD2 - County of Orange 30166 3/15/2018 Caltrans Colvos 30178 3/22/2018 Editrans (12-02/704) Route 91 Ramp Kehabilitation 30185 3/22/2018 Department of Transportation Route 51 Ramp Kehabilitation 30265 3/22/2018 Department of Transportation Route 51 Ramp Kehabilitation 30269 4/4/2018 Chino Development Corp. Tract 19694 Block 4 30284 4/10/2018 Caltrans 07-3009UA Route 110 302843 4/10/2018 Caltranta Creerside Road Raised Crosswils 30394 4/20/2018 Caltranta Creerside Road Raised Crosswils 30315 4/25/2018 California Professional Engineering 2016-03Slumy Traffic Signat@Green River&Montana	\$ 1,492,622.0	2/15/2018 Mendian Parkway Barton Road Street Improvements	8,000	400 Day	120 Working Days	Miguel	John W	99.0%						1	
30268 37/72018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2 30280 3/13/2018 Brightive Landscape Los Olivos 30584 3/14/2018 Oritiz Enterprises Inc. OSO Parkway Bridge - PD2 - County of Orange 30166 3/15/2018 City of Irwindale 2017/2018 Resurfacing Project 30178 3/21/2018 Caltrans (12-02/7/04) Route 91 Ramp Rehabilitation 30185 3/22/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach 30289 4/4/2018 Chino Development Corp. Tract 19934 Block 4 30289 4/4/2018 Caltrans 07-3009U4 Route 91 Route 110 302843 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30394 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30315 4/20/2018 City of West Covina Creekside Road Raised Crosswalks 30315 4/25/2018 Caltrans Cort Road & 1-215 - County of Riverside 30315 4/25/2018 Caltrans Creekside Road Raised Crosswalks 30315 4/25/2018 Caltrans Creekside Road Raised Crosswalks	\$ 85,562.7 \$ 3,288,999.0		65 13,261	10 Day 0 Day	90 Working Days 60 Working Days	Gordon Edward	Rick Jim	99.0% 99.0%			2/23/2018 4/17/2018	2/23/2018	2/28/2018	Docusion FedEx	
30280 3/13/2018 Brightview Landscape Los Olivos 30554 3/14/2018 Ortiz Enternises Inc. OSO Parkway Bridge - FD2 - County of Orange 30166 3/15/2018 City of Irwindale 2017/2018 Resurfacing Project 30178 3/21/2018 Caltrans (12-002/704) Route 91 Ramp Rehabilitation 30185 3/22/2018 Beador Construction San Gabriel Rver Bike Path Gap Long Beach 30285 3/22/2018 Department of Transportation Route 51 2-007804 30285 3/22/2018 Caltrans 07-3009U4 Route 118 Beador A 30285 3/22/2018 Caltrans 07-3009U4 Route 110 30284 4/10/2018 City of Santa Clarita Soledad Canyon Route 11 30282 4/17/2018 City of Santa Clarita Creetside Road Raised Crosswalks 30319 -4/10/2018 City of Santa Clarita Creekide Road Raised Crosswalks 30738 4/25/2018 California Professional Engineering 2016-03_ Slumy Traffic Signat@Green River&Montana 30766 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/20	\$ 3,685,159.7	3/7/2018 Chino Development Corp. Pine Avenue Improvements Stages 1 & 2	9,000	400 Day	160 Working Days	Miguel	Јепу	92.0%			4/6/2018		4/24/2018	(GULX	+
30166 3/15/2018 City of Irwindale 2017/2018 Resurfacing Project 30178 3/21/2018 Caltrans (12-02)/704 Route 91 Ramp Kehabilitation 30185 3/22/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach 30285 3/22/2018 Department of Transportation Route 512-007/04 30285 4/4/2018 Caltrans 07-3009U4 Route 110 30284 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30319 -4/10/2018 Riverrock Real Estate Group Centerstone Plaza 30315 4/25/2018 Caltron Professional Engineering 2016-03 Soledad Canyon Road Ruether 30315 4/25/2018 Caltron Professional Engineering 2016-03 Soury Traffic Signal@Green River&Montana 30315 4/25/2018 Caltron Professional Engineering 2016-03 Soury Traffic Signal@Green River&Montana 30304 4/36/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30303 4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Indian Wells Cook Street Rubberzed Pavement Overlay/	\$ 322,326.0	3/13/2018 Brightview Landscape Los Olivos		500 Day	30 Working Days	Michele	Rick	99.0%			4/19/2018	4/24/2018			Mid
30178 3/22/2018 Caltrans (12-02/704) Route 91 Ramp Rehabilitation 30185 3/22/2018 Department of Transportation San Gabriel River Bike Path Gap Long Beach 30285 3/27/2018 Department of Transportation Route 91 R2-00780A 302869 4/4/2018 Chino Development Corp. Tract 19694 Block 4 302829 4/4/2018 Caltrans 07-3009UA Route 110 302843 4/10/2018 Caltrans 07-3009UA Route 110 30282 4/10/2018 City of Santa Clanta Soledad Canyon Road Ruether 30282 4/17/2018 City of Santa Clanta Creexide Road Raised Crosswalls 30282 4/17/2018 City of Santa Clanta Creexide Road Raised Crosswalls 30319 4/25/2018 California Professional Engineering 2016-03Slumy Traffic Signat@Green River&Montana 30756 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 Lennar Homes La Palima 30339 4/30/2018 City of Ginian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 2,157,960.0 \$ 285,503.1	3/14/2018 Oruz Enterprises Inc. OSO Parkway Bridge - FD2 - County of Orange 3/15/2018 City of Invindale 2017/2018 Resurtacing Project	28,235 2,500	0 Night 25 Day	534 Working Days 30 Working Days	Gordon Edward	Art Jim	99.0% 99.0%			6/6/2018 4/6/2018	4/3/2018	6/20/2018	FedEx	+
30185 3/22/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach 30285 3/27/2018 Department of Transportation Route 5 12-007804 30285 4/4/2018 Chino Development Corp. Tract 19834 Block 4 302843 4/10/2018 City of Santa Clarita Soledat Canyon Road Ruether 302814 4/10/2018 City of Santa Clarita Soledat Canyon Road Ruether 302814 4/10/2018 City of West Covina Residential Street Hehabilitation at Various Locations 30315 4/25/2018 City of West Covina Residential Street Hehabilitation at Various Locations 30315 4/25/2018 California Professional Engineering 2016-03_ Siumy Traffic Signat@Green River&Montana 30766 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 974,781.3	3/21/2018 Caltrans (12-0Q7704) Route 91 Ramp Rehabilitation	4,920		40 Working Days	Edward	Doug	99.0%			4/9/2018	4/9/2018	4/17/2018	GSO	
30289 4/4/2018 Chino Development Corp. Tract 19894 Block 4 30229 4/5/2018 Caltrans 07-3009UA Route 110 30243 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30319 -4/10/2018 Riverrock Real Estate Group Centerstone Plaza 30261 4/17/2018 City of West Covina Residential Street Hehabilitation at Various Locations 30315 4/25/2018 Caltronia Professional Engineering 2016-03_Siumy Traffic Signat@Green River&Montana 30766 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 -4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 63,360.0	3/22/2018 Beador Construction San Gabriel River Bike Path Gap Long Beach	660	0 Day	30 Working Days	Jerry	Jorge	0.0%							
30229 4//5/2018 Caltrans 07-3009UA Route 110 30243 4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether 30319 -4/10/2018 Riverrock Real Estate Group Centerstone Plaza 30262 4/17/2018 City of West Covina Residential Street Rehabilitation at Various Locations 30319 -4/20/2018 City of Santa Clarita Creekside Road Raised Crosswalks 30738 4/25/2018 California Professional Engineering 2016-03_ Slumy Traffic Signat@Green River&Montana 30766 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 Lennar Homes La Palma 30339 5/2/2018 City of Simi Valley FY 2017-18 Annual Major Streets	\$ 8,330,362.0 \$ 3,360,000.0		58,550 11,000	0 Night 1,500 Day	180 Working Days 120 Working Days	Jim Miguel	Rick Jerry	99.0% 94.0%			4/13/2018				
30319 -4/10/2018 Riverrock Real Estate Group Centerstone Plaza 30262 4/17/2018 City of West Covina Residential Street Rehabilitation at Various Locations 30315 4/20/2018 City of Senta Clanta Creekside Road Raised Crosswalks 30738 4/25/2018 California Professional Engineering 2016-03_Slumy Traffic Signal@Green RiversMontana 30766 4/25/2018 Alkinson Scott Road & 1-215 - County of Riverside 30300 4/26/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Ginian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 29,757,315.0	4/5/2018 Caltrans 07-3009U4 Route 110	62,600	Night	610 Working Days	Jim	Doug	99.0%			4/6/2018	4/6/2018	4/13/2018	GSO	
30282 4/17/2018 City of West Covina Residential Street Rehabilitation at Various Locations 30315 4/20/2018 City of Santa Clanta Creexiside Road Raised Crosswalls 30738 4/25/2018 California Professional Engineering 2016/03_ Slumy Traffic Signat@Green River&Montana 30766 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 Lennar Homes La Palma 30348 5/2/2018 City of Ginia Wells Cook Street Rubbenzed Pavement Overlay/	\$ 167,766.0	4/10/2018 City of Santa Clarita Soledad Canyon Road Ruether	169 3,640	35 Night 0 Dav	15 Working Days	Maurice	John M	99.0%			6/13/2018	6/13/2018	6/19/2018	FedEx	6
30315 4/20/2018 Cily of Santa Clanta Creekside Road Raised Crosswalks 30738 4/25/2018 California Professional Engineering 2016-03_Slumy Traffic Signal@Green River&Montana 30766 4/25/2018 California Professional Engineering 2016-03_Slumy Traffic Signal@Green River&Montana 30766 4/25/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 Lennar Homes La Palma 30344 5/2/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 518,750.0 \$ 427,770.0	4/17/2018 City of West Covina Residential Street Rehabilitation at Various Locations	3,640 2,600	0 Day 10 Day	15 Working Days 40 Working Days	Maurice Cody	Randy Jim	99.0% 99.0%			5/15/2018	5/15/2018	6/11/2018	FedÉx	
30766 4/25/2018 Atkinson Scott Road & I-215 - County of Riverside 30300 4/26/2018 City of Simi Valley FY 2017-18 Annual Major Streets 30339 4/30/2018 Lennar Homes La Palma 30344 5/2/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 321,690.3	4/20/2018 City of Santa Clanta Creekside Road Raised Crosswalks	22	70 Night	30 Working Days	Greg	John M	99.0%					5, 172010		
30300 4/26/2018 City of Simi Valley FY 2017-18 Annual Major Štreets 30339 -4/30/2018 Lennar Homes La Palma 30348 5/2/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/	na \$ 93,387.0		5 35,435	45 Day 0 Day/Night	45 Working Days 360 Working Days	Edward Gordon	John W Art	99.0% 99.0%			9/6/2018		0/12/2010	FedEx	
30339 4/30/2018 Lennar Homes La Palma 30348 5/2/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/	\$ 3,281,677.5 \$ 1,517,770.0	4/26/2018 City of Simi Valley FY 2017-18 Annual Major Streets	8,000	200 Day	40 Working Days	Cody	John M	99.0%			5/18/2018	5/18/2018	9/12/2018 6/1/2018	FedEx	
30348 5/2/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/ 30595 5/2/2018 Alkineon Limonite & L15 - County of Riverside	\$ 1,072,000.0	4/30/2018 Lennar Homes La Palma	1,200	Day	90 Days	Michele	Rick	95.0%							May
	\$ 599,599.5 \$ 2,668,098.0	5/2/2018 City of Indian Wells Cook Street Rubbenzed Pavement Overlay/ 5/2/2018 Atkinson Limonite & I-15 - County of Riverside	3,780 31,582	20 Day 0 Day/Night	45 Working Days 356 Working Days	Maurice Gordon	John W Art	99.0% 99.0%			5/24/2018 9/13/2018	5/23/2018	5/31/2018 9/18/2018	FedEx FedEx	ac
30126 5/7/2018 City of Long Beach Runway 12-30 Rehabilitation	\$ 1,820,438.0	5/7/2018 City of Long Beach Runway 12-30 Rehabilitation	5,900	0 Day & Nite	60 Calendar Days	Gordon	Doug	99.0%			6/8/2018		6/8/2018	Fed Ex	
30347 5/14/2018 Lennar Homes Euclid Avenue Improvements	\$ 958,430.0	5/14/2018 Lennar Homes Euclid Avenue Improvements	1,800	Day	90 Days	Michele	Jim	65.0%							e
30367 5/14/2018 City of Hermosa Beach Hermosa Avenue Pavement Resurfacing Project 30374 5/17/2018 City of Rolling Hills Estates Resurfacing Project On Various City Streets FY 2018	\$ 2,160,864.4 \$ 978,788.0	5/14/2010 City of Relling Hills Estates Resurfacing Project On Various City Streets FY 2018	7,660		80 Working Days 50 Working Days	Edward Maurice	John M John M	99.0% 99.0%			6/26/2018	6/26/2018 6/19/2018	7/12/2018	FedEx	-

No.#	Date	Agency / Owner	Project Title	Bid Amount	AC Tonnage		-	Contract Time	P.M.	Supt	Coor	Completed	Removal	Concrete Removal	Grindings	Cont. Rec.	Date of Letter	Sent Back	Via	
0394 0518	5/22/2018 5/22/2018		Esplanade Ave Street Improvement (SJ-393) \$ N. Residential St. Improvements	381_410.00 409.877.00	2,600 1,070		Day Day	30 Calander Days 30 Working Days	Edward Maurice	John W Rick		99.0% 99.0%			-	6/19/2018 7/2/2018	6/19/2018 7/2/2018	7/24/2018	FedEx	_
0658	5/23/2018	County of Orange	John Wayne Airport	3,668,233.00	5,000		Day	365 Working Days	Jim	Doug		99.0%				7/16/2018	7/16/2018	7/23/2018	Drop Off	
0581	5/24/2018	ICDC	Portola Springs PA-6 Enclave 5B Phase 1 and 2	2,055,055.00	10,000	2,340	Day	120 Working Days	Miguel	Rick		99.0%						7/11/2018		
0410 0441	5/29/2018 5/29/2018	City of Paramount Pomona Unified School District	Paramount HivdArtenal Street Resultacing sintersection improvements at Diamond Ranch High	837,770.00	2,400 150		Day Day	35 Working Days 37 Calendar Days	Cody	Rick Jim		99.0% 99.0%				6/25/2018 6/14/2018	6/20/2018 6/14/2018	7/5/2018	FedEx	
0454	5/29/2018		Pavement Rehabilitation (Bid No. 2018-04)	274,103.00	11,320		Day	75 Working Days	Greg Maurice	John W		99.0%				6/14/2018	6/14/2018	6/19/2018 6/25/2018	Fedex	_
0417	5/31/2018	Department of Transportation	Route 15 (08-1H0904) \$	786,170.30	940		ay/Night	35 Working Days	Edward	Jeny		99.0%				6/12/2018	6/11/2018	0/20/2010	TOULA	
0689	6/1/2018		JOC - HCA Parking Lot \$	441,904.00	2,550		Day	20 Working Days	Gordon	Rick		99.0%				8/10/2018	5/9/2018	8/10/2018	Emailed	
0767	6/1/2018 6/4/2018	City of Inglewood Dennig Lorton and Associate	North La Brea Avenue Improvement \$ Rodeo Drive Grind and Overlay	4,540,992.00	8,850 20		Day Night	150 Working Days 1 Working Day	Gordon Maurice	John M Art		99.0% 99.0%				8/2/2018	7/11/2018	8/15/2018	FedEx	_
0429	6/5/2018		2018 Parking Lot Rehabilitation & ADA Improvements	436,735.00	666		Day	45 Working Days	Greg	Rick		99.0%				615/2018	6/15/2018	6/20/2018	Fedex	_
0443	6/5/2018		Dinah Shore Drive & Date Palm Improvement \$	2,023,923.00	8,111	1,470	Day	45 Working Days	Maurice	John W		99.0%	-			6/13/2018	6/13/2018	6/25/2018		
0481	6/5/2018 6/7/2018		Singleton Rd - Calimesa \$ 2018 Street Resurfacing Project No. 17-18-06	1.684,585.00	4,300		Day	60 Working Days	Michele	John W		99.0%							_	
0440	6/7/2018		Harley Knox Improvements	567,764.00 3,820,847.00	1,810 8,500	20 1,500	Day Day	30 Working Days 250 Working Days	Maurice Michele	John M John W		99.0% 99.0%				7/3/2018	7/3/2018	7/10/2018	FedEx	_
0474	6/12/2018		Acacia Avenue, California Street, 1st Street and Alley	349,895.00	638	300	Day	40 Working Days	Greg	John W		99.0%				7/6/2018	7/6/2018	7/17/2018	Fedex	
0475	6/14/2018	City of Jurupa Valley	Sale Routes to Schools \$	884 158.00	260	560	Day	40 Working Days	Greg	John W		99.0%				7/10/2018	7/10/2018	7/13/2018	Fedex	_
0486	6/19/2018 7/5/2018		San Dimas Avenue ET AL Pavement Rehabilitation \$ Heritage Tract 34406-3	1,627,965.00	9,620 5,245	230 1,200	Day Day	80 Working Days 40 Working Days	Maurice Michele	Jim John W		99.0% 99.0%				6/27/2018 10/12/2018	6/27/2018	7/12/2018	FedEx	
0580	7/9/2018		Olanda Street Improvement (Project No. 4011.67.908)	260.975.94	558		Day	45 Working Days	Edward	John M		99.0%				7/26/2018	7/26/2018	10/12/2018 8/7/2018	FedEx	_
0571	7/12/2018	Town of Apple Valley	Apple Valley Village Accessibility \$	484,565.00	1,640	360	Day	40 Working Days	Maurice	Jim		99.0%				7/12/2018		0///2010	1 Gally	
0573 0576	7/17/2018 7/17/2018		Local Street Rehabilitation (Project No. 7919) \$ Citrus Avenue from Santa Ana Avenue to Slover	1 747 202.00	11,400 552		Day	80 Working Days	Edward	Rick		99.0%				8/10/2018	8/8/2018	8/15/2018	FedEx	
0663	7/23/2018		The Resort	502,703.00 4,061,059.00	12,000		Day Day	35 Working Days 120 Working Days	Greg Miquel	Jim Jim		99.0% 99.0%								
0609	7/26/2018	City of Malibu	2017-18 Street Maintenance Project \$	654,979.86	1,867	0	Day	45 Working Days	Edward	John M		99.0%				8/8/2018	8/3/2018	8/10/2018	FedEx	_
0637	8/1/2018	City of Lynwood	Olanda Street & Virginia Ave Improvement Project \$	1,539,949.00	1,100	607	Day	70 Working Days	Edward	John M		99.0%				8/20/2018	8/20/2018			_
0713	8/1/2018 8/1/2018		2017/2018 Artenal and Minor Street Maintenance \$ Rossmoor Full Depth \$	7,489,107.00	22,800		Day Day	140 Working Days 365 Calendar Days	Jim Gordon	John W Rick	Kim	99.0% 99.0%		(i		8/7/2018	0/11/2010	0/40/00/1	Desusia	
416	8/1/2018	County of Orange	Rossmoor North & Collectors Grind & Overlay	1 749 702.68 2,347,264.42	U	U	Day	JUD Calendar Days	Gordon	RICK	Kim	99.0%				0///2018	9/11/2018	8/10/2018	Docusign	_
0674	8/9/2018	City of Westlake Village	Joint City Pavement Rehab. FY 18-19 \$	2,350,700.00	9,100	325	Day	75 Working Days	Cody	John M		99.0%				8/20/2018	8/16/2018	8/29/2018	FedEx	
0675	8/9/2018		Duncan Ave Street Improvements (4011.67.907)	1,137,855.78	1,600	544	Day	70 Working Days	Edward	John M		99.0%				8/31/2018	8/29/2018	9/10/2018	FedEx	
0695	8/16/2018 8/17/2018	C.S. Legacy Lennar Homes	Wells Ananza Sidewalk Improvements \$ Hentage Lakes 6 \$	25 300.00 796 000.00	220 3,500		Day Day	1 Working Day 45 Days	Maurice Michele	Art John W		99.0% 99.0%								_
0780	8/17/2018	Martin Harris Construction	Santa Fe Swap Meet \$	379 000.00	250		Day	30 days	Michele	Rick		99.0%				11/5/2018		1/2/2019	FedEx	-
1130	8/17/2018	Brightview Landscape	Saddleback College Running Track \$	295,000.00	2,100		Day	30 days	Miguel	Rick		99.0%					the management			
0741	8/22/2018		Slurry Seal for Camino de Estrella Project No. \$	999,259.15	0		Day		Brian	Rick		99.0%				8/22/2018	8/22/2018	8/30/2018	FedEx	-
0787	8/22/2018 8/23/2018	Riverside Transportation Departme County of San Bernardino	La Sierra Avenue \$ Cherry Avenue and Andel Drive \$	2,008,439.00 5,442,912.00	10,105 43,000		Day Day	30 Working Days 180 Working Days	Jim Jim	John W Jim		99.0% 99.0%				8/27/2018		0/00/0040	Jessika	
0758	8/23/2018	County of Riverside Purchasing an	Triple Crown Road/Fire Station 54 Road Paving Project s	95,645.00	240		Day	15 Working Days	Greg	John W		99.0%	_			0/2//2010		8/29/2018	Jessika	_
0702	8/24/2018	Skanska	Skanska Front Enlry \$	106,078.50	160		Day	2 Working Days	Maurice	Todd		99.0%					-			_
0947	8/30/2018		Route 405 12-0H0454 \$	345 000.00	4,100		Day	180 Working Days	Jim	Art		99.0%				-				
0748	9/4/2018 9/12/2018	City of Loma Linda City of San Bernardino	Pavement Rehabilitation at Various Locations (CIP#18- Intill Housing-Sidewalk and Street Improvements	419 966.15	2,950 3,000		Day Day	30 Working Days	Edward	John W Jim		99.0% 99.0%		1		9/21/2018	9/18/2018	11/0/0010	FordFit	_
0823	9/12/2018	County of Orange	Rossmoor Phase 1C - Crackseal and AC Repairs JOC	1,423,875.00	7,882		Day	60 Working Days 45 Working Days	Maurice Gordon	Rick		99.0%				11/8/2018 8/10/2018	10/30/2018	11/9/2018 8/10/2018	FedEx Emailed	-
0779	9/13/2018	City of Norco	Second St Widening st I-15 Inter \$	353,294.00	115	47	Day	45 Working Days	Edward	Jerry		99.0%					10/22/2018	10/26/2018		_
0860	9/13/2018	ICDC	Water Quality Basins 70A \$ Water Quality Basins 70B \$	1,504,996,48	600	250	Day	75 Working Days	Miguel	Rick		99.0%								
0861	9/13/2018 9/17/2018		Forterra	1,475,002.52	600 775		Day Day	75 Working Days 30 Working Days	Miguel Michele	Rick John W		99.0% 0.0%							_	
0809	9/17/2018	Five Point Communites	OCGP Sports Park Access Rd \$	642,341.00	300		Day	30 Working Days	Michele	Rick		99.0%				-				_
0840	9/18/2018		Florence Street Rehabilitation (Norwalk Blvd to \$	973,887.00	6,600	120	Day	35 Working Days	Maurice	Rick		99.0%				10/25/2018	10/12/2018	10/19/2018		-
0819	9/25/2018 9/25/2018	LACSD Belco Electric	Fill Below Grade Portions of Rail Spurs at Puente Hills	246,670.00	1,600		Day	45 Working Days	Maurice	Art		99.0%				40000040	10/16/2018	10/19/2018		_
0921	10/3/2018		Carnino Aventura Sidewalk Project & Thousand Paims	185.560.00 2.019,190.50	320		Day Day	10 Working Days 65 Working Days	Maurice Edward	John M John W		99.0% 99.0%				12/7/2018 10/24/2018	12/2/2018 10/23/2018	12/12/2018 10/26/2018		_
971	10/3/2018	Spectrum Construction	12-0N2704 Route 91 Weight Station \$	223,862.00	2,030			250 Working Days	Jim	Art		99.0%				10/24/2010	10/20/2010	10/20/2010	1 Cules	_
2489	10/8/2018		OC Streetcar \$	2,645,117.50	22,242			1095 Calendar Days	Jim	Art		75.0%				5/15/2020		5/15/2020	Docusign	
0814	10/10/2018		Chinon Trail Improvements \$ D5 Reach B East	389,737.00	1 850		Day	30 days 20 Days	Michele Michele	Rick Rick		99.0% 99.0%				10/29/2018		11/15/2018		_
0837	10/10/2018		Almond & Jurupa S	78,400.00	250		Day Day	15 Days	Michele	Jim		99.0%								
0877	10/11/2018		08-1E6104 Widening of Sholder and Installing Rumble \$	1,788,310.00	5,250	15	Day	80 Working Days	Edward	John W		99.0%				11/1/2018	10/30/2018	11/7/2018	GSO	
0886	10/11/2018 10/16/2018		Asphalt Pothole Repairs \$ 08A3010 Route 79- Hemet	516,300.00	900	150		365 Working Days	Cody	Art		99.0%								_
1698	10/18/2018		Route 5 12-0C8904 S	288,296.00	123 14,500		Day Night	20 Working Days 250 Working Days	Jim Jim	John W Art		99.0% 99.0%		_		2/14/2019 8/1/2019	2/14/2019 7/31/2019	2/28/2019	Fedex	_
1001	10/22/2018	Park West Rescom	Ridge Valley Parkway PCC Trail	200 351.80		460	Day	20 Working Days	Miguel	Todd		99.0%				1/30/2019	1/31/2013	2/11/2019	_	-
982	10/23/2018	City of Duarte	2018 Street Rehabilitation Project \$	526 840.00	3,300	20	Day	65 Working Days	Maurice	Jim		99.0%				11/19/2018	11/14/2018	11/21/2018	FedEx	-
0965 0847	10/25/2018 10/29/2018		Arkell Drive Street Improvements \$ Street Light Conduit Installation	209.660.00	391 20		Day	20 Working Days 1 Working Day	Greg	John M		99.0% 99.0%	_						_	
051	10/29/2018		Edinger/Atlanta/Warner Statiation	19,296.00 2,175,778,00	9,440		Day Day	70 Working Days	Maurice Jim	John M Rick		99.0%								
944	11/1/2018	City of Highland	Pavement Management Program Sectors B, C, D & E - \$	1,768,954,00	8,080	50	Day	60 Working Days	Maurice	John W		99.0%	n n			10/29/2018	10/29/2018	11/7/2018	FedEx	-
966	11/6/2018	Dennis Lorton & Associates	Bristol Street Parking Lot	42,400.00	280	0	Day	1 Working Day	Maurice	Art		99.0%							_	-
999 976	11/6/2018 11/16/2018	Caltrans City of Long Beach	Route 142 08-1E8504 \$ 15th Street Bicycle Boulevard, R-7075 \$	5 439 395.00 941,788.00	29,920		Night Day	160 Working Days	Jim Jerry	Rick		99.0% 99.0%				11/12/2010	11/8/2018	11/16/2018	FedEx	_
87	11/16/2018	Culver City	2019 Pavement Rehab Project \$	1,937,770,00	8,000		Day	120 Calendar	Cody	John M		99.0%					12/11/2018	11/10/2018	FOUEX	
D17	11/29/2018	Skanska USA Civil	SR-60 Truck Lanes \$	4,597,892.52	46,000	0 Da	y/Night	650 Working Days	Edward	Art		95.0%								5
029	11/29/2018		District 5 Phase II Master Backbone Street \$ Verdure Ave & Chandler Blvd, Improvement Project	1,377,896.00	5,800			40 Working Days	Greg	Rick		90.0%				12/5/2018		12/8/2018		
)35 46	12/5/2018	City of Burbank City of San Clemente	Verdugo Ave & Chandler Blvd. Improvement Project \$ Artenal Street Pavement Maintenance for Ave. Pico, \$	1.387.770.00	7,500 3,280			68 Calander Days 90 Working Days	Cody Jenry	Jim Rick		99.0% 99.0%				1/23/2019	1/16/2019 1/16/2019	1/28/2019	FedEx	_
569	12/19/2018	County of Orange	Prima Deschecha Land Fill - San Juan Capistrano \$	886,663.25		12 Da	yough		Gordon	Rick	Kim	99.0%				1/10/2019	1/10/2019			-
87	12/21/2018	Lennar Homes	Briggs Road Improvements \$	206,998.00	230		Day	5 Working Days	Miguel	John W		99.0%								1
214	1/4/2019 1/4/2019	Brookfield Homes Lennar Homes	The Groves - Whittier Streets Summit @ Rosena Perimeter Streets	4,648,913,90	22,000 21,528		y/Night	120 Days	Miguel	Jorge		99.0%				1/18/2019		2/26/2019		_
81	1/10/2019	Los Angeles County Department of		3,119,000.00	21,320		Day Day	80 Days	Miguel Jerry	Jim John M		99.0% 99.0%								
.07	1/10/2019	City of Downey	Paramount Boulevard Median Island Improvement \$	1,521,946.00	1,000	723	Day	75 Working Days	Greg	Rick		99.0%								
33	1/16/2019	Flatiron Corp.	Route 5 12-0K0224 \$	3,878,618.00	35,800	1	Night	990 Working Days	Jim	Art		60.0%				10110100				1
50 52	1/23/2019 1/29/2019	Leatherwood Construction City of Chino	D5 Rach B East (#20611801 & 20651801) \$ Slurry Seal Maintenance Work	115.289.00 372.805.00	630 0		Day Day	20 Working Days 120 Working Days	Greg Brian	Rick Darren		99.0% 99.0%				10/17/2018 2/18/2019	2/18/2019	1/29/2019	Fed-Ex FedEx	1
53	1/31/2019		Box Canyon Road	1 377 000.00	4,100		Day	55 Working Days	Cody	John M		99.0%					2/13/2019	2/20/2019 2/28/2019	FedEx	
71	1/31/2019	City of Downey	Fire Station Interim Construction	207,307.00	550		Day	36 Calendar Days	Greg	Rick		99.0%								-
15	2/4/2019		Western Ave. & In-Tract Improvements	3,658,952.04	10,000	2,000	Day	180 Days	Miguel	Jorge		99.0%				2/6/2019		2/15/2019		1
97 81	2/7/2019 2/12/2019	Doty Brothers City of Cathedral City	Edison Parking Lot \$ Ortega Road Widening and Sidewalk Gap Closure \$	97,082,00	315 640		eekend	EQ Marking Day	Greg	John M		99.0%				0440046	0/00/00/-		D	f
51 74	2/12/2019 2/14/2019	Flatiron Corp.	Redlands Passenger Rail Project (RPRP) Mainline	459.998.00 2.913.039.65	640 19,000		Day ay/Night	50 Working Days 520 Working Days	Maurice Gordon	John W Art		99.0% 99.0%				3/1/2019 6/28/2019	2/28/2019	3/13/2019 7/12/2019	Runner Kir FedEx	<u>, n</u>
78 -	2/20/2019	City of Arcadia	2018/2019 Pavement Rehab. Program \$	2,517,700.00	10,000		Day	90 Calander Days	Cody	Jim		99,0%				3/11/2019	3/7/2019	3/13/2019	FedEx	i
74	2/20/2019	LA Metro / Deco Pave	Metro Sound Wall #11-2 \$	2,092,660.00	14,770	0 1	Night	520 Working Days	Gordon	Art		99.0%				3/15/2019		4/17/2019	FEDEX	1
570	2/20/2019		Metro ODS - 10 FWY	21,500.00	16			250 Working Days	Gordon	Art	12	99.0%				2/18/2019	2/11/2019	2/22/2019	FedEx	Ĵ
208	2/21/2019 2/22/2019	City of San Gabriel Brookfield Homes	2018 CDBG Street Improvement Project Cash Contract s Archibald & ORR Improvements	377,334.00 515,623.00	1,200 500		Day Day	30 Working Days 40 Days	Maurice Miguel	Jim Jim	Kim	99.0% 99.0%				4/3/2019 2/25/2019	4/17/2019	4/8/2019	FedEx	
93	2/22/2019	Philbin Construction	Hentage Lake - Menifee	137,992.00	5		Day	20 Days	Miguel	John W		99.0%				2/18/2019		3/1/2019 2/26/2019		
90	2/25/2019	City of Paramount	FY 2018-2019 Various City Streets	1,737,700.00	6.000		Day	40 Working Days	Cody	Rick		99.0%			1	3/13/2019	0/7/0040	3/19/2019	FedEx	-

Job No.#	Date	Agency / Owner	Project Title	Bid Amount	AC Tonnage	Concrete	ay/Night	Contract Time	P.M.	Supt	Coor	Completed	Dirt Removal	Concrete Removal	Grindings	Cont. Rec.	Date of Letter	Sent Back	Via	
31206	2/26/2019	Duke Realty	24960 San Michele Road	191,952.00	1,450	Î Î	Day		Greg	John W	Î.	99.0%				3/4/2019		3/6/2019		-
31267 31213	2/27/2019 3/1/2019		Van Buren Phase 3 Street Improvements 5 Irvine Blvd. & Alton Signal Modifications 5	5,650,000.00	15,000	2,000	Day Day	180 Days	Miguel Greg	John W Rick	Kim	99.0% 99.0%						9. Š	_	
31213	3/7/2019	CEM Construction Corp/Baldwin Pa	Walnut Creek Nature Park Improvements	5 78,430.00	188	0	Day		Augustine	John M	Ted	99.0%	_			10/4/2019		10/4/2019		-
31229	3/12/2019		FY 18-19 Asphalt Paving Project	1 377 700.00	11,200	60 0	Day	90 Calander Days	Maurice	John W	Kim	99.0%				5/17/2019	5/16/2019	5/22/2019	FedEx	
31273 31282	3/13/2019 3/14/2019		Irvine Center/Odyssey Subsidence Repair \$ Route 5 (12-0R2704)	41,158.00 4,797,622.00	0 32,800	0	Day Night	None 110 Working Days	Greg Jim	Doug Rick		99.0% 99.0%								-
31316	3/18/2019	City of Lake Forest	Citywide Roadway Improvement	4,988,350.00	16,359	500	Day	110 Working Days	Jim	Rick	Kim	99.0%								
31261 31309	3/19/2019 3/19/2019		2018 Pavement Management Program (REVIVE 25) Annual Pavement Maintenance Various Locations	2,720,103.65 5,369,997.00	5,000	0 305	Day Day	60 Calendar Days 180 Calender Days	Brian Maurice	John W Doug	Kim Kim	99.0% 99.0%				5/1/2019 4/11/2019	4/25/2019 4/11/2019	5/6/2019 4/18/2019	FedEx	-
31370	3/27/2019	City of Santa Ana	First and Raitt	799,096.00	810	100	Day	30 Working Days	Jim	Rick	Kim	99.0%				4/26/2019	4/26/2019	4/29/2019	Fedex	
31277	3/28/2019		Street Rehabilitation Program S Circle Park Driveway Project	5 1,111,700.00	6,000	500	Day	60 Working Days	Maurice	John M	Ted	99.0% 99.0%				4/12/2019	4/10/2019	4/17/2019	FedEx	
31290 31286	3/28/2019 4/2/2019		Street and Alley Rehabilitation Improvements	268,576.00 4,259,116.55	100 22,000	75 514	Day Day	30 Working Days 155 Working Days	Augustine Edward	John M Jim	Ted Kim	99.0%				4/18/2019 5/8/2019	5/7/2019	5/13/2019	FedEx	-
31319	4/9/2019	City of Huntington Beach	Residential Overlay Maintenance Zone 6	3 546 889.00	27,795	335	Day	60 Working Days	Maurice	Doug	Ted	99.0%				5/23/2019	5/20/2019	6/10/2019	FedEx	
31515	4/9/2019 4/17/2019		Caltrans (07-3W8504) Route 1 - Malibu S Caltrans (12-0R2504) Route 90	800,300.00	5,300 23,000	0	Night Night	155 Working Days 60 Working Days	Maurice	Art Rick	Kim	99.0% 99.0%				4/1/2019	4/1/2019	4/11/2019	Fedex	
31382 31348	4/11/2019		Euclid Street Rehab	3,878,948.00 3,787,500.00	19,000	300	Day	80 Working Days	Jim Cody	Doug	Kim	99.0%				5/16/2019	5/15/2019	5/22/2019	FedEx	-
31350	4/24/2019	City of Simi Valley	Minor Street Rehab SV 19-08	510,124.25	3,650		Day	40 Working Days	Edward	John M	Ted	99.0%				5/16/2019	5/15/2019	5/17/2019	FedEx	
31359 31355	4/24/2019 4/25/2019	Hemet Unified School District City of San Bernardino	Playground Asphalt Removal & Reconstruction S Pavement Rehab 10 Locations	3 136,999.00 4,383,952.00	1,080	0 2,400	Day Day	10 Working Days 120 Working Days	Maurice Edward	John W John W	Kim	99.0% 99.0%				5/15/2019 4/30/2019	5/15/2019 4/30/2019	6/4/2019 6/17/2019	FedEx FedEx (Agre	omenty
31371	4/20/2019		Old Topanga Rd Improvemet Project	1.585.842.00	7,800		Day	40 Working Days	Edward	John M	Ted	99.0%				6/4/2019	5/20/2019	6/6/2019	FedEx	CHICHLY
31531	4/30/2019		El Prado Road Reconstruction	2 392 367.80	6,950	695	Day	ca	Gordon	Jerry	Kim	99.0%				5/22/2019	5/23/2019	5/24/2019	Fedex	
31383 31385	5/1/2019 5/1/2019		Baker Ranch S Mt San Antonio College Field S	80,626.00 385,000.00	1,000	0	Day Day		Maurice Maurice	Art		99.0% 99.0%								
31543	5/2/2019		Ontario Ranch Road	510,510.00	1,700	150	Day	20 days	Miguel	Jim	Kim	99.0%								-
31561	5/2/2019		Road Repair Services (Pothole Repair Remove &	1,019,100.00	4,000	0	Day	180 Working Days	Augustine	John M	Ted	99.0%				5/0/0040	F (0)(0040			
31486 31402	5/3/2019 5/7/2019	City of Long Beach County of Ventura	Annual Contract for Major & Secondary Highway S Pavement Resurfacing Yerba Buena Area	10,000,000.00 3,919,808.95	25,000	60	Day Day	365 Days 75 Working Days	Jerry Edward	Jorge John M	Ted Ted	99.0% 99.0%				5/3/2019 5/22/2019	5/2/2019 5/21/2019	8-May 5/30/2019	Fed-Ex FedEx	-
31407	5/8/2019	City of San Clemente	Street Rehabilitation for S. Ave La Esperanza and Ave	384,055.00	2,120	18	Day	35 Working Days	Augustine	Rick	Ted	99.0%				6/13/2019	6/10/2019	0.00/2010		
31413 31414	5/8/2019 5/10/2019		Boys Republic Asphalt Pavement S LAVVA - ITF Bus Drop Off	90,000.00	\$ 1,200.00	0	Day Day		Maurice Gordon	John W Todd	Kim	99.0% 99.0%								-
31414	5/10/2019	J & M Concrete	Disneyland Syborn Parking Lot	5 90,300.00 5 86,349.88	0	0	Day		Gordon	Todd		99.0%								
31416	5/10/2019	City of Santa Fe Springs	Santa Fe Springs Rd. Improvement	2,011,700.00	\$ 9,500.00	600	Day	40 Working Days	Cody	Jorge	Ted	99.0%				5/14/2019	5/10/2019	5/17/2019	FedEx	
31425 31447	5/10/2019 5/15/2019		South Gate Manholes Asphalt Paving Services at Temecula Valley Regional	47.840.00 295.657.98	0 2,225	0	Night Day	280 Working Days 30 Working Days	Gordon Augustine	Darren John W	Kim	99.0% 99.0%								
31510	5/16/2019	Guy F. Atkinson	Route 60/710	5 019 753.00	24,100		Night	850 Working Days	Jim	Art		99.0%								
31451	5/20/2019		Normandie ave. Street Improvements	677,770.00	3,700 820		Day	30 Working Days	Edward	John M	Ted	99.0% 99.0%				6/13/2019	6/12/2019	6/19/2019	FedEx	-
31672 31457	5/20/2019 5/21/2019		Newhope Street Rehab. & Resurfacing	221,433.00	8,500	20 500	Day Day	60 Calendar Days 45 Working Days	Augustine Maurice	John W Rick	Kim	99.0%				8/20/2019 6/5/2019	6/5/2019	8/20/2019 6/11/2019	US Mail FedEx	-
31485	5/22/2019	Caltrans	Route 15, 74, 79 Contract No. 08-1,15604 5	3 655 135.00	15,222	10	Both	65 Working Days	Jim	John W	Kim	99.0%								
31502 32361	5/22/2019 5/22/2019		2019 Pavement Management Project (REVIVE 25) JOC Pavement Maint-Cowan Heights- FY 19-20	3 696 389.42 2,584,747.69	5,000	0	Day Day	80 Working Days 365 Calendar Days	Brian Gordon	John W Rick	Kim	99.0% 99.0%				7/1/2019	7/1/2019	7/15/2019	FedEX Agree	ement a
31463	5/23/2019	City of Downey	Firestone Boulevard Street Improvement Project	1,648,493,00	5,630	350	Both	70 Working Days	Greg	Rick	Kim	99.0%				6/14/2019	6/13/2019			-
31565	5/23/2019	City of Bellflower	Eucalyptus Avenue Street Improvements 2019-20 Pavement Management Program System 4	606,436.00	190	115	Day	90 Working Days	Gordon	Rick	Kim	99.0%				6/18/2019	0.000-00-0	7/8/2214	FodE	
31475 31492	5/28/2019 5/29/2019		2019-20 Pavement Management Program System 4 8 Bolsa Avenue	5 1 414 770.00 1 123 923.00	12,900	370	Day Day	70 Working Days 50 Working Days	Edward	Jim Doug	Kim Ted	99.0% 99.0%				6/26/2019 5/30/2019	6/20/2019 5/30/2019	7/2/2019 5/31/2019	FedEx Emailed	-
31524	5/29/2019	City of Santa Ana	Local Street Preventative Maintenance FY 2018-19	5 1 716 649.00	2,500	620	Both	65 Working Days	Maurice	Rick	Kim	99.0%				6/19/2019	7/3/2019			1
31590 31700	5/29/2019 5/29/2019		08-1J4104 Route 71 08-1H3404 Precast Slab and Curb Ramp Replacement	89,456.00 394,015.00	500		Night Night	140 Working Days 90 Working Days	Jim Edward	Art	-	99.0% 99.0%				6/20/2019	6/19/2019	6/24/2019	Fed-Ex	
31700	5/30/2019		Annual Roadway Resurfacing Project FY 2018/2019	2,025,451.00	2,191 2,320	1,200	Day	80 Working Days	Greg	Rick	Kim	99.0%				6/25/2019	6/25/2019	6/28/2019	Fed-Ex	
31970	5/30/2019	RSB Group Inc.	(08-1H6404) Rte#210 EB Highland Ave Off-Ramp 5	132,500.00	610		Night	80 Working Days	Edward	Art		99.0%								
31690 31494	5/31/2019 6/3/2019	J. Francis City of Palm Springs	08-1J204 Route 15,91,215 Runway Cores - Palm Springs Airport	5 74,726.00 5,773.37	83 0	0	Night Night	122 Working Days 1 Working Day	Jim Gordon	Art John W	Kim	99.0% 99.0%							-	
31495	6/3/2019	City of Moreno Valley	FY 18/19 Citywide Pavement Rehab.	4,430,000.00	21,000	500	Day	160 Working Days	Maurice	John W	Kim	99.0%				6/20/2019	6/20/2019	6/26/2019	FedEx	
31498	6/4/2019		FY 18/19 Major Arterial Rehab. RMDJOC 6635 Pavement Preservation (Seal Coats)	1,309,989.00	8,900	100	Day	90 Working Days	Edward	Jim John M	Kim	99.0%				6/19/2019	6/18/2019	6/25/2019	FedEx	-
31500	6/4/2019 6/5/2019	County of Los Angeles City of Chino Hills	Rolling Ridge Drive Pavement Rehab.	4,700,000.00	7,300	350	Day Day	365 Calendar Days 50 Working Days	Jerry Maurice	John M John W	Ted Kim	99.0% 99.0%				7/11/2019 6/11/2019	6/17/2019 6/11/2019	7/16/2019 6/12/2019	FedEx FedEx-(Agre	ement (
31509	6/5/2019	City of San Bernardino	Pavement Rehab at 12 Locations	4,434,390,49	19,710	732	Day	120 Working Days	Edward	John W	Kim	99.0%				6/18/2018	6/17/2019	6/18/2019	Hand Deliver	red (Agr
31740 31526	6/5/2019 6/10/2019	County of Orange City of Temecula	John Wayne Airport- Pavement Maintenance & Repair Pavement Rehabilitation Program - Citywide - Rancho	3,914,178.00 855,333.00	5,000 6,100	250 1,060	Night Day	365 Calendar Days 60 Working Days	Jim Maurice	John W	Ted Kim	99.0% 99.0%	_			7/31/2019 6/13/2019	7/31/2019 6/13/2019	8/9/2019 7/2/2019	Fedex FedEx	1
31602	6/10/2019		Lincoln Street Pavement Rehabilitation & Striping	833,360.25	5,800	5	Day	45 Working Days	Gordon	John W	Kim	99.0%				0/10/2019	0/10/2018	112/2019	TOULA	
31528	6/12/2019	Exclusive Towing	Towing Yard Street Improvements	27,292.00	160		Day		Greg	John W	Kim	99.0% 0.0%							_	
31882 32156	6/18/2019 6/19/2019	Hal Hayes Construction James W, Fowler Co,	Chino Creek Levee Asphalt Repaying Montezuma/Mid City Pipeline- San Diego	162,233.56 1,355,924.86	1,420	0 1	Day Day/Night	640 Working Days	Greg Gordon	Art		0.0%							-	
31830	6/20/2019	County of Riverside	Runway 18-36, Taxiway A - French Valley Airport	2,046,047.00	10,250	0	Day	180 Calender Days	Gordon	John W	Kim	99.0%				10/29/2019	7/29/2019	11/20/2019	Delivered	
31582 31644	6/27/2019 7/1/2019	City of Downey City of Claremont	FY 2018/19 Slumy Seal Project District 3 CIP No. 19-12 Second Street And Bonita Avenue Resurfacing Project,	313,425.87 84,844.00	0 400	0	Day Day	30 Working Days 14 Working Days	Brian Maurice	Rick Jim	Kim Kim	99.0% 99.0%				6/27/2019 7/24/2019	6/27/2019 7/24/2019	7/1/2019 7/25/2019	FedEx FedEx	6
31642	7/2/2019	City of Hemet	2018-19 Slurry Seal Project, CIP No. 5688 5	815 575.00	120	ŏ	Day	50 Working Days	Brian	John W	Kim	99.0%				8/19/2019	8/15/2019	8/26/2019	FedEx	1 5
32160 31621	7/2/2019 7/3/2019		Contract for Local Street Improvements Project R-7153 CDBG Colt 18-2-03K, 18-1-03K, 18-1-03I	40,000,000.00	75,000 682	5,000 356	Day	2 years 90 Working Days	Jerry	Jorge	Kim	50.0% 99.0%				12/4/2019				1
31621	7/3/2019	City of Colton Sema Construction	(08-1C29U4) Route #10 Landscape Improvement	176,766.00 120,821.40	662 860		Day Night	250 Working Days	Augustine Edward	John W Árt	- Allin	99.0%			-	12/4/2019	10/11/2019		1	1
31666	7/9/2019	City of Irvine	Irvine Business Complex (IBC) Sidewalk	1 233 233.00			Day	160 Working Days	Jerry	Rick	Kim	99.0%				8/2/2019	8/2/2019	8/9/2019	FedEx	1 - 5
31671 31723	7/9/2019 7/18/2019	Landsea/Murow CM Park West Rescom	Archibald Street Improvements District 1 West Novel Segment 2	969.000.00 138.726.00	2,000	700 300	Day Day	35 days 360 Days	Miguel Miguel	Jim Rick	Kim	99.0% 95.0%								-
31686	7/19/2019	Giantech Construction Inc.	57 Wheeler Avenue	86,265.00	425	0	Day		Augustine	Jim		99.0%								1
31719	7/29/2019	Pavement Recycling Systems, Inc.	Harco Street ET AL	878 583.34	4,997	0	Day	260 Working Days	Edward	Jorge	B.47	99.0%								1
31893 31705	7/29/2019 7/30/2019	Brightview Landscape City of Laguna Niguel	District 5 Area 1 Chinon, Cadence, Trebel Alicia Parkway Arterial Pavement Rehabilitation	186,000.00 2,348,777.00	17,000	400 300	Day Day	120 Days 60 Working Days	Migue! Maurice	Rick Rick	Mindie Kim	98.0% 99.0%				8/23/2019	8/23/2019	9/12/2019	FedEx	-
32311	7/30/2019	Los An eles County Department of	RMDJOC6647 Pavement Reconstruction (Sustainable)	5.100.000.00				1 Year	Jerry	Doug	Deonne	99.0%				8/7/2019	8/6/2019	5/12/2019	, out A	
31750 31829	7/31/2019 8/1/2019	Lewis Management City of Alhambra	Citrus Avenue AC Grind & Overlay S FY 17-18 SB1 Street Rehabilitation	544,000.00		15 225	Day	30 Days 65 Working Days	Miguel Gordon	Jim Jim	Kim Kim	99.0% 99.0%				9/19/2019		0/37/0040	FedEx	1
31829	8/1/2019	California Professional Engineering	Santa Anita Ave Corridor	2,682,820.50	20	50	Day Day	55 WORKING Days	Maurice	John M	Ted	99.0%				3/13/2019		9/27/2019	FEUEX	-
32780	8/1/2019	Thomas Nagy Construction	(PLR) 5500 Sepulveda Blvd - Culver City 5	36,672.00	80	0	Day	2 Working Days	Augustine	John M	Ted	99.0%								
31834 31780	8/2/2019 8/5/2019	GM Grading Carmel Partners	Perns Offsite Expo Asphalt	1 133 983.00 41 023.00	2,880 100	2,000	Day Day		Greg Greg	John W John M	Kim Ted	99.0% 99.0%	_							
31864	8/6/2019	Peterson Chase	Route 91,110 07-331604	97,487.00	403		Night	90 Working Days	Jim	Art		99.0%								
31721	8/8/2019	City of Stanton	2019 Citywide Street Resurfacing Route 15 Contract No. 08-1F1424	1,206,869.00	8,065	50	Day	60 Working Days	Edward	Doug	Ted	99.0%				8/20/2019	8/20/2019	8/23/2019	FedEx	1
32305	8/15/2019 8/21/2019	Myers & Sons Construction Chumo Construction	Route 15 Contract No. 08-1F1424 Route 57	1 256 166.00		0	Night Night	400 Working Days 440 Working Days	Jim Jim	Art		99.0% 0.0%				3/2/2020		3/3/2020	Mail	
31775	8/22/2019	City of Norco	Vine Avenue, Driftwood PI, Half Moon Ct	409.970.00	3,450	67	Day	30 Working Days	Edward	Јепу	Kim	99.0%				9/20/2019	9/19/2019	9/24/2019	Hand Deliver	ed
31778 31831	8/22/2019	County of San Bernardino Westlake Village	CSA 70, R47 Road Slurry Seal Annual Street Resurfacing FY 19-20	63,193.74	0 2,550	0	Day	30 Working Days	Brian Gordon	Darren John M	Kim	99.0% 99.0%			-	9/5/2019 10/4/2019	9/5/2019	9/13/2019	FedEx Delivered	1
31831 31790	* 8/23/2019 8/27/2019		Asphalt CAP Summer 2019	1,110,900.31		0	Day Day	35 Working Days 15 Working Days	Augustine	John M John M	Deonne Ted	99.0%				9/4/2019		10/10/2019	Delivered	-
31867	8/27/2019	C.S. Lenacy	Verdugo Street Beautification Project	77,710.40	120	0	Day		Maurice	Art	Rick	99.0%				9/24/2019	9/24/2019	10/2/2019	FedEx	
32054 31843	8/28/2019 9/3/2019	City of San Fernando City of Loma Linda	Glenoaks Blvd. Street Resurfacing and Highway Safety s Pavement Rehabilitation at Bellaire St., Taylor St., 5	2,399,784.00	5,900 1,200	1,300 40	Day Day	80 Working Days 15 Working Days	Maurice Maurice	John M John W	Deonne Kim	99.0% 99.0%				11/25/2019 9/11/2019		12/10/2019 9/23/2019	FedEx FedEx	-
31884	9/5/2019	City of Corona	Street Maintenance & Rehabilitation 2017-22 (rebid)	6,244,244.00	29,809	202	Day	60 Working Days	Jerry	Jerry	Kim	99.0%				0/11/2019	011/2019	9123/2019	I CULA	-
31872	9/10/2019		Gate 36 Rehabilitation	155 120.00	540	0	Day		Gordon	Jim	Ted	99.0%			1					

Job No.#	Date	Agency / Owner	Project Title	Bid Amount	AC Tonnage	Concrete	Day/Nigh		P.M.	Supt	Coor	Completed	Dirt Removal	Concrete Removal	Grindings	Cont. Rec.	Date of Letter	Sent Back	Via	
31890	9/10/2019	Leonida Builders Inc.	McSweeny Farms - Phase 2 - Hernet \$	113,342.00	1,419	0	Day	2 Working Days	Augustine		Kim	5.0%				9/19/2019	Ť	10/10/2019		
31895 31844	9/10/2019 9/12/2019	Leonida Builders Inc.	McSweeny Farms - Phase 3 - Hemet \$ Road Repair Service - 2	37,052.00 2,249,880.00	315 8,000	0	Day Day	2 Working Days 180 Working Days	Augustine Augustine	John W John M	Kim Ted	0.0%				9/19/2019 12/5/2019		10/10/2019	FedEx	_
31916	9/17/2019	Caltrans	Route 79 08-1F6904	7,642,529,00	42,000	0	Night	150 Working Days	Jim	John W	Kim	99.0%				10/4/2019				
32037	9/17/2019	Powell Construction, Inc.	(07-276104) Rie #110_Construct Maintenaince Vehicle \$	89,590.19	180		Night	140 Working Days	Edward	Art		99.0%								
31862 32174	9/18/2019 9/18/2019	City of Santa Ana California Professional Engineering	Edinger Protected Bike Lanes \$ Caltrans 12-0P0104 Route 39	1,663,906.00 134,025.00	3,190 40	707	Day Night	150 Working Days	Augustine Maurice	Rick John M	Mindie Ted	99.0% 99.0%				10/2/2019		10/9/2019	FedEx	_
31976	9/19/2019	City of Orange	CDBG FY 18-19 Maple Neighborhood, Sacramento	536,244.00	1,820	185	Day	60 Calendar Days	Maurice	Doug	Ted	99.0%				10/9/2019	10/9/2019	10/21/2019	FedEx	+
31899	9/23/2019	Duke Realty	Perns & Nandina Paving Project	168,384.50	1,175	0	Day		Greg	John W		99.0%				10/1/2019				
31897 31925	9/24/2019 9/24/2019	Calpro Max/City of La Verne Kaiser Permanente	Regional Commuter Bicycle Gap Closure Project \$ Normandie N. Parking Lot (Harbor City \$	238 584.00 40 070.00	750 70	0	Day Day	10 Working Days 2 Working Days	Augustine Augustine	Jim John M	Ted	99.0% 99.0%							11	
31977	9/24/2019	Commerce Colony	Archibald Street Improvements \$	1,949,000,00	3,500	3,000	Day	60 Working Days	Miguei	Jim	Kim	98.0%				11/4/2019	11/4/2019		1	
31982	9/26/2019	City of Glendora	Loraine Avenue Street Rehabilitation - Palm Drive to	1,438,622.00	10,250	220	Day	45 Working Days	Maurice	Jim	Kim	99.0%				10/17/2019		10/21/2019		
31900 31908	10/1/2019 10/2/2019	County of San Bernardino Fullmer Construction	Chino_Philipelphia Street \$ Casmalia Street Improvements	1,278,376.38 655,000,00	4,225	242	Day Day	60 Working Days	Edward Miguel	Jim Jim	Mindie	99.0% 99.0%				12/2/2019	12/2/2019	12/5/2019	FedEx	_
32212	10/2/2019	City of Industry	Arenin Avenue Reconstruction	3.053.713.50	3,840	1,700	Day	120 Working Days	Gordon	Jim	Mindie	99.0%				10/30/2019				
31954	10/7/2019	City of Santa Ana	Edinger Avenue Rehabilitation	688 956.00	2,150	100	Day	90 Working Days	Jim	Rick	Mindie	99.0%								
32086 32159	10/11/2019 10/15/2019	City of Riverside Ortiz Enterprises Inc.	Magnolia Avenue Improvements Bid No. /631 S Route 5 Contract No. 12-0K0214	13,138,339.25 4,915,852,50	43,228 45,300	2,700 0	Day Night	200 Working Days 1110 Working Days	Jim Jim	John W Art	Mindie	99.0% 50.0%		_	_		_			
32223	10/15/2019		City of Burbank - Traffic Responsive Signal System	133,880,00	20	70	Day	15 Working Days	Maurice	John M	Mindie	99.0%								_
32031	10/17/2019	City of Chino Hills	Pine Avenue Pavement Rehabilitation Project, Project	192 444.00	920	0	Day	20 Working Days	Maurice	John W	Kim	99.0%				10/18/2019	10/18/2019	10/21/2019	FedEx	
32231	10/17/2019	SBCTA/Atkinson	SR-210 Lane Addition \$	6,349,608.00	69,400		Day & Nit		Gordon	Art	Mindie	78.0%				1/8/2020		1/13/2020	FedEx	
31969 32083	10/23/2019 10/24/2019	City of Santa Ana City of Santa Ana	Bristol Street and Edinger Avenue Class II Bike Lanes S Bristol Street Rehabilitation	607,839,99 639,608.00	250	126 30	Day Day	90 Working Days 90 Working Days	Edward Jim	Rick	Mindie Mindie	99.0% 99.0%				11/27/2019	11/27/2019	12//05/2019	FedEx	_
32147	11/4/2019	City of Irwindale	2019 Resurfacing Project:Longden Avenue From Live	819 777.00	6,720	20	Day	50 Working Days	Maurice	John M	Ted	99.0%				11/18/2019	11/18/2019	12/5/2019	FedEx	
32225	11/5/2019	Pavement Coatings	2020 Pavement Management Program (Neighborhood \$	330,995.00	3,200	0	Day	60 Working Days	Maurice	Art	T -1	99,0%		_						
32022 32148	11/12/2019 11/12/2019	City of Lynwood City of Desert Hot Springs	Lynwood ATP Cycle Community Linkages \$ Paim Drive Street Lighting and Safety improvement \$	2,053,968.60 2,099,222.00	2,636 5790	1,209 200	Day Day	60 Working Days 85 Working Days	Edward Maurice	Doug John W	Ted Mindle	99.0% 99.0%				11/27/2019	11/27/2019 11/20/2019	12/5/2019	FedEx	_
	11/12/2019	Hathaway Dinwiddie	Spectrum Terrace Phase 2 \$	799,827.00	7330	0	Day		Greg	Rick		0.0%								
32092 32260	11/14/2019 11/19/2019	City of El Monte	Slurry Seal & Pavement Resurtacing Project - Phase 1 \$ Route 91 Weigh Station	1 325 747.00	2000	285	Day	45 Working Days	Gordon	Jim	Mindie	99.0%				12/16/2019		12/19/2019	FedEx	
32260	11/19/2019	Spectrum Construction Group City of Brea	Asphalt Grind & Overlay 5	221,517.00 33,410,00	1,900	0	Night Night	150 Working Days 1 Working Day	Jim Augustine	Art Rick	Ted Mindie	99.0% 99.0%				11/27/2019				_
32056	11/21/2019	City of Los Alamitos	Noel Street Pavement Rehab \$	116,565.00	780	10	Day	30 Working Days	Augustine	Rick	Mindie	99.0%				12/9/2019				
32063	11/21/2019	City of El Monte	Ramona Blvd & Valley Blvd. Intersection \$	2,997,428.00	2,025	1,100	Day	120 Working Days	Augustine	Jim	Mindie	99.0%				12/10/2019	12/3/2019	1/10/2020	FedEx	
32116 32074	11/21/2019	Landsea Homes City of Montebello	Merrill Avenue Street Improvements Street Improvements	1 459 459.00 133 352.00	4,500	1,400 50	Day Day	85 Working Days 15 Working Days	Miguel Augustine	Jim Rick	Mindie Mindie	99.0% 0.0%				12/16/2019				_
32251	12/3/2019	City of El Monte	Slurry Seal and Pavement Resurfacing - Phase 2	3 462 905.50	3000	0	Day	60 Working Days	Gordon	Jim	Mindie	99.0%				1/6/2020		1/13/2020	10000	-
32087 32234	12/5/2019 12/10/2019	County of San Bernardino Transpo Sukut Construction	Montclair ADA Ramps & Sidewalk \$ Cow camp and street Improvements PH 2B	940,699.00	560 45000	500 1500	Day	30 Working Days 225 Working Days	Augustine	Rick	Mindie	99.0% 99.0%				12/18/2019	4/07/0000	12/20/2019		
32143	12/10/2019	Tolar Manufacturing Inc.	Parking Lot Slurry	4,400,000,00 38,070,00	45000	5	Day Day	10 Working Days	Miguel Augustine	Rick Jerry	Mindie	99.0%				2/3/2020	1/27/2020	2/10/2020	MAIL	
32141	12/17/2019	Pardee Homes	Highland Springs Avenue Street Improvements	6 891 770.93	12230	1530	Day	220 Working Days	Greg	John W		99.0%				1/21/2020	1/14/2020	1/23/2020	DocuSign	
32172	12/18/2019	City of Westminster	Citywide Overlay	1,131,621.00	7065	150	Day	60 Working Days	Jim	Doug	Ted	99.0%				1/3/2020	1/22/2020			
33035 32167	12/18/2019 12/19/2019	County of Orange JB Paving & Engineering	JOC Maintenance & Facilities Slurry & Paving Services \$ YVWD - Slurry \$	1.500.000.00 53,510.00	U	٥	Day & Nit Day	 365 Calendar Days 	Gordon Greg	Rick John W	Mindie	99.0% 99.0%				3/2/2020 1/8/2020		3/6/2020 1/24/2020	docusign MAIL	
32171	1/2/2020	Pardee Homes	Wilson Street Improvements \$	1,154,144.00	5390	740	Day		Greg	John W	Mindie	99.0%				1/21/2020	1/14/2020	1/23/2020	DocuSign	_
32253	1/6/2020	County of Orange	OCPW Fruit Street - Pave \$	314,576.24	960			e 90 Calander Days	Gordon	Rick	Mindie	99.0%							11	
32249 32259	1/7/2020	City of Menifee Chumo Construction	CIP 20-10 Andalus/a/Belcanto Street Resurtacing \$ Route 133	1.009.844.00 377.819.00	5580 1500	410	Day Night	40 Working Days 250 Working Days	Maurice Jim	John W Art	Gio	99.0% 99.0%	-			1/17/2020 2/7/2020	01/17/2020	1/29/2020 2/20/2020	FedEx Mail	_
32507	1/7/2020	Belco Elecnor Group	City of Burbank - Midtown Commerical Traffic Signal	272,800,00	20	190	Day	15 Working Days	Maurice	John M	Deonne	99.0%				DHEOLO		2120/2020	IVIDII	
32554	1/9/2020	Stephen Doreck	Brea _ Puente Street Improvements \$	1,921,565.50	13,366	196		165 Working Days	Edward	Rick	Gio	99.0%				6/12/2020	6/12/2020	6/14/2020	FedEx	
32188 32242	1/14/2020 1/14/2020	County of Ventura Walsh Construction	Malibu_Yerba Buena Road Resurfacing \$ FEDEX Express ONTR Expansion Project \$	2,298,467.40 329,765.00	6,632	60	Day Day	80 Working Days	Edward Gordon	John M Art	Deonne	99.0% 99.0%				2/10/2020 1/20/2020	2/5/2020	1/20/2020	FedEx DocuSign	_
32512	1/15/2020	City of Torrance	Residential Street Rehabilitation - Area A g	2 133 840.00	7800	644	Day	120 Working Days	Gordon	John M	Ted	99.0%				2/28/2020	2/28/2020	3/6/2020	FedEx	
32198	1/16/2020		La Puente Community Park AC & Slurry Quote \$	109,407.00	1056	0	Day	60 Working Days	Augustine	John M	Ted	99.0%								
32286 32317	1/23/2020 1/28/2020	City of Chino Hills City of Dana Point	Pipeline Avenue Pavement Rehabilitation Project No. Slurry Seal Project FY 19/20	219,894.00 1,897,897.00	1600	5	Day Day	20 Working Days 60 Working Days	Maurice Kim	John W Rick	Mindie Mindie	99.0% 99.0%				2/26/2020 3/6/2020	2/26/2020	3/6/2020 3/10/2020	FedEx FedEx	_
32312	2/1/2020	City of San Jacinto	Sanderson Avenue Safety Improvements Project, \$	773,226.06	0	Ū	Day	90 Working Days	Brian	John W	Mindie	99.0%				2/19/2020	2/19/2020	2/26/2020	FedEx	
33129	2/1/2020	County of Orange	El Toro Building Statuto	403,775.05	1955	0	Day	40 Working Days	Gordon	Rick	Gio	99.0%								
32243 32256	2/3/2020 2/5/2020	City of Camarillo Crescenta Valley Water District	Earl Joseph Drive Paving Final Paving on Pennsylvania Avenue	681,901.50 82,620,00	3,068	83	Day Day	25 Working Days 30 Working Days	Edward Augustine	John M Jim	Deonne Mindie	99.0% 99.0%				2/18/2020	2/12/2020			_
32328	2/11/2020	City of Paramount	Neighborhood Street Resurfacing on Various City	1,238,777.00	5380	420	Day	40 Working Days	Maurice	Rick	Deonne	99.0%				2/28/2020	2/19/2020	3/10/2020	FedEx	+
32364 32337	2/11/2020 2/13/2020	City of Huntington Beach	Graham, Slater, Newland and Atlanta Rehabilitation \$ RCTC_Route#15 & Rairoad Canyon Road	5,151,955.00	25881	1495	Day	105 Working Days 1 434 Working Days	Jim	Doug	Deonne	99.0%				0/00/0000	0/11/00000		E. IF	
32337	2/18/2020	City of Rancho Santa Margarita	FY 19-20 Annual Residential Sturry Seal	2,169,978.46 368,166.88	20,000	0	Day & Nig Day	30 Working Days	Edward Brian	Art Rick	Mindie	99.0% 99.0%				3/20/2020 2/25/2020	3/11/2020 2/27/2020	3/24/2020 3/4/2020	FedEx FedEx	
32557	2/19/2020	Peterson-Chase	07-311704 Route 134 \$	6 610 784.00	38400		Night	60Working Days	Jim	Art		25.0%			-	6/10/2020		6/16/2020	fedex	
32288 32315	2/20/2020 2/27/2020	City of Ontario City of Simi Valley	2020 Spring Pavement Rehabilitation Project \$ FY 2019-20 Minor Streets Rehabilitation Program, \$	2,197,669.00 992,543,70	15100 4,000	340 154	Day	40 Working Days 50 Working Days	Maurice Edward	John W John M	Mindie Deonne	99.0% 99.0%				2/28/2020	7/24/2020	3/10/2020	FedEx	
32306	2/28/2020	Department of Transportation	Route 215 from PM R40.3 to PM 43.1 Contract 08-	992,543,70	4,000	154	Day Night	30 Working Days	Jim	John W	Gio	99.0%				2/28/2020		3/3/2020	Emailed	
32277	3/2/2020	Schuler Constructors	Keith Tank Project - Corona	159 929.32	1100	0	day	10 Working Days	Augustine	Jerry	Gio	99.0%								<u>Et r</u>
32331 32339	3/2/2020 3/3/2020	City of San Marino City of Temple City	FY 2019 Street Rehabilitation Program Project S Las Tunas Blvd Pavement Rehabilitation Phase 1, S	2,109,419.00	12600 4880	100 20	Day	60 Working Days 21 Working Days	Maurice Maurice	John M John M	Deonne Deonne	99.0% 99.0%				3/17/2020 3/18/2020	3/17/2020 3/18/2020	3/27/2020	FedEx FedEx	_
32309	3/4/2020	City of Norco	Hamner Avenue Street Rehabilitation \$	662,312.00	4000	20	Night	20 Working Days	Edward	Jerry	Mindie	99.0%				3/25/2020	3/18/2020	3/27/2020	FCUEX	
32345	3/5/2020	Pulte Homes Company	West Haven Cascade Offsite Street Rehabilitation	649,000.00					Miguel	Jim	Gio	99.0%								
32359 32643	3/5/2020 3/9/2020	City of Norco Crosstown Electrical Data, Inc.	FY 2019-2020 Slurry Seal Project S City of Newport Beach - Traffic Signal Upgrade S	147,708.97 112,540.00	0	0	Day Day	20 Working Days 10 Working Days	Brian	John W John M	Mindie	99.0% 99.0%				3/19/2020	3/19/2020	4/14/2020	FedEx	_
32351	3/14/2020	City of Moreno Valley	Pothole Repair Services	\$1650.00 per hr	850	0	Day	365 Working Days	Maurice Augustine		Mindie	99.0%							-	
	3/17/2020	City of Anaheim	Master Agreement for Slurry Seal and Crack Seal				Day		Brian	Rick	Mindie	0.0%				3/18/2020	3/17/2020	3/25/2020	FedEx	
32314 32316	3/19/2020 3/19/2020	Sturgeon Electric American Civil Contractors	(08-384234) Rte #10 Install Fiber Obtic Cable System \$ Rte. #110 Place High Enction Surface Treatment	225,651.17 172,858,70	220 790		Night Night	150 Working Days 100 Working Days	Edward Edward	John W Art	Mindie	99.0% 99.0%								1
32335	3/19/2020	City of Menifee	Ethanac Road & Sherman Road Street Resurfacing \$	1,276,845.68	3,292			60 Working Days	Edward	John W	Mindie	99.0%			-	3/27/2020	4/27/2020	4/10/2020	1	
32349	3/19/2020	City of China Hills	2019-2020 Street Improvement Project ST200001	1.093 145.00	11550	0	Dav	40 Working Days	Maurice	John W	Mindje	99.0%				4/9/2020		4/15/2020	FedEx	
32466 32262	3/19/2020 3/20/2020	City of Compton Bosco Constructors	Annual Residential Street Rehabilitation-Phase 1 (09-316504) Rte#118 MVP	5,295,068.00 \$75,275.00	18920 250	1863 0	Day Night	130 Working Days 150 Working Days	Gordon Edward	John M Art	Deonne	99.0% 99.0%	_							
32336	3/20/2020	Teichert	(07-312004) Rte 2/5/101/105/110 Modify Traffic \$	\$75,275,00	450			500 Working Days		Doug	Deonne	0.0%								_
32350	3/26/2020	City of Chino Hills	Bayberry Drive and Valle Vista Drive Project 5	637,229.00	4400	180	Day	40 Working Days	Maurice	John W	Mindie	99.0%					5/8/2020			
32526 32360	3/31/2020 4/1/2020	City of Rancho Cucamonga City of Norco	FY 19-20 Local Slurry Seal Pavement Rehabilitation S Crestview Drive Pavement Improvement Project	196,232.00	2,000	224	Dav	60 Working Days	Brian Edward	John W Jerry	Mindie Mindie	99.0% 99.0%				4/20/2020 4/15/2020	4/20/2020	5/6/2020	FedEx	
32372	4/1/2020	City of Jurupa Valley	Granite Hill Drive Pavement Rehabilitation	646,098.00 999,777.00	8000	40	Day	30 Working Days	Maurice	John W		99.0%				4/15/2020	4/17/2020	4/22/2020 5/5/2020	FedEx FedEx	
32367	4/2/2020	City of Victorville	Third Avenue Road Improvement	1,790,000.00	4800	200	Day	70 Working Days	Augustine	Jim	Mindie	99.0%								
32382 32442	4/7/2020 4/7/2020	City of Loma Linda City of Santa Ana	Pavement Rehab on Barton Road S Henninger Neighborhood Residential Street Repair	768,677.00	6260	0 600	Day	40 Working Days 50 Working Days	Maurice	John W Rick	Mindie Gio	99.0% 99.0%				4/15/2020	4/15/2020	5/6/2020	FedEx	
32442	4/1/2020	City of Santa Ana	Local Street Preventative Maintenance	698.227.00 1,987,588.00	3570	150	Day Day	90 Working Days	Jim Jim	RICK	Gio	99.0%				5/7/2020 5/7/2020		5/29/2020 6/5/2020	fedex	
32551	* 4/14/2020	California Professional Engineering	City of Cudahy - ATP Cycle 2 Project \$	154,680.00	100	60	Day	10 Working Days	Maurice	John M	Deonne	99.0%				11		0/0/2020		1
32647	4/14/2020	County of Los Angeles	RMDJOC6679 Pavement Preservation (Seal Coats), S	4 200 000,00	1100		Day		Brian	Darren	Decor	99.0%				6/3/2020	4/22/2020	6/5/2020	FedEx	1
32770 32936	4/14/2020 4/14/2020	County of Los Angeles County of Los Angeles	Del Air Project 6696-300-00 s Ladera Heights 6'990-600-00 s	987 576.79 2,942 683,89	4480 10261		Day Day		Kim Kim	Doug John M	Deonne Deonne	99.0% 99.0%					_			
	4/14/2020	County of Los Angeles	RMDJOC6680 Pavement Preservation (Seal Coats), \$	4,800,000.00			Day		Brian	Darren		99.0%		-	-	6/3/2020	4/22/2020	6/5/2020	FedEx	1
32480	4/16/2020	City of Newport Beach	Cameo Highlands	2,425,694.00	8000	440	Day	90 Working Days	Jim	Rick	Gio	99.0%								1
32426	4/22/2020	Caltrans	(08-1H3414) Rtes 210/215/259 Place RHMA-G, Cold	6,324,158.90	35,900	0	Night	50 Working Days	Edward	John W	Gio	99.0%				5/7/2020		5/11/2020	fedex	

loh No #	Dete	Anoneu / Owner	Broket Title	Bid Amount	AC Torrer	Con	Daught	Contract Time	P.4	0,	04	Complete	Dirt Removal	Concrete	Colorthan	Card De	Date of Letter	Sent Back		
Job No.# 32434	Date 4/22/2020		Project Title Westminster Blvd	578,255.00	AC Tonnage 3291	50	e Day/Nigh Day	Contract Time 50 Working Days	P.M. Jim	Supt Doug	Coor Deonne	Completed 99.0%	Rentoval	Removal	Grindings	Cont. Rec. 5/1/2020	Letter	5/4/2020	Via fedex	
32518	4/23/2020 4/29/2020	Caltrans	12-0R8904 Route 5 Asphalt Roadway & Parking Lot Restoration	1,815,853,00	10300	12	Night	60 Working Days	Jim	Rick	Gio	99.0%				5/26/2020		6/2/2020	fedex	
32423 32424	4/29/2020	Metropolitan Water District County of Riverside Transportation	La Sierra Ave Reconstruction and Slurry Seal Project	281.000.00 2499.955.40	30 14,900		Day 6 Night/Day	30 Working Days 40 Calender Days	Augustine Edward	John W John W	Gio Mindie	99.0% 99.0%				5/11/2020		5/15/2020	fedex	
32513 32433	4/29/2020 4/30/2020		Road Maintenance and Rehabilitation Improvement Antonio Parkway Rehabilitation	\$ 655,945.00	2081	0	Day	30 Working Days	Gordon	John W	Mindie	99.0% 99.0%				5/6/2020				-
32584	4/30/2020	City of Orange	Annual Slurry Seal at Various Locations, FY 19-20, SP-	412 137.00 377 737.78	2480 410	0	Day Day	35 Working Days 60 Working Days	Jim Brian	Rick Rick	Gio Mindie	99.0%				6/15/2020	6/15/2020	5/20/2020 6/29/2020	fedex FedEx	
32534 33458	5/5/2020 5/5/2020		FY 19-20 Slumy Seal & Rehabilitation S Rossmoor Collectors Grind & Overlay	1,545 799.84	0 13021	0	Day Day	70 Working Days 22.5 Working Days	Brian Gordon	Rick Rick	Mindie Gio	99.0% 99.0%				5/8/2020	5/8/2020	5/18/2020	FedEx	
33462	5/5/2020	County of Orange	Rossmoor Locals Grind & Overlay	2,148,320.90 1,933,562.72	12468	0	Day	22.5 Working Days	Gordon	Rick	Gio	99.0%								
32473 32530	5/7/2020 5/7/2020	Lennar Homes City of Pasadena	Merrill and Haven Street Improvements S Resurfacing of Orange Grove Avenue	1 481 832.15 5,098,175.00	16845	1854	Day	45 Calendar Days 120 Working Days	Miguel Gordon	Jim Jim	Gio Mindie	99.0% 99.0%		_		6/12/2020		6/10/2020 6/19/2020	FedEx FedEx	
32516	5/12/2020	Belco Elecnor Group	City of Palm Springs - Traffic Signal and ADA	\$ 429,750.00	120	380	Day	20 Working Days	Maurice	John W	Gio	99.0%						0/19/2020	TOULA	-
32893 32492	5/14/2020 5/19/2020		Interstate 215 Placentia Ave Interchange 2020 Street Resurtacing Project # 19-20-04	4 550 967.00 685 000.00	52250 3016	0 150	Day & Nite Day	500 Working Days 40 Working Days	Gordon Augustine	Art John M	Deonne	69.0% 99.0%				6/25/2020 6/22/2020		6/29/2020	FedEx	
32546	5/19/2020	City of Sierra Madre	Sierra Vista Park Parking Lot Improvement	132,375.50	20		- 00 g	20 Working Days	Kim	Jim	Mindie	99.0%				6/10/2020	6/10/2020	6/12/2020	FedEX	1000
32624 32491	5/19/2020 5/28/2020		2020 Citywide Street Improvements Stalley Blvd @ Almond Ave Traffic Signal Project	1,193,078,17 1,023,000,00	4000 1025	248 250	Day Day	75 Working Days 55 Working Days	Gordon	John W Jim	Mindie Mindie	99.0% 65.0%		_		6/30/2020 6/24/2020	6/10/2020	7/2/2020 7/2/2020	FedEx	
32529	5/28/2020	City of Placentia	FY 2019-20 Artenal Roadway Rehabilitation Project Katella Ave Widening - REBID	2 339 799.00	15000	115	Day	100 Working Days	Maurice	Rick	Mindie	99.0%				6/22/2020	6/22/2020	7/9/2020	FedEx	
32804 32685	5/28/2020 6/1/2020		2020 Fall Pavement Rehabilitation Project - 1303	24,874.20 2,499,333.00	145 18620	600 30	Day Day	60 Working Days 40 Working Days	Augustine Maurice	Rick John W	Gio Mindie	99.0% 99.0%		_		8/19/2020 6/3/2020	6/3/2020	8/27/2020 6/22/2020	Hand Delive	r
32517	6/3/2020		2020 Street Improvements Project - Olive Avenue and g Residential Roadway Rehabilitation Project GT229	\$ 300,433.00	1333	150	Day	40 Working Days	Augustine	Jim	Mindie	99.0%				6/24/2020		7/2/2020	FedEx	1
32570 32651	6/4/2020 6/4/2020	City of Rolling Hills Estates	Resurtacing Project on Palos Verdes Drive North and	\$ 1,623,078.06 \$ 576,635.00	15560 2780	1490 146	Day Day & Nite	50 Working Days 30 Calendar Days	Maurice Kim	Rick John M	Deonne Deonne	99.0% 99.0%		_		6/22/2020 7/8/2020	6/22/2020	7/15/2020	FedEx	
32769 32762	6/5/2020 6/10/2020		Port-A-Port Airport Pavement Maintenance S Orangethorpe Avenue	360.921.20 791.814.00	280 4970	110 40	Day Day	50 Calendar Days 45 Working Days	Gordon	John W Rick	Gio Gio	99.0% 99.0%				6/25/2020 8/10/2020	8/10/2020	7/21/2020	FedEx FedEx	
32562	6/16/2020	Caltrans	Route 215 38.5 to 37.4	\$ 210,000.00	4910	150	Night	30 Working Days	Jim	John W	Gio	99.0%	-			6/17/2020	0/10/2020	8/13/2020	redex	
32565 32897	6/16/2020 6/16/2020	Caltrans City of Manhattan Beach	Route 215 (9.0 to21.1) Route 15 (5.0 to 8.7) Second Street Resurfacing Project	\$ 280,000.00 \$ 692,857.24	2379	200 105	Night Night	30 Working Days 60 Working Days	Jim Gordon	John W John M	Gio Deonne	99.0% 99.0%				6/17/2020 8/18/2020	8/6/2020	9/8/2020	Docusign	
32674	6/17/2020	Belco Elecnor Group	City of Glendale - North Verdugo T.S. Project	175,950.00	140	100	Day		Maurice	John M	Deonne	99.0%								
32585 32599	6/18/2020 6/18/2020	City of Chino Hills	2019-2020 Pavement Rehabilitation Phase 2 Canyon Hills Road Pavement Rehab Project	1 119,322.00 106.000.00	8300 250	340 0	Day Day	40 Working Days 25 Working Days	Maurice Augustine	John W John W	Mindie Gio	99.0% 99.0%				7/2/2020 6/25/2020	7/1/2020	7/9/2020 7/2/2020	FedEx FedEx	
32655	6/25/2020	City of San Dimas	Alley Reconstruction - Alley P - Cataract to Monte Vista Alicia Parkway . Jeronimo Road and Marguente	134,960.00	350	85	Day	30 Working Days	Kim	Jim	Gio	99.0%				7/21/2020	7/15/2020	7/24/2020	FedEx	
32650 32691	6/26/2020 6/30/2020	City of Walnut	Walnut_Amar Road Street Rehabilitation from Nogales	2,343,333.00 1,225,901.50	19620 8,500	110	Day 5 Day	50 Working Days 65	Maurice Edward	Rick Jim	Gio Gio	99.0% 99.0%				8/11/2020 7/24/2020	8/11/2020 7/24/2020	8/13/2020	FedEx	-
33023 32616	6/30/2020 7/1/2020	Guy F. Atkinson	12-0K0234 Route 5 Cowan Heights Overlay	3,390,661.00	34580		Night	750 Working Days	Jim	Art	Gio	25.0%						7400000	FadFr	
32930	7/1/2020	City of Orange	2020-2021 Asphalt Replacement At Various Locations	20,800.00 607,000.00	2000	0	Day Day	317 Calender Day	Gordon Maurice	Rick Rick	Gio	99.0% 80.0%		_		7/1/2020 8/25/2020	8/12/2020	7/16/2020 8/28/2020	FedEx	
33017 32798	7/1/2020 7/2/2020		Sepulveda Blvd. Rehabilitation Street Rehab Via Pico, Ave Pico, Navarro, Calle De	3,092,535.00 1,990,098,13	16300 5315	630 511	Day Night	110 Working Days 60 Working Days	Gordon Kim	John M Rick	Deonne Gio	99.0% 99.0%				8/24/2020 8/19/2020	8/19/2020	9/9/2020	FedEx Hand Deliver	
32639	7/9/2020	City of Glendora	Glendora_Dike St, Prospero Dr, Soderberg Ave Ghent	329,797,49	2,558	34		30 Working Days	Edward	Jim	Gio	99.0%				7/17/2020	6/19/2020	9/2/2020 7/22/2020	FedEx	
32808 32854	7/14/2020 7/20/2020		Vista Del Lago Streets Project Bear Street Improvement Project - I-405 Baker St., City	479,626.00 657,777.00	4400 4500	10 72	Day Day	10 Working Days 30 Working Days	Augustine Maurice	John W Doug	Gio Deonne	99.0% 99.0%				10/26/2020 9/2/2020	8/6/2020	10/29/2020 9/10/2020	FedEx FedeX	_
32925	7/20/2020	Walsh Construction	OIAA - Taxiway C Improvement	132,165.00	990	۵	Day	100 Calendar Days	Gordon	Art		99.0%				9/10/2020	0/0/2020	9/14/2020	Docusign	
32730	7/28/2020 7/29/2020		El Toro Memorial Park Curb & Drive Project g Overlay and Repair to Calle Pino	\$ 416,999.00 \$ 92,600.00	1950 412	300	Day Day	25 Working Days 15 Working Days	Augustine Augustine	Rick Jerry	Gio Gio	99.0% 0.0%		_						
32696	8/1/2020	City of Yorba Linda	Fairmont Blvd 400 FT S/O Avenida Del Rey Access to	5 113,472.00	120	16	Day	75 Working Days	Kim	Rick	Gio	99.0%				8/6/2020	7/28/2020	8/10/2020	FedEx	
32846 32855	8/2/2020 8/5/2020	Santa Clarita Valley Water Agency	Los Nietos Road Street Improvements (Pioneer S Ridge Route Road Pavement Repair	2 634 444.00 75.000.00	17596 145	600 0	Day Day	40 Working Days 15 Working Days	Maurice Augustine	Jorge John M	Gio Deonne	99.0% 99.0%				9/2/2020	8/11/2020	9/15/2020	FedEx	
33223 32719	8/5/2020 8/6/2020		City Parking Lots Rehabilitation Sheeps Creek & Hwy 2	\$ 726,700.00	1743 350	210	Day Day	60 Working Days	Gordon	John M Art	Deonne	99.0% 99.0%				9/10/2020	8/6/2020	9/14/2020	FedEx	
32756	8/6/2020	County of Orange	Back Parking Lot - 1300 S. Grand	51,324.00 447,436.46	3630	0	Day	30 Working Days 30 Working Days	Gordon	Rick	Gio	99.0%							-	
32727 32799	8/7/2020 8/10/2020		Abandon Manhole : Hamilton Street & Santa Ana Avenue Improvement :	79,756.00 1,360,022.00	3788	610	Day Day	60 Working Days 140 Working Days	Jim Kim	Doug Doug	Deonne Deonne	99.0% 99.0%				9/24/2020	8/20/2020	9/10/2020	Hand Deliver	
32932	8/10/2020	City of Lake Elsinore	Citywide Slurry Seal Project CIP No. 210014	1,316,641.00	4026	010	Day	120 Working Days	Gordon	John W	Gio	99.0%				9/7/2020	9/3/2020	9/18/2020	Docusign	
32742 32743	8/11/2020 8/13/2020		University Drive States	823,902.40 47,850.00	9640 200	_	Day Day	60 Working Days 30 Working Days	Jim Jim	Art Art		99.0% 99.0%								
32821	8/13/2020	City of Riverside	Permanent Trench Resultacing	251,445.00	518	107	Day	35 Working Days	Jim	John W	Gio	99.0%								
32869 32764	8/14/2020 8/18/2020		2019-2020 Annual Slurry Seal Project #2020-07 32020-21 Canyon View - Grind, ARAM, and Overlay 32020-2000-2000-2000-2000-2000-2000-200	262,780.66 1,070,528.00	0 8,400	0	Day Day	25 Working Days 45 Working Days	Brian Edward	Darren Jim	Gio Gio	99.0% 99.0%				9/14/2020 9/9/2020	9/9/2020 9/9/2020	9/21/2020 9/16/2020	FedEx	1(
32859 32781	8/18/2020 8/19/2020	City of Rancho Santa Margarita	FY 20-21 Annual Slurry Seat Las Tunas Blvd Pavement Rehabilitation Phase 2.	414,250.00	0	0	Day	40 Working Days	Brian	Darren		99.0%				8/19/2020	8/19/2020	8/27/2020	Email/FedEx	
32781 32867	8/19/2020 8/19/2020		FY 2019-2020 Annual Street Rehabilitation Project	974,333.00 1,458,888,00	7620 9262		Day Day	30 Working Days	Maurice Maurice	John M Rick	Deonne Gio	99.0% 99.0%		_		9/2/2020 9/3/2020	9/1/2020 9/3/2020	9/8/2020 9/21/2020	FedEx	
32779 32784	8/21/2020 8/25/2020	City of Menifee City of La Verne	Public Works Maintenance & Operations Center Fruit Street Medians Improvements	359,406.00	0 350	126	Day	40 Working Days	Augustine	John W	Gio	99.0%				9/10/2020	9/2/2020	9/15/2020	Docusign	_
33115	8/26/2020	City of Torrance	Residential & Arterial Pavement Improvement	528,524.00 3,687,032.00	20919	200 125	Day Day	60 Working Days 100 Working Days	Augustine Gordon	Jim John M	Gio Deonne	99.0% 99.0%				9/14/2020 10/23/2020	9/14/2020	11/6/2020	FedEx	1
32864 32926	9/3/2020 9/3/2020		San Dimas Trench Repair S Capital Improvment Project No. 16-20A Old River	33,525.00 75,414.32	200	0	Day Day	1 Working Day	Augustine Brian	Jim John M	Gio Deonne	99.0% 99.0%				9/29/2020	9/29/2020			
32853	9/8/2020	City of Rancho Cucamonga	Foothill Boulevard Pavement Rehabilitation Milliken	1.441,579.00	9300	210	Day	40 Working Days	Maurice	Jim	Gio	99.0%				9/14/2020	9/14/2020	9/21/2020	FedEx	
32904 32958	9/9/2020 9/9/2020		Baseline Road Improvements S Merrill Ave - Grove - Flight	473.000.00	520 7000	112	Day DAY	40 Working Days 70 Working Days	Augustine Mique	Jim Jerry	Gio Gio	99.0% 99.0%				9/15/2020	9/15/2020	9/22/2020	FedEx	
	9/10/2020	Los Angeles Depart.Of Power And	REBID Pine Tree Wind Power Plant Access Road	810,400.00					Brian	Darren	Deonne	0.0%				1/13/2021	14.00/00.000	1/19/2021	FedEx	
33047 33376	9/15/2020 9/16/2020	City of Inglewood	2018-2019 CDBG Ward 5 Street Improvements for Street and Alley Improvements Project FY 2020-21	292,228.00 2,154,150.00	760 12590	130 555	Day Day	40 Working Days 120 Working Days	Jim Gordon	John W John M	Gio Deonne	99.0% 99.0%		-		11/3/2020 3/3/2021	11/3/2020	11/9/2020 3/11/2021	FedEx FedEx	-
32894 32998	9/17/2020 9/17/2020	Murow CM - IPT Perris DC III	Western Way Culver City - Traffic Signal Left Turn Phasing Upgrade	510,000.00	2000	150 40	DAY Day	60 Working Days	Miguel	John W John M	Gio	99.0% 0.0%		_						1
33136	9/17/2020	Belco Elecnor Group	Broadway Improvements & Traffic Signal Modification	6 94,400.00 6 63,225.00	20	40	Day		Maurice Maurice	John M	Deonne	99.0%								
32892 33014	9/18/2020 9/23/2020		CSA 70 R-8 Fog Seal Project Palomar Avenue Widening Project	304,512.35	0 292	0	Day	Working 30 Calendar Days	Brian Kim	Brian John W	Gio	99.0% 99.0%				10/21/2020	9/23/2020 10/21/2020	10/30/2000	FedEx	1°
33078	9/23/2020	Landsea Homes	Eucalyptus Avenue Street Impovements	590,000.00	292 2700	300	Day Day	40 Working Days	Miguel	Jim	Gio	98.0%				11/23/2020	11/23/2020	10/22/2020 11/23/2020		
32927 32934	9/24/2020 9/24/2020	City of San Gabriel City of San Gabriel	2020 CDBG Local Streets Slurry Seal Project; Contract 2020 Pavement Rehabilitation Project Contract No. 20-	218,040.00 1,316,573.03			Day Day		Brian Brian	Darren John M	Deonne	99.0% 99.0%				10/14/2020	10/14/2020	10/19/2020	Runner	1
32913	9/29/2020	City of Pomona	Major Street Rehabilitation - 2015 Metro Call Project	9,154,356.14	33,800) Jay & Nigh	205 Working Days	Edward	Jim	Gio	98.0%				11/17/2020	11/17/2020	11/20/2020	FedEx	
32937 33020	9/29/2020 9/29/2020	Ontario International Airport	Nutmeg Street and Hancock Avenue Rehabilitation - 4 Amazon Repairs	1,528,627.00 110,005.00	9390 675	170 0	Day Day	35 Working Days 5 Working Days	Maurice Gordon	John W John W	Gio Gio	99.0% 99.0%				9/29/2020		9/29/2020	Hand Deliver	1
32947	10/8/2020	City of Norco	Norco_Second Street Widening	698,765.00	725	196	3 Day & Nigt	120 Working Days	Edward	Jerry	Gio	99.0%				10/29/2020	10/29/2020	11/2/2020	FedEx	
32961 33044	- 10/14/2020 10/14/2020	City of Seal Beach	FY 19-20 Arterial Street Resurfacing Program - Bolsa S FY 20-21 Annual Slurry Seal Program Project CIP	199,532.00 205,670,45	900 31	100 0	Day Day	25 Working Days 25 Working Days	Augustine Brian	Doug Doug	Deonne Deonne	99.0% 99.0%				10/19/2020 10/15/2020	10/15/2020	10/23/2020 10/23/2020	FedEx FedEx	
32972 33268	10/15/2020	City of Brea	Alley Rehabilitation Project	140,648.00	200	100	Day	15 Working Days	Augustine	Rick	Gio	99.0%				10/20/2020		10/22/2020	FedEx	=
33268	10/15/2020 10/16/2020	International Line Builders	Annual Overlay Program & Annual Concrete Replacem Santa Ana - Euclid St At Hazard Signal Modification	1,440,375.00 74,103.00	4556 20	746 20	Day Day	60 Working Days	Gordon Maurice	Jorge John M	Deonne Deonne	99.0% 99.0%				12/11/2020 7/9/2020	11/25/2020	12/21/2020 7/9/2020	FedEx	-
32974 32874	10/16/2020	Belco Elecnor Group	Palm Springs - Tahquitz Canyon Improvements 2 Lyttle Creek Street Improvements 2	129,000.00	60 1100	20 30 100	Day	20 Marking Day	Maurice	John W	Gio	99.0%				8/1/2020		8/1/2020		
32877	10/19/2020	SC Ontario	Eucalyptus Avenue Street Improvements 5	5 197,573,52 5 1,230,000.00	3200	100	Day Day	20 Working Days 70 Working Days	Miguel Miguel	Jim Jim	Gio Gio	99.0% 95.0%								
32965 33356	10/19/2020	Leonida Builders	Allessandro Alley Improvements - Phase 1 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	105,225.00	1025	0	Day	4 Working Days	Augustine	Art		99.0%				D/45/050/	045/2004		Email	
33052	10/19/2020 10/20/2020	KB Homes	Tract18026 West Haven Offsite Street Improvements	475,000.00 1,079,000.00	1650 16000	230 2000	Day Day	20 Working Days 60 Working Days	Miguel Miguel	John W Jim	Gio Gio	95.0% 95.0%	1000			3/15/2021 11/19/2020	3/15/2021 11/19/2020	3/15/2021 11/20/2020	Email Docusign	
33199 33729	10/20/2020 10/20/2020	Murow CM/Landsea Homes	Haven Avenue Street Improvements \$2020-21 Pavement Overlay	5 700,000,00	3800 19690	200 0	Day Day	40 Working Days 120 Working Days	Miguel	Jim Rick	Gio Gio	98.0% 0.0%				1/7/2021	1/7/2021	1/8/2021	DocuSign	
00123	10/20/2020	ony of Calibrau	FAFA-F1 L DACHIEIL CACIU	4,638,132.00	19090	0	Day	120 WORKIN Days	Jim	RICK	GO !	0.0%				7/15/2021		7/20/2021		

ob No,#	Date	Agency / Owner	Project Title	Bid Amount	AC Tonnage Co	oncrete Da	av/Niab	Contract Time	P.M.	Supt	Coor	Completed	Removal	Concrete Removal	Grindings	Gont. Rec.	Date of Letter	Sent Back	Via
32992	10/21/2020		Rancho Cucamonga - Traffic Signal Project \$	176,748,00			Day	Connact Hills	Maurice	John M	Deonne	99.0%	110110 741		Grandings	9/25/2020	setter	9/25/2020	Via
33056	10/22/2020	Turtle Rock Crest Community Asso	Turtle Rock Pavement Rehabilitation \$	811,311.00	6800		Day	30 Working Days	Augustine	Rick	Gio	99.0%				11/3/2020		11/6/2020	FedEx/Email
33261 33007	10/22/2020	City of Carson	223rd Street Improvement \$	1,671,391.68	7317	520	Day	100 Working Days	Gordon	Jorge	Deonne	95.0%				12/11/2020	11/25/2020	12/21/2020	Fed/Ex
3007	10/26/2020 10/26/2020	Lewis Operating Corp. Moote Companies / KB Homes	Van Vieit Tract 20161 Improvement S Underwood Tract 29835-2 Offsite Street Improvements S	958,737.50 2,189,000.00					Miguel Miguel	Jerry John W	Gio Gio	95.0% 90.0%				1/5/2021	1/5/2021	1/11/2021	FedEx
33015	10/27/2020	Belco Elecnor Group	Rialto - Left Turn Signal Improvements HSIP 8	53 633.00	20	30	Day		Maurice	John M	Deonne	99.0%				3/8/2021	115/2021	3/8/2021	FEUEX
33091	10/28/2020	City of Santa Ana	Adams Park Parking Lot Improvements \$	67,767.00	18	34	Day	25 Working Days	Kim	Rick	Gio	99.0%				11/12/2020		11/23/2020	Eric V. Hand
33042	11/4/2020	City of Cypress	Cypress_Arterial Rehab \$	699,327.00	4,700	0	Day	30 Working Days	Edward	Rick	Gio	99.0%				12/1/2020	12/1/2020		
3065	11/4/2020	City of Victorville City of Santa Ana	El Rio & Calvary Rd Repair & Vault Lid Replacement Bristol Street Protected Bike Lanes \$	279,009.00	535	1000	Day	20 Working Days	Augustine	Jim	Gio	99.0% 99.0%				12/14/2020		12/14/2020	Fedex
33292	11/4/2020	City of Santa Ana City of Santa Ana	South Main Street Corridor	1 967 436.00 187 920.00	1050		Day Day	75 Working Days 220 Working Days	Jim Jim	Rick	Gio	0.0%							_
3069	11/16/2020	Belco Elecnor Group	Los Angeles - On Call Traffic Signal Project \$	242,635,00	60		Day	Let Hommig Bujo	Maurice	John M	Deonne	99.0%				3/8/2021		3/8/2021	
33144	11/19/2020	City of Temecula	Pavement Rehab Program - Citywide West Side \$	1,711,230.62	6500		ay/Night		Brian	John W	Gio	99.0%				12/9/2020	12/9/2020		
33331 33426	11/19/2020 12/2/2020	Myers & Sons Construction Chuma Construction	Route 15 08-1F1434 \$ 07-288304 RTE#2,60,164,210 \$	3,106,458.00	19750		Night	350 Working Days	Jim	Art	Deserve	70.0%				1/0/0004	4/0/0004		
32999	12/3/2020	OHL USA	Route 101 07-303704	83 800.85 773 280.00	364 4320	0	Night	170 Working Days 550 Working Days	Edward Jim	Doug Art	Deonne	0.0%				4/9/2021	4/9/2021	4/12/2021	
3260	12/3/2020	Chumo Construction	07-332604 Route 10 \$	763 753.80	7190	0	Night	400 Working Days	Jim	Art		70.0%							
3253	12/8/2020	City of Yorba Linda	FY21-22 Manhole and Valve Box Adjustment \$	69,524.78	20	0	Day	540 Calender Days	Brian	Darren		75.0%							
3141	12/10/2020	County of Orange	Coyote Canyon Landlill \$	132,030.04	135		Day	60 Working Days	Gordon	Rick	Gio	99.0%							
3230 3367	12/10/2020 12/10/2020	City of Riverside AToM Engineering	SB-1 Maintenance and Traffic Improvements \$ Flonda Ave Water Repairs \$	2,681,359.00	9200	1000	Day Day	100 Working Days 2 Working Days	Jim Augustine	John W John W	Gio	99.0% 99.0%				3/1/2021	3/1/2021	3/3/2021	FedEx
3171	12/14/2020	City of Westminster	CDBG 20-21 Improvements	345 792.00	2000		Day	30 Working Days	Jim	Doug	Deonne	99.0%							
3224	12/15/2020	City of Buena Park	Rosecrans Avenue Street Resurfacing Project \$	599,864,00	3800		Day	30 Working Days	Augustine	Rick	Gio	99.0%				2/12/2020	2/9/2020	2/17/2020	FedEx
3386	12/16/2020	OHLUSA	Route 71 07-210624 \$	1,947,425.00	19260		Night	720 Working Days	Jim	Art		5.0%							
3244 3175	12/22/2020 12/28/2020	Lennar Homes	French Valley - Offsite Street Improvements \$ Palmdale - Palmdale Blvd & 90th T.S. Project \$	918,000.00	4000		Day	30 Working Days	Miguel	John W	Gio	90.0%				1/25/2021	1/25/2021	1/27/2021	Email
3186	1/6/2021	County of Riverside	Ramona Express Resurtacing (Rider Street to Warren \$	152 246.00 7 916 616.59	54,010	0	Day Ninht	60 Calendar Days	Maurice Edward	John M John W	Deonne Gio	99.0% 99.0%		_		1/14/2021	1/14/2021		
			GreenBrier Ave B/T Spring St. & Mezzanine Way R-		04,010		. signe		Lanua			55.070	-			WI WEDEL	WINEVE I		
33194	1/12/2021	City of Long Beach	7153 \$	1,173,779.33	2586		Day		Jerry	Jorge	Deonne	99.0%							
3254	1/14/2021	City of Cypress	Residential Street Resurfacing Improvements CDBG Pr \$	138,472.00	90	0	Day	30 Working Days	Brian	Darren	Gio	99.0%				3/1/2021	3/1/2021	3/5/2021	FedEx
3196 3302	1/15/2021	City of Long Beach	Lomina Ave B/T Adderely Dr & Rosebay St. R-7153 \$ Asphalt Repairs at Legacy Buildings \$	823,810.10	1523		Day	40 Work's Day	Jerry	Jorge	Deonne	99.0%							
3302	1/15/2021 1/19/2021	City of Banning	2020-07 Citywide Street Improvements	11,475.00 678,501,50	30 4520		Day Day	10 Working Days 60 Working Days	Gordon	Art John W	Gio	99.0% 99.0%				2/25/2021		Decusiar	
3903	1/19/2021	County of Orange	Prima Deschecha North Access Road Resurfacing \$	454,878.00	3450		Day	3 Months	Gordon	Rick	Gio	99.0%				2/23/2021	-	Docusign	
1281	1/19/2021	County of Orange	Channel Repair \$	118,823.92	0	0	Day	30 Working Days	Gordon	Rick	Gio	0.0%							
4406	1/19/2021	County of Orange	Fence Repair	171,685.86	0		Day	30 Working Days	Gordon	Rick	Gio	0.0%							
3225	1/19/2021 1/20/2021	County of Orange City of Glendale	JOC for Slurry and Paving Services-Facilities-MA-080- Montrose Community Park	755,412,22	550		Day Day	365 Calendar Days 40 Working Days	Gordon Augustine	Rick	Gio Gio	0.0%				1/25/2021 5/5/2021		1/26/2021	Docusign
3512	1/26/2021	City of El Segundo	FY 20/21 Pavement Rehabilitation	838,000.00	4800		Day	50 Working Days	Gordon	John M	Deonne	99.0%				3/3/2021	3/3/2021	5/5/2021 3/12/2021	
3269	1/27/2021	City of Jurupa Valley	Bain Street Pavement Rehabilitation \$	1,148,333.00	6500	545	Day	60 Working Days	Maurice	John W	Gio	99.0%				3/15/2021		3/17/2021	FedEx
235	2/1/2021	City of Oxnard	Bryce Canyon North and South Neighborhood and \$	4,174,871.23	16,360	982	Day	90 Working Days	Edward	John M	Deonne	99.0%				3/3/2021	3/3/2021	3/8/2021	FedEx
242	2/4/2021	City of Glendora	Downtown Village Parking Lot Rehabilitation \$	197,500.00	750		Day	40 Working Days	Augustine	Jim	Gio	99.0%				2/22/2021	10 - C	3/1/2021	FedEx
435	2/4/2021	City of El Monte	Ramona Blvd Street Resurfacing Project \$	2,949,717.80	11860	900	Day	120 Working Days	Gordon	Jim	Gio	95.0%				1			
3066	2/5/2021	City of Long Beach	Third Street B/T Alamitos & Junipero Ave. R-7131 \$	1,813,779.49	1445		Day	60 Working Days	Jerry	Jorge	Deonne	99.0%							
3255	2/8/2021	City of Long Beach	Newport Ave, - Coronado Ave. \$	605,458.67	683		Day	90 Working Days	Јепу	Jorge	Deonne	99.0%				2/8/2021			
3259	2/9/2021	City of Fullerton	Orangethorpe Avenue Street Improvements Project \$	605,236.00	4500		Day	35 Working Days	Augustine	Rick	Gio	99.0%				3/8/2021		3/11/2021	FedEx
3262	2/10/2021	Crosstown Electrical Data, Inc.	Inglewood - ITS Gap Closure Project \$	178,200.00			Day		Maurice	John M	Deonne	99.0%				8/18/2020		8/18/2020	
3247	2/15/2021	Pardee Homes	Atwell Meadowline Way Street Improvements \$,	2500		Day	30 Working Days	Miguel	John W	Gio	95.0%	······			2/3/2021	2/3/2021	1/31/2021	Docusign
3318	2/16/2021	Pulte Homes Company	Tract 32102-1 and 32102-F Street Improvements \$	2,795,795.00			Day	120 Working Days	Miguel	John W	Gio	80.0%				3/23/2022	3/23/2021	3/24/2021	docusign
4002	2/16/2021	HZS Engineering/City of LA	Sanborn Avenue Reconstruction \$				Day	274 Working Days	Gordon	Art		99.0%				9/13/2021		9/20/2021	
3283	2/17/2021		FY 2020-2021 Slurry Seal Project \$	84,350.00	24		Day	30 Working Days	Brian	Darren	Gio	99.0%				4/8/1900			
33287	2/17/2021	Belco Elecnor Group	Anaheim - Katella Ave Widening Trench Repair \$,	20		Day	45 MG 11 - D	Maurice	Art	Deonne	99.0%				3/8/2021		3/8/2021	
33338	2/18/2021 2/18/2021		Ridge Route Road Pavement Repair Phase 2 \$ Santa Gertrudis Ped & Bike Trail - Temecula \$	75,000.00 105,915,00	120		Day	15 Working Days	Augustine	Jorge		99.0%			-	3/5/2021		3/9/2021	FedEx
33272	2/18/2021	Leonida Builders, Inc.	Chestnut Ave. Ocean to Broadway R-7153				Day	120 Working Days	Gordon	Art		70.0%				4/9/2021		5/19/2021	
3349	2/23/2021	City of Long Beach City of Huntington Beach	Residential Overlay Zone 3	2.614.115.00	25000		Day Day	60 Working Days 60 Working Days	Jerry Jim	Jorge Rick	Gio	99.0%				2/1 8/2021	3/18/2021	2/22/2024	
3653	2/23/2021	City of Norwalk	Local Streets Rehabilitation - Zone 27 East of Gard \$	1,051,330,00	10700		Day	40 Working Days	Gordon	Rick	Gio	99.0%				3/18/2021 5/27/2021	5/25/2021	3/22/2021 6/24/2021	FedEx
3308	2/24/2021		North Indian Canyon Drive Widening Project Phase 2 \$	1,998,488,24	9,355	-	Day	60 Working Days	Edward	John W	Gio	98.0%				3/11/2021	3/11/2021	3/16/2021	FEUEX
3325	2/25/2021	City of Santa Ana	Flower St. Rehabilitation from McFadden Avenue to 1st \$		2500		Day	40 Working Days	Jim	Rick	Gio	99.0%				3/2/2021	3/2/2021	3/10/2021	
3757	2/25/2021	Crosstown Electrical Data, Inc.	Caltrans - 07-4V1404 Route 213 Bid \$	211.510.00	20		Day	HO WORKING Days	Maurice	John M	Deonne	0.0%				5/2/2021	5/2/2021	5/1//2021	
340	3/1/2021	Otimans	Duke Rider \$	2,377,225,00			Day	120 Working Days	Miguel	John W	Gio	90.0%				3/1/2021	3/1/2021	3/5/2021	docusion
3354	3/1/2021	RMV Realty, Inc.	PA-3.1 Dry Utility Improvements - Rancho Mission Viejc \$				Day	160 Working Days	Miguel	Rick	Gio	99.0%				4/6/2021	4/6/2021	4/13/2021	docusign
3466	3/1/2021	City of Riverside	2019/2020 Arterial & Minor Phase I \$	4,531,263.50	16367		Day	140 Working Days	Jim	John W	Gio	99.0%				6/7/2021	6/7/2021	6/9/2021	uovualyn
4263	3/2/2021	Belco Elecnor Group	HSIP-Cycle 6 Olympic Blvd-City of Los Angeles \$	317,516.45			Day	365 Calendar Days	Gordon	John M	Deonne	0.0%				er rideWde I			
1521	3/4/2021	Belco Elecnor Group	San Gabriel - Instersection Safety Improvements \$		20		Day		Maurice	John M	Deonne	99.0%							
3333	3/5/2021	City of Long Beach	Conant St, Carita St & Steamlee Ave. R-7153 \$		1690		Day	60 Working Days	Jeny	Jorge		99.0%				1			1
3380	3/10/2021	City of Westminster	Ward Street Improvements \$	2,696,290.00	15300		Day	80 Working Days	Jim	Doug	Deonne	99.0%				3/16/2021	3/16/2021	3/16/2021	1
3388	3/10/2021	GC- Visionary Service Inc.	MSWC Parking Lot #5 \$	181,282.00	1500		Day	10 Working Days	Augustine	Jerry	Gio	99.0%							Í
3351	3/11/2021	County of San Bernardino	Beech Avenue (Phase I) \$		3,530		Day	30 Working Days	Edward	Jim	Gio	99.0%							1
3530	3/11/2021	Lennar Homes	Edison Avenue Street Improvements \$	4,590,000.00	6000		Day	110 Working Days	Miguel	Jerry	Gio	5.0%			1	6/24/2021	6/24/2021	7/6/2021	DocuSign
3374	3/18/2021	City of San Bernardino	Seal) \$				Day	60 Calendar Days	Edward	John W	Gio	99.0%			1				
3528	3/23/2021		FY 2020-21 CDBG Street Improvements \$	458,770.00		0	Day	60 Calendar Days	Augustine	Jim	Gio	99.0%							
3521	3/31/2021		Traffic Signal Installations and Modifications \$			50	Day		Maurice	John W	Deonne	99.0%			3.355				
3637	4/1/2021		LA Country Club Parking Rehab \$				Day	90 Working Days	Augustine	Јепу	Gio	99.0%							
3535	4/2/2021	Lennar Homes	Off-Site Street Improvements -Tract Map 20092, El Rar \$				Day	110 Working Days	Miguel	Jim		80.0%				5/11/2021	5/11/2021	5/20/2021	DocuSign
432	4/5/2021		2020-2021 Annual Slurry Seal Project \$	296,353.70			Day		Brian	Darren		99.0%				5/6/2021		5/7/2021	FedEx
562	4/5/2021	City of Banning	Ramsey Street and Hathaway Street Improvements \$				Day	180 Working Days	Gordon	John W	Gio	92.0%				5/27/2021		6/21/2021	Docusign
396	4/7/2021		Carson St. B/T West City Limits to Clark Ave R-7131 \$.,			Day	60 Working Days	Jerry	Jorge		75.0%							-
590	_ 4/7/2021	City of Inglewood	Centinela Aven Medians & ADA Improvements \$	6,850,739.50			Day	200 Working Days	Gordon	John M	Deonne	60.0%				6/8/2021			
421	4/8/2021		El Evado and Other Roads \$				Day	60 Working Days	Edward	Jim	Gio	99.0%					(
3582	4/8/2021	AMES Construction	08-0E3304 Route 60 \$				Night	340 Working Days	Jim	Art		0.0%			1	6/8/2021		6/10/2021	
693	4/8/2021	City of Anaheim	Anaheim Island Phase 2 Rehabilitation Project RCP202 \$				Day	22 Working Days	Kim	Rick		99.0%							1
442	4/13/2021	J & M Conc Contractors	LAWA ITFW - Los Angeles Airport \$	70,862.65			Day		Gordon	Todd		99.0%				4/19/2021			
465	4/14/2021	City of Garden Grove	Arterial Street Rehabilitation \$	-,,			Day	100 Working Days	Jim	TBD		99.0%				4/28/2021	4/28/2021	5/3/2021	
3497	4/14/2021	City of Jurupa Valley	Mission Boulevard Pavement Rehabilitation \$	1,488,488.00			Day	40 Working Days	Maurice	John W	Gio	99.0%				5/24/2021	5/24/2021	5/28/2021	FedEx
3639	4/15/2021	R.V. Concrete	Route 91, 15 08-1L6804 \$				Night	95 Working Days	Jim	Art		0.0%				6/22/2021	6/22/2021	6/23/2021	
3439	4/16/2021		Dist. 8 44th Street, 44th Ave & 44th Way R-7153 \$				Day	60 Working Days	Jerry	Jorge		99.0%							
3443	4/16/2021	City of Long Beach	Dist. 3 Channel Dr. (PCH to 7th St.) R-7153 \$				Day	30 Working Days	Jerry	Jorge		99.0%							
3451	4/19/2021	City of Long Beach	Dist. 4 St. Louis Ave. Dawson Ave. Spaulding St. \$	137 314.03	359	1	Day	30 Working Days	Jerry	Jorge	-	99.0%				10			

ob No.#	Date	Agency / Owner	Project Title	Bid Amount	AC Tonnage	Concrete	Day/Nigh	Contract Time	P.M.	Supt	Coor	Completed	Dirt Removal	Concrete Removal	Grindings	Cont. Rec.	Date of Letter	Sent Back	Via	
33624	4/21/2021	City of Lake Elsinore	Collier Ave Pavement Rehab & Striping Project \$	1,192,114.05	13467	45	Night	40 Working Days	Gordon	John W	Gio	99.0%					1			
33537	4/22/2021	City of Riverside	Overland (Phase 1) Water Main Replacement Project	252,265.00	548	62	Day	35 Working Days	Kim	Jerry	510	99.0%				5/20/2021	5/20/2021	5/20/2021	PO Email	=
33581	4/22/2021	Ortiz Enterprises Inc.	Route 405 - 07-293604	1,010,235.00	8370		Night	580 Working Days	Jim	Art		2.0%				9/17/2021		9/17/2021	1	
33700	4/22/2021	City of Palos Verde Estates	Via Campesina Street Improvements #PW-681-20 \$	248,888,00	1260	10	Day	30 Working Days	Maurice	John M	Gio	99,0%				6/2/2021	6/2/2021	6/4/2021	Email/fedex	
33491	4/28/2021	Lennar Homes	Rancho Diamonte TR. 35393-1 - Hemet \$	608,608.00	4000	2000	Day	80 Working Days	Miguel	Jim		99.0%				5/20/2021	5/20/2021	5/20/2021	DocSign	
33522	4/28/2021	City of Buena Park	Dodds Avenue Pavement Rabbilitation \$	316,316.00	1160	110	Day	40 Working Days	Maurice	Rick	Gio	99.0%				5/12/2021	5/12/2021	5/20/2021	FedEx	
33539	5/4/2021	City of Corona	Street Pavement Maintenance & Rehabilitation \$	2,644,044.00	18000	183	Day	60 Working Days	Kim	Jerry	-	99.0%				5/19/2021	5/19/2021	5/20/2021	docusign	_
33656	5/4/2021	Fullmer Construction	Logistics Center Eastvale \$	2,779,779,00	1000	1200	Day	110 Working Days	Miguel	Jim		80.0%			-	6/25/2021	6/25/2021	7/15/2021	FedEx	
33730	5/4/2021	Pavement Coatings Inc	2021 Street Maintenance Project \$	368,381.00	1860	50	Day	(00 Mindian Dava	Maurice	John W	Gio	99.0% 99.0%				8/3/2021 8/3/2021		8/4/2021 8/4/2021	Email	_
33781	5/5/2021 5/5/2021	City of Riverside	2019/2020 Arterial & Minor Streets, Phase 3 \$ Plaza Del Amo at Western Ave Mobility \$	2,795,350.00	2000	1000 290	Day	100 Working Days 90 Working Days	Jim Gordon	John W John M	Deonne	99.0%				7/21/2021	7/19/2021	8/3/2021	FedEx	
33855 33580	5/10/2021	City of Torrance City of El Monte	Cedar Ave, Lower Azusa Road, City Limit Area \$	2,373,225.00	6890	645	Day Day	60 Working Days	Gordon	Jim	Gio	99.0%				6/24/2021	6/24/2021	6/25/2021	FedEx	
33507	5/11/2021	City of Moreno Valley	Juan Bautista De Anza Multi-Use Trail - Phase 1	733,202.00	2020	1000	Day	110 Working Days	Augustine	John W	Gio	85.0%	-			6/16/2021	6/16/2021	OF LOVE OF I	TCULX	-
33561	5/11/2021	City of Bell Gardens	Various Residential Street Improvements FY 20-21	451,000.00	1340	200	Day	40 Working Days	Augustine	Rick	Gio	99.0%				5/26/2021	5/26/2021			+
33764	5/12/2021	City of Santa Clarita	2020-21 Annual Slumy Seal \$	866,304.45	2200	0	Day	30 Working Days	Gordon	John M	Deonne	99.0%				6/9/2021	6/9/2021	6/28/2021		
33515	5/13/2021	County of San Bernardino	Gamet Street and Other Roads \$	396,435.92	3,265	0	Day	20 Working Days	Edward	John W	Gio	99.0%								
33731	5/13/2021	City of Moreno Valley	Pavement Rehabilitation for Various Local Streets \$	1,294,784.00	4925	325	Day	160 Working Days	Gordon	John W	Gio	99.0%				6/17/2021	6/17/2021	6/28/2021		
33778	5/18/2021	Tri Pointe Homes, Inc.	Victoria Street Improvements - Fontana \$	268,268.00	500	200	Day	20 Working Days	Miguel	Jim	Gio	95.0%				8/22/2021	8/22/2021	9/29/2021	DocuSign	
33907	5/18/2021	County of Orange	Phase 2 - Panorama Heights Grind & Overlay \$	899,446.00	4907	136	Day	35 Working Days	Gordon	Rick	Gio	99.0%							_	_
33945	5/18/2021	County of Orange	St. Andrews Parking Lot Slurry Seal \$	47,752.59	0	0	Day	10 Working Days	Gordon	Rick	Gio	99.0%								_
34532	5/18/2021	County of Orange	Grind & Pave Old Courthouse \$	60,380.80	130	3	Day	21 Working Days	Gordon	Rick	Gio	0.0%							-	_
34647	5/18/2021	County of Orange	7 ditemo i di kilar	1,949,626.83	12871	0	Day	30 Working Days	Gordon	Rick	Gio Gio	0.0%								
34649	5/18/2021 5/18/2021	County of Orange County of Orange	Hidden Ranch \$ JOC for Pavement Maintenance FY 2021-2022 \$	1,220,070.43 722,723.35	7087	0	Day Day	30 Working Days 365 Calendar Days	Gordon Gordon	Rick	Gio	0.0%								-
33529	5/19/2021	Duke Realty	Beech & Santa Ana Street Improv - Fontana \$	401,734.50	1220	300	Day	40 Working Days	Miguel	Jim	010	99.0%				5/11/2021	5/11/2021	5/20/2021	DUKE Conn	ect
33532	5/19/2021	Duke Realty	Los Angeles St. & Rivergrade Rd - Irwindale \$	220,627.35	700	100	Day	20 Working Days	Miguel	Jim		85.0%				5/11/2021	5/11/2021	5/20/2021	DUKE Conn	
33533	5/19/2021	City of Long Beach	Dist. 9 - 68th St., Atlantic Ave to Orange Ave.R-7153 \$	648,732.00	1154		Day		Jerry	Jorge		99.0%								T
33534	5/19/2021	Lewis Operating Corp.	Parkside In-Tract Streets \$	716,771.76	3500	700	Day	60 Working Days	Miguel	Jim		90.0%				7/9/2021	7/9/2021	7/12/2022	DocuSign	
33559	5/20/2021	City of Agoura Hills	FY 2021-2022 Pavement Rehabilitation Project \$	804,553.44	2425	215	Day	45 Working Days	Augustine	John M	Deonne	99.0%				6/3/2021		6/3/2021	FedEx	
33567	5/20/2021	City of Lake Forest	Glenn Ranch Road Rehabilitation Project \$	1,422,422.00	11010		Day		Maurice	Rick	Gio	99.0%				5/26/2021	5/26/2021	6/9/2021	Fedex	-
33616	5/20/2021	City of Azusa	Residential Resurfacing Project 2021 \$	897,324.50	800	500	Day	30 Working Days	Brian	Jim		99.0%				6/22/2021	6/22/2021	7/2/2021	FedEx	4
33626	5/20/2021	City of Ontario	2021 Fall Pavement Rehabilitation Project \$	4,433,499.00	24877	2585	Day	20 Madding Day	Maurice	John W	Gio	99.0%				5/24/2021	5/24/2021	5/27/2021	FedEx	1
33646 33649	5/20/2021 5/20/2021	City of West Covina City of El Monto	Fire Station No. 4 Parking Lot Improvements \$ El Monte Bike Blvd, and Pavement Rehabilitation	208,194.00	450 3530	209	Day	30 Working Days	Kim	Jim	Gio	99.0% 99.0%				6/22/2021	6/22/2021	7/6/2021	Hand Del. E	٧.
33649	5/20/2021	City of El Monte City of Long Beach	El Monte Bike Blvd, and Pavement Rehabilitation \$ Myrtle Ave. B/T Market St. & South St. R-7153 \$	948,744.00 130,853.00	3530	135	Day Day	40 Working Days 10 Working Days	Gordon Jerry	Jim Jorge	910	99.0%					+			+
33665	5/25/2021	City of Aliso Vielo	FY 21-22 Slurry Seal & Rehabilitation \$	511,563.00	4	0	Day	30 Working Days	Brian	Darren		99.0%								-
33658	5/27/2021	City of Norwalk	Local Zone Street Rehabilitation Program - Phase 1, Zo \$		0	0	Day	40 Working Days	Brian	Darren		99.0%								-
33629	5/28/2021	City of Mission Viejo	Asphalt Repairs & Asphalt Overlays of Various St	1,422,777.00			Day	45 Working Days	Maurice			99.0%				6/15/2021	6/15/2021			
33564	6/1/2021	Century Communities	Perris Blvd Street Improvement \$	387,715.17	1000	200	Day	40 Working Days	Miguel	John W		99.0%				9/13/2021	9/13/2021	11/3/2021	DocuSign	
33588	6/1/2021	City of Paramount	Neighborhood Street Improvements on Various City Stn \$		5,340	434	Day	40 Working Days	Edward	Rick	Gio	99.0%				7/6/2021	7/6/2021			
33689	6/1/2021	City of Cerritos	Asphalt Improvements in Residential Streets Project #1 \$		225	0	Day	30 Calendar Days	Kim	Rick		99.0%				6/30/2021	6/30/2021	7/7/2021	FedEx	
33575	6/3/2021	City of Redondo Beach	Inglewood Ave at Manhattan Beach Blvd Intersection In		670	200	Day	90 Working Days	Augustine	John M	Deonne	6.0%				7/12/2021	6/21/2021			_
33762	6/3/2021	City of Fullerton	Runway Edges Enhancement Project \$	2,568,760.00	2800	0	Night	86 Working Days	Gordon	Doug	Deonne	95.0%				7/26/2021	7/21/2021	8/12/2021	FedEx	-
34108 33739	6/8/2021 6/9/2021	Walsh / City of Long Beach City of El Monte	Reconst Taxiway L Project @ The Long Beach Airport \$	1,785,410.00 1,887,325,00	13247 3,200	0 490	Day/Nigh Day	t 435 Working Days	Gordon Edward	Art Jim	Gio	8.0%	500 CY	520 CY	2,100 TN	7/14/2021	7/14/2021	7/20/2021	Fedex	
33739	6/9/2021	City of San Clemente	Active Transportation for El Monte Station and Downtow \$ FY2020 Major Street Maintenance FY2021 Slurry Seal \$		3,200	490 67	Day	60 Working Days 60 Working Days	Kim	Rick	910	99.0%	300 0 4	320 0 1	2,100 11	7/21/2021	7/21/2021	7/27/2021	Fedex	+-
33752	6/10/2021	Pavement Coatings Inc	2021 Annual Street Maintenance Project	126,400.00	380	0	day	20 HOURING Days	Maurice	Art		99.0%				1/2/2021	THE REVE !	nenevel.	TOULA	-
33583	6/14/2021	City of Long Beach	Outer Traffic Circle R-7131-A	526,097.92	526	Ť	Day		Јепу	Jorge		99.0%								
33609	6/14/2021	City of Long Beach	Atherton Place R-7131-A \$	56,097.92	527		Day		Jerry	Jorge		99.0%						1		
33610	6/14/2021	City of Long Beach	Sant Fe Ave. R-7131-A \$	263,505.66	845		Day		Jerry	Jorge		99.0%								
33699	6/17/2021	Lennar Homes	Monterado - Street & Storm Drain Improvements	779,779.00	4000	300	Day	30 Working	Miguel	Jim		85.0%				7/12/2021	7/12/2021	9/8/2021	DocuSign	_
33644	6/22/2021	City of Long Beach	Ocean Blvd. & 54th StreetR-7131-A \$	22,130.00	43		Day		Jerry	Jorge		99.0%								
33680	6/25/2021	City of Westminster	Street Improvemetns fro Mcfadden Avenue	1,142,160.00	6000	100	day	30 Working Days	Jim	Doug	Deonne	99.0%				6/30/2021	6/30/2021	7/9/2021	_	
33692	6/28/2021	City of Mission Viejo	Los Alisos Boulevard, Marguerite Parkway and Santa Margar		16400	510	Day	45 Working Days	Maurice	Rick	Gio	90.0%				74400001	7/4 4/0001	8/3/2021	E de la	
33706 33854	6/28/2021 6/30/2021	City of Mission Viejo	Via Escolar Pavement Rehabilitation Project \$ Westminster Library Parking Lot Seal Coat	174,471.00 21,102.95	1080	0	Day Day	30 Working Days 5 Working Days	Kim Gordon	Rick Rick	Gio	99.0% 99.0%	-		-	7/14/2021	7/14/2021	8/6/2021	FedEx	
33654	7/1/2021	County of Orange Century Communities	Westminster Library Parking Lot Seal Coat Tessera Tract 33370 Franklin and Auto Center Dr., Lake		1300	400	Day	60 Working Days	Miguel	NUN	310	80.0%	-			5/3/2021	5/3/2021	5/4/2021	DocuSign	+-
		source y sourceallings	Counter of the counter frammenta Auto Genter DL, Law 4		,500	-00	Day	se morning mails				00.070				U. U. EVA I	UN LUL I		o coordigin	
33709	7/1/2021	City of West Hollywood	Mid City, La Brea & SMB Pavement Repair Program	1,597,729.00	10460	0	Day	35 Working Days	Maurice	John M	Deonne	99.0%				7/12/2021	7/12/2021	7/20/2021	Fedex	
33694	7/7/2021	VCI Construction, INC. / LB	Shoreline Drive & Ocean Blvd. \$	65,915.00	33		Day		Јепту	Jorge		99.0%								
33705	7/7/2021	City of San Gabriel	2021 Pavement Rehabilitation Project \$	5,232,394.90	55,044	0	Day	60 Working Days	Edward	Jim		99.0%								
33720	7/15/2021	City of La Verne	2020-21 Hormel/Ramona Grind and Overlay Improveme		4404	0	Day	20 Working Days	Maurice	Jim	Gio	99.0%				7/15/2021	7/15/2021		Email/ Hand	Deliv
33747	7/20/2021	City of Rancho Mirage	Tamarisk Neighborhood Pavement Rehabilitation	350,618.00	1700	25	Day	60 Working Days	Augustine	John W	Gio	99.0%			-	9/2/2021	7/05/065	Dia mana -	FadE	
33787	7/22/2021	City of Anaheim	State College Boulevard Improvements from Ball Road	484,848.00	3500	140	Day	22 Working Days	Kim	Rick		99.0%				7/28/2021	7/28/2021	8/3/2021	FedEx	+
4076 3863	7/27/2021 7/28/2021	Lennar Homes City of Wildomar	Street Improvements - Tract Map 20205 (PA 2) and Tra Road Maintenance and Rehabilitation Project	1,956,956.00 664,622.50	8600 1672	1000	Day Day	240 Working Days 30 Working Days	Miguel Gordon	Jim John W	Gio	15.0%				9/27/2021 8/2/2021	9/27/2021 8/2/2021	10/6/2021 8/10/2021	DocuSign FedEx	+
4058	7/29/2021	City of Newport Beach	Mission Bay Drive Street Improvements		1310	1	Day	60 Working Days	Kim	Rick	310	99.0%				9/2/2021	9/2/2021	0,10/2021	TOULA	+
33776	8/5/2021	City of Ontario	ATP Lycle 4: Safe Routes To School Pedestrian Improvement \$		2890	4050	Day	300 CD	Maurice	John W	Gio	80.0%	1			7/30/2021			1	-
3794	8/5/2021	City of Long Beach	Alamitos Ave. Bikeway R-7131-A	166,493.31	4		Day		Jerry	Jorge		99.0%								1
3946	8/5/2021	City of Alhambra	FY 2020-2021 SB 1 Street Rehabilitation		11840	983	Day	60 Working Days	Gordon	Jim	Gio	96.0%				9/7/2021		9/17/2021		
3949	8/6/2021	City of Beaumont	Annual Citywide Street Rehabilitation & Maintenance \$	5,296,803.32	15148	572	Day	90 Calander Days	Gordon	John W		99.0%				9/17/2021		10/5/2021		
3813	8/11/2021	City of Long Beach	Del Amo Blvd. R-7131-A \$		4		Day		Jerry	Jorge		99.0%					-			
3826	8/12/2021	City of Long Beach	Winslow Ave Between Colorado Ave R-7153 \$		709		Day		Јепту	Jorge		99.0%								_
3914	8/12/2021	County of Ventura	Pavement Resurfacing - Simi Area, Spec. No. RD22-03		25	19	Day	40 Working Days	Kim	John M		99.0%				9/16/2021	9/14/2021	9/21/2021	FedEx	
33817	8/16/2021	City of Long Beach	Various Streets in District 7. R-7153	725,087.82	3046		Day	100.141	Jerry	Jorge		99.0%								-
3843	8/16/2021	Toll Brothers	The Meadows - Street Improvements	4,941,887.50	21100	2000	Day	120 Working Days	Miguel	Rick		75.0%	-			8/24/2021	8/24/2021	8/25/2021	DocuSign	-
3930	8/25/2021	City of Fountain Valley	Rehabilitation and Resurfacing of Euclid Street From Ec		8710	350	Day	30 Working Days	Jim	Rick	Gio	99.0%				9/20/2021	9/20/2021	9/22/2021	Dec Of	+
3894	8/30/2021	City of Corona	Street Pavement Maintenance & Rehabilitation 22-010F \$		37350	567	Day	100 Working Days	Kim	Jerry	0	98.0%				9/2/2021	9/2/2021	9/17/2021	DocuSign	-
3869	9/1/2021	Irvine Ranch Water District	MWRP Paving Near Buildings 90, 100, and 110 \$	174,991.00	300	25	Day	60 Working Days	Augustine	Rick	Gio	99.0%				9/3/2021	0/00/2004	10(4/2024	Denviller	+
4001	9/1/2021	Lewis Operating Corp.	Meridian Phase 3 Street Improvements \$	2,517,333.00	1000	7000	Day	100 Working Days	Miguel	John W		95.0%				9/29/2021	9/29/2021	10/1/2021	DocuSign	-
4041	9/2/2021	City of Gardena	Van Ness Avenue and 139th Street Improvement \$		7725	373	Day	60 Working Days	Gordon		Deonne	99.0%				10/5/2021	40/7/0001	10/19/2021	1	+
3986	9/4/2021	City of Rosemead	Walnut Grove Resurfacing Phase 1 \$	1,342,157.00	6200	500	Day	35 Working Days	Jim	Jim		99.0%				10/7/2021	10/7/2021	10/11/2021		_

ob No.#	Date	Anency (Owner	Project Title	Bid Amount	AC Tonnage	Concrete	a Daw/Ninh	Contract Time	P.M.	Sunt	Coor	Completed	Removal	Concrete Removal	Grindinas	Cont Rec	Date of Letter	Sent Back	Via	
JD NO.#	Date	Agency / Owner	Project Title N. Concourse Avenue Street Improvement Project CP		AC ronnage	concrete	e vay/Nigh	Contract Lime	r.M.	Supt	Coor	Completed	rtentoval	Nemoval	Grinaings	Cont. Rec.	Letter		Via	_
34059	9/8/2021	City of Montebello	880	224,473.00	921	72	Day	35 Working Days	Kim			98,0%				11/18/2021	11/4/2021			
4264	9/9/2021	Griffith Co.	Main Street Interchange - Lake Elsinore \$	446,979.00	3860	0	Day/Nite		Gordon	Art		0.0%				2/10/2022	THELL	2/10/2022		-
3868	9/10/2021	City of Long Beach	South Street \$	512,083.30	1995		Day		Jerry			99.0%								_
3898	9/13/2021	City of Long Beach	5th Street Margo to East End R-7153						11.17			99.0%								
3975	9/13/2021	City of Long Beach	Dist. 5 Ebell St Greenbrier Rd. R-7153 \$	198,158.80	240		Day		Jerry	Jorge		99.0%								
4117	9/14/2021	City of La Verne	Country Club and Monterey Et Al Grind, Overlay, ARAM \$	722,971.55		-			Maurice			99.0%				11/3/2021	10/28/2021	11/16/2021	FedEx	
3911	9/15/2021	City of Long Beach	Long Beach Airport R-7131-A \$	241,389.77	2004	_	Day		Jerry	Jorge		0.0%								_
3956	9/16/2021	Private Owner-Jay Du Nesme	Asphalt Repair Forset Glen Rd - Twin Peaks \$	76,826.00	410	0	Day	15 Working Days	Augustine	Jerry		99.0%								
3992	9/16/2021	City of Alhambra	Street Improvements Project Bid No. #N2M21-2 \$	333,333.33	1362	154	Day	40 Working Days	Kim	Jim		95.0%		0		09/30/20201	9/30/2021	10/12/2021	FedEx	
3924	9/21/2021	City of Long Beach	Grand Prix Race Track R-7131-A \$	38,400.00	4		Day		Jerry	Jorge		0.0%								
4126	9/21/2021	Lennar Homes	Adobe Springs Tract 36733 Winchester Road Street and \$	1,029,029.00	2100	500	Day	120 Working Days	Miguel	John W		0.0%				10/18/2021	10/18/2021	10/18/2021		
3938 4162	9/24/2021 9/26/2021	City of Moreno Valley City of Riverside	Heacock St Ped/Bike Enhancements & Gregory Ln to 6 \$ 2020/2021 SB-1 Street Maintenance Improvements \$	395,254.00	600 20000	60 800	Day	80 Working Days	Augustine	John W	Gio Gio	99.0%				12/10/2021	44/40/2024	12/14/2021	FedEx	_
3990	9/28/2021	City of Costa Mesa	Randolph Avenue and St. Clair Street Improvement \$	4,734,134.00 382,725,50	40	82	Day Day	140 Working Days 45 Working Days	Jim Kim	John W Doug	Giù	0.0%		(11/10/2021 10/11/2021	11/10/2021 10/25/2021	11/15/2021 11/2/2021	FedEx	_
4175	9/28/2021	City of Costa Mesa	Citywide Parkway Maintenance, Street Rehabilitation ar \$	2,828,000.00	14273	752	Day	100 Working Days	Kim	Doug		30.0%				2/22/2022	1/4/2022	THEFE	FOULA	_
3950	9/29/2021	City of Long Beach	Dist. 5 All Streets R-7153	45,000.00	4	105	Day	ree troning buje	Jerry	Jorge		99.0%				CLECCE	1747EVEL			-
3964	10/4/2021	Los Angeles Country Club	Los Angeles Country Club Tennis Lot Asphalt Repair \$	209,141.00	940	0	Day	15 Working Days	Augustine	Јепту	Gio	99.0%				9/30/2021		10/4/2021		-
3969	10/5/2021	City of Norco	Wayne Makin Park Slurry Seal Project \$	52,725,89	15	0	Day		Brian	Darren		99.0%								-
3967	10/6/2021	City of Norco	Corporate Yard Pavement Rehab \$	612,755.00	2000	50	Day	45 Working Days	Augustine	Jenry	Gio	99.0%		0		10/22/2021	-	11/8/2021		
3979	10/7/2021	City of Highland	Pavement Management Program \$	2,098,506.00	5299	100	Day	55 Working Days	Augustine	Jim	Gio	99.0%				10/27/2021		11/8/2021		-
4166	10/7/2021	Burbank-Glendale-Pasadena Airpo	Taxilane Alpha Rehabilitation - Burbank Airport \$	1,197,129.65	5644	0	Night	60 Working Days	Gordon	Doug	Deonne	95.0%				10/26/2021		11/23/2021	FedEx	
4344	10/7/2021	Lennar Homes	Tract 19787 - Grand Park Street, "A" Street, Archibald A \$	2,218,218.00	9000	600	Day	35 Working Days	Miguel	John W		0.0%				2/8/2022	2/8/2022	2/10/2022	DocuSign	
3978	10/11/2021	City of Long Beach	Dist. 5 Olser Ave. & Parkcreast St. R-7153 \$	438,789.40	854		Day		Jerry	Jorge		99,0%								
3980	10/11/2021	City of Long Beach	Dist. 5 Monlaco Rd. to Woodruff Ave. R-7153 \$	823,807.10	4		Day		Jerry	Jorge		99.0%								
981	10/11/2021	City of Long Beach	Dist. 5 Monlaco Rd. Clark to Tulaln Ave. R-7153 \$	821,623.37	2333		Day		Jerry	Jorge		99.0%								
996	10/11/2021	City of Long Beach	Dist. 4 Resevior Dr. \$	583,250.00	1143		Day		Jerry	Jorge	_	99,0%		_						
4438	10/14/2021	Walsh	Mckinley Grade Separation - Corona \$	1,089,897.00	12557	0	Both	460 Working Days	Gordon	Art		0.0%				1/24/2022		1/24/2022	docuSign	
	10/14/2021	City of El Monte	Sewer Replacement Nevada Avenue & Bodger St Area \$	3,055,667.90			Day		Bob			0.0%								
3997	10/18/2021	City of Long Beach	Grand Ave. Beween 10th Street & 11th Street \$	226,312.76	262		Day		Jerry	Jorge		99.0%								
4023	10/18/2021	CitY of Long Beach	Woodruff Ave.B/T Palo Verde Ave & Conquista Ave. \$	105,274,45	197	_	Day		Јепу	Jorge	_	99.0%								
1024	10/18/2021	City of Long Beach	17th Street Between Cherry Ave & Junipero Ave. \$	457,508.00	695		Day		Jerry	Jorge		99.0%						·	_	_
4131	10/22/2021	NASCAR	New Valley Construction-NASCAR Coliseum Paving prc \$	530,910.00	2680	0	Day		Maurice	Art	Gio	99.0%								_
1355	10/22/2021	RMV Realty, Inc.	PA-3.2A Street Improvements \$	1,244,244.00	7500	800	Day	75 Working Days	Miguel	Rick		88.0%				11/9/2021	11/9/2021	11/9/2021	DocuSign	_
4119	10/28/2021	City of Newport Beach	East Coast Highway and Marguerite Avenue Pavement \$	3,363,056.00	18972	662	Day	80 Working Days	Kim	Rick	01.	98.0%	_			12/1/2021	11/30/2021	44/40/0004		_
1144	10/29/2021 11/1/2021	City of Laguna Woods Toll Bros., Inc.	Pavement Management Plan Project Moulton Parkway \$ Metro Heights (Montebello Hills) - PHASE 1 AND 3 Stre \$	172,969.00 2,675,250.00	1300 9000	0 800	Day	20 Working Days	Maurice	Rick Rick	Gio	99.0% 98.0%				44/0/0004	44/0/0004	11/18/2021	FedEx	-
065	11/9/2021		Casa Verdes Pavement Rehabilitation	2,675,250.00	840	008	Day Day	160 Working Days 25 Working Days	Miguel Augustine	John M	Deces	98.0%				11/2/2021	11/2/2021	11/17/2021	DocuSign	-
4070	11/18/2021	City of Long Beach	Dist. 9 - 60th Street between Atlantic to Orange Ave. R- \$	717,651.58	1334	U	Day	25 WORKing Days	Jerry		Deonne	0.0%								
4070	11/18/2021	City of Long Beach	Dist. 9 -72nd St, between Atlantic PI, & Myrtle Ave, R-7 \$	238,577.90	505	_	Day		Јепу	Jorge Jorge		99.0%								-
4163	11/30/2021	Robertson's Ready Mix	Ramsey & Hathaway Improvements	413,710.75	2630	150	Day		Gordon	John W	Gio	76.0%								-
4114	12/2/2021	City of Long Beach	Pine Ave., Aquarium Way, & Queens Way \$	65,184.00	5	100	Day		Jerry	Jorge	010	99.0%								-
4116	12/2/2021	The Metropolitan Water District of		1,936,977.00	11,150	153		140 Working Days	Edward	John W		99.0%				1/12/2022	1/12/2022	1/17/2022		-
34218	12/2/2021	City of El Monte	Traffic Calming Plan with Class IV Bike Lanes \$	897,024.16	2810	11	Day	120 Working Days	Gordon	Jim	Gio	95.0%			~	2/28/2022	1/12/2022	111/2022		-
34481	12/2/2021	Green Giant Landscape	Bluff Top Parl Trail - HB \$	395,374.00	2500	0	Day	30 Working Days	Jim	Art	GID	99.0%				4/18/2022	4/18/2022	4/20/2022		-
			Industrial Streets (Phase 1) Water and Sewer Main		2000		Daj	ou monang buju			-	00.070				4/10/2022	HIGEOLL		-	-
4550	12/2/2021	SRK Engineering	Improvements \$	610,838.90	5510	0	Day	75 Working Days	Jim	Art		0.0%				5/4/2022	5/4/2022	5/11/2022		
34614	12/6/2021	Riverside Construction	Loma Linda- California Street Widening \$	525,350.00	5110	0	Day		Maurice	Art		0.0%								
34154	12/7/2021	City of Newport Beach	Jamboree Road Pavement Rehabilitation and Reclaime \$	3,955,555.55	19950	700	Day	80 Working Days	Kim	Rick		60.0%				1/28/2022				
4439	12/7/2021	Wright Construction	Dunlap Bridge \$	29,000.00	150	0	Day	100 Calendar Days	Gordon	Art		0.0%								
4134	12/8/2021	County of Riverside Transportation	Rancho Callifornia Road and Anza Road \$	1,049,260.40	5,200	9	Day & Nigl	14 Days	Edward	John W		99.0%								
4164	12/10/2021	City of Huntington Beach	Junior Lifeguard Parking Lot Part of Annual Contract \$	608,710.44	2523	10	Day	30 Working Days	Jim	Jorge	Deonne	0.0%				12/13/2022	12/13/2022	12/15/2022		
4141	12/13/2021	City of Manhattan Beach	Slurry Seal Project Central Area of Sand Section \$	673,275.00	50	0	Day	45 Working Days	Brian	Darren		99.0%								
4389	12/14/2021	City of Burbank	Local/Residential Street Rehab Phase 1 of Cycle 2 \$	7,761,320.00	51100	918	Day	140 Working Days	Gordon	John M	Deonne	5.0%				2/18/2022		3/3/2022		
4155	12/15/2021	Eastern Municipal Water District	Paving Repair at Murrieta Rd & Margarita Rd-Murrieta \$	63,000.00	150	0	Night	25 Working Days	Augustine	John W	Gio	99.0%					· · · · · · · · · · · · · · · · · · ·			
4200	12/15/2021	City of Laguna Niguel	Niguel Road (Alta Terra To Highlands Avenue) Paveme \$	866,924.00	3375	220	Day	60 Working Days	Maurice	Rick	Gio	50.0%						II		
4248	12/16/2021	R.V. Concrete	Caltrans 08-1J2104_Route 60 Chino \$	122,100.00	780	0	Night	370 Working Days	Jim	Art		50.0%				2/10/2022	2/10/2022	2/22/2022		
4347	12/16/2021		Off-Site Improvements in Sierra Avenue, Duncan Canye \$	1,989,000.00	13000	1500	Day	120 Working Days	Miguel	Jim		70.0%				2/2/2022	2/2/2022	2/7/2022	FedEx	
4153	12/17/2021	City of Santa Ana	2022 Asphalt Pothole Repair \$	552,770.00	900	0	Day	365 Calendar Days	Maurice	Art		25.0%							_	1
	10/04/	2	Palomar, McVicar and Grand Street Signing & Striping	1,177,177.00																
4465	12/21/2021	Beazer Homes	Improvements in the City of Wildomar		2000	600	Day	60 Working Days	Miguel	John W		5.0%				1/01//2022	11/5/1900			_
4172	12/28/2021	City of Eastvale	2021 Annual Asphalt Concrete Overlay Project (Pro \$	3,169,744.00	28065	0.00	Day	45.111	Maurice	John W		90.0%				1/14/2022	1/12/2022		-	_
4216	1/4/2022	City of Norwalk	Local Streets Rehabilitation-CDBG FY 21-22 \$	1,041,470.00	4550	360	Day	45 Working Days	Gordon	Rick	Gio	99.0%				1/21/2022	4/48/2000	1/31/2022	FedEx	_
4184	1/6/2022	City of San Bernardino	Pavement Rehab at Nine Locations \$	4,738,119.00	24,700			120 Working Days	Edward	John W		90.0%				1/15/2022	1/15/2022	1/18/2022		_
4291 4562	1/6/2022	City of Vernon	Pacific Blvd., Santa Fe, & Vemon Ave Street Improvem \$	878,606.00	4500	0	Day	45 Working Days	Jim	John M	Deonne	0.0%				3/8/2022	3/8/2022	3/10/2022	Deer: O'-	_
4562	1/6/2022	Landsea Homes City of Newport Beach	Coyote Canyon Road Street Improvements \$ Via Lido Soud and Nord Pavement Rehabilitation Contr	1,299,299.00 958,859,00	9600 4268	900 63	Day	30 Working Days	Miguel	Jim		0.0%			_	3/25/2022	3/25/2022	3/25/2022	DocuSign	-
4171 4195	1/7/2022	VLJM, LLC	Repair Asphalt Main Parking Lot - Camp Pendelton \$	284,797.00	4268	63	Day Day	80 Working Days	Kim Augustine	Rick	Gio	99.0% 99.0%				1/26/2022	12/23/2021		-	_
4195	1/11/2022	Heritage Fields El Toro, LLC	District 2 Marine Way Street Improvements, City of Irvir \$	2,949,900.00	13000	800	Day	10 Working Days 160 Working Days	Miguel	Jerry Rick	GIO	0.0%				5/12/2022	5/12/2022	5/20/2022	FedEx	_
4202	1/12/2022	City of Buena Park	Eight Street Rehabilitation Project \$	2,949,900.00	1740	100	Day	4 Working Days	Augustine	Rick	Gio	99.0%				1/26/2022	5/12/2022	5120/2022	reuex	-
437	1/12/2022	City of Torrance	Residential & Arterial Pavement Improvement \$	7,077,915.00	39444	190	Day	150 Working Days	Gordon	John M	Deonne	0.0%	1.065 CY	105 CV	37,800 TN	1/20/2022				-
249	1/13/2022	City of Downey	Florence Ave Pavement Rehabilitation Project Capital 1	1,459,369.00	11475	220	Day	60 Working Days	Maurice	Rick	Gio	99.0%	1,005 01	193 0 1	57,000 TN	1/27/2022	1/26/2022			-
	1/15/2022	JM Construction Inc	Fallbrook Redeve Road Pavement Repair \$	343,674.00	1800	0	Day	120 Calendar Days		Jerry	Gio	0.0%				2/1/2022	ILVILUEZ			-
1298	1/17/2022	Long Beach Water	WD-08-22 Street Renair Services Contract No. 3659 \$	200,000.00	1000		Day	ine calendar Days	Kim	Jorge	0.0	0.0%				1/13/2022	1/13/022			-
220	1/18/2022	Duke Realty	Perry St. & Barrett Ave. Street Improvements - Perris \$	496,701.00	1500	400	Day	45 Working Days	Miguel	Jared		35.0%				1/27/2022	1/27/2022	1/28/2022	DocuSign	i
1251	1/25/2022	City of Rancho Cucamonga	Foothill Blvd Pavement Rehabilitation	1,689,439.00	7890	240	day	55 Working Days	Maurice	Jim	Gio	50.0%				2/21/2022	2/16/2022	2/24/2022	fedex	÷
1267	2/1/2022		FY 21/22 Annual Residential Overlay \$	135,693.00	845	0	Day	25 Working Days	Jim	Rick	Gio	99.0%				2/2/2022	2/2/2022	2/4/2022	1000X	-
1268	2/1/2022	City of Santa Ana	Gamey Business Improvements \$	4,189,151.00	18000	2000	Day/Night		Jim	Rick	Gio	30.0%				2/9/2022	2/9/2022	2/14/2022		
4325	2/1/2022	City of Santa Ana	Macarthur Boulevard Resurfacing: Flower Street to Mair \$	823,333.00	3330	300	Day	60 Working Days	Jim	Rick	Gio	0.0%				4/5/2022	4/5/2022	4/6/2022	1	Ĩ
4374	2/1/2022	Chino Preserve Development	Town Center Street Improvements for Community Facil \$	7,699,707.00	12000	2000	Day	140 Working Days	Miguel	Jerry	310	0.0%				3/3/2022	3/3/2022	3/17/2022	Email	-
		and a second sec						is creating ways	million	cond.		0.070					LULL			-
4552	2/1/2022	Harbor Companies	08-1M0004 \$	224,500.00	54	298	Night	45 Working Days	Jim	Jim		0.0%				5/4/2022	5/4/2022	5/10/2022		
4242	2/3/2022	City of Norco	Dales Drive and Parkridge Avenue Street Improvement \$	512,465.00	1,850			50 Working Days	Edward	Јепту		99.0%				3/9/2022	39/2022	3/14/2022		1
4297	2/3/2022	City of Riverside	Permanent Trench Resurfacing for Garfield and Overlar \$	323,323.00	1220	74	Day	21 Working Days	Kim	John W	Gio	99.0%								ŝ

				Bid Amount									Dirt	Concrete			Date of	Sent Back	-	
Job No.#	Date	Agency / Owner	Project Title		AC Tonnage	Concrete		Contract Time	P.M.	Supt	Coor	Completed	Removal	Removal		Cont. Rec.	Letter		Via	_
34663	2/4/2022		Taxilane G		510	0	Day	30 Working Days	Gordon	Doug	Deonne	0.0%	0 CY	0 CY	510 TN					
34250	2/7/2022		FY 2021-2022 Slurry Seal Project 5		120	0 3	Day	30 Working Days	Brian	Darren	01.	50.0% 50.0%				3/15/2022	3/15/2022	3/23/2022		
34255	2/8/2022	· · · · · · · · · · · · · · · · · · ·	I-15 Interim Corridor Operations Project and Related Wi S Route 215		3,100			105 Working Days	Édward	John W	Gio							5/6/2022	_	-
34526	2/8/2022		110010 210		7030	0	Day	90 Working Days	Jim	Art		5.0%				5/3/2022	5/3/2022	5/6/2022		
34292	2/10/2022				10200	20	Day	120 Calendar Days	Augustine	Jerry	Gio	99.0%		0.014	0.711					_
34273	2/11/2022		Crenshaw Repair		100	0	Day	10 Working Days	Gordon	John M.	Deonne	0.0%	0 CY	0 CY	0 TN					_
34375	2/17/2022	Caltrans	12-0S8604 - Route 39		21300	0	Day	80 Working Days	Jim	Doug	Deonne	0.0%				3/11/2022	3/11/2022	3/16/2022		
34584	2/24/2022	Wreck Age Demolition, Inc.	Gladstone Reservoir Demolition & Parking Lot Improv		521	0	Day	4 Working Days	Augustine	Jim	Gio	0.0%								
34482	2/25/2022	City of Riverside	Permanent Trench Resurfacing for Oleander Court Wat	115,511.00	220	10	Day	21 Working Days	Kim	John W		0.0%								
34124	2/28/2022	City of Long Beach	Atlantic Ave. between 10th & Anaheim Street	163,394.80	30		Day		Jerry	Jorge		0.0%								1.0
34405	3/1/2022		Repair Asphalt Road 53 Area to San Mateo Rd		11600	20	Day	120 Working Days	Augustine	Jerry	Gio	95.0%								
34431	3/1/2022		Neighborhood St Improvement on Various City Streets F		3752	440	Day	40 Working Days	Maurice	Rick	Gio	0.0%				3/21/2022	3/17/2022			
34466	3/1/2022		Merrill Avenue Street Widening	915,915.00	4600	0	Day	40 Working Days	Miguel	Jerry		0.0%				4/5/2022	3/16/2022	4/8/2022	DocuSign	-
34432	3/2/2022		2021-22 Street Improvement Project		1620	260	Day	60 Working Days	Maurice	Jim	Gio	0.0%				3/29/2022	3/29/2022	3/31/2022	FedEx	
34460	3/2/2022		Market Street Corridor Improvement Project R-7177		11500	1423	Day	240 Working Days	Kim	Jorge	Deonne	0.0%	627 CY	1,633 CY	6,210 TN	4/1/2022	4/4/2022		A	
34333	3/4/2022		Dist. 7 - 37th Street b/t Country Club Dr. & Pacific Ave.		170		Day		Jerry	Jorge		0.0%								-
34334	3/4/2022	City of Long Beach	Dist. 8 - Country Club Dr. b/t San Anotnio & Pacific Ave		3552		Day		Jerry	Jorge		0.0%								-
34335	3/4/2022	City of Long Beach	Dist. 1 - 16th Street between Pacific Ave. & Elm Ave.	467,176.91	587		Day		Jerry	Jome		0.0%							hin	-
34336	3/7/2022	Duke Realty	Citrus & Slover Street Improvementt - Fontana	396,172.75	300	150	Day	40 Working Days	Miguel	Jim		5.0%				2/22/2022	2/22/2022	2/22/2022	DocuSign	-
34337	3/7/2022	Duke Realty	Rider & Harvill Street Improvement - Perris	585,950.00	1400	500	Day	60 Working Days	Miguel	John W		0.0%				3/3/2022	3/3/2022	3/3/2022	DocuSign	
34338	3/7/2022	Moote Companies	Palomino Off-Site Improvements - Norco	2,399,483.11	5500	900	Day	110 Working Days	Miguel	Jerry		5.0%				2/28/2022	2/28/2022	3/4/2022	DocuSign	
34363	3/9/2022		Westlake Village, FY 21-22 Project 5	1,025,336.20	3,300	18	Day	35 Working Days	Edward	John M	Deonne	95.0%				4/21/2022	4/21/2022	4/26/2022		
	3/10/2022		Fire Station 31-Seismic Retrofit-Reloc Site Improv		600	0	Day	4 Working Days	Augustine	Jim	Gio	0.0%								-
34376	3/14/2022		Dist. 2 - Bremuda Street between Cherry Ave. & Juniper		3	-	Day		Jerry	Jorge		0.0%							1	
34377	3/14/2022		Dist. 8 - Locust Ave. between Silva St. & Mountain View		3		Day		Jerry	Jorge		0.0%								
34378	3/14/2022	1 10 10 C	Dist, 8 - Atlantic Avenue between 45th Street and 46th 5		5		Day		Sar	1.1.1		0.0%					-			
343/0	3/14/2022	ony of congleading	Dist, 0 - Allanut Avenue between som oneer and 40th t				Day		Jerry	Jorge		0.076								
34379	3/14/2022	City of Long Beach	Dist. 8 - Pacfic Ave, between Del Amo Blvd, & 52nd St.	376,439.62			Day		Јепу	Jorge		0.0%								
34380	3/14/2022		Dist. 7 - 27th Street between Delta Ave. & Gale Ave.	340,774.47			Day		Jerry	Jorge		0.0%								
34381	3/14/2022	City of Long Beach	Dist. 7 - Cota Avenue between 25th Street & Willow Ave	257,370.99			Day		Jerry	Jorge		0.0%								
34410	3/15/2022	K1 Speed, Inc.	K1 Speed Race Track-Paving 5	1,170,858.00	4112	0	Day	15 Working Days	Maurice	John W		99.0%								
34433	3/22/2022	La Habra Heights	FY 2020-21 Street Improvement Project 1031522-	1,066,168.00	2574	40	Day	80 Working Days	Maurice	Rick	Gio	10.0%				4/12/2022	4/12/2022	4/22/2022	FedEx	
34452	3/23/2022	Meritage Homes	Sorenstam Drive Street Improvements - Beaumont, CA	894,889.00	4000	800	Day	35 Working Days	Miguel	John W		30.0%				3/31/2022	3/23/2022	4/1/2022	FedEx	
34490	3/24/2022	City of Santa Ana	Local Street Preventative Maintenance FY 21-22	2,189,000.00	5600	400	Day	60 Working Days	Jim	Rick	Gio	0.0%				4/8/2022	4/8/2022	4/12/2022		
34489	3/30/2022	RV Concrete	Route 57, 12-0S8804	1,285,956.00	8310	0	Night	90 Working Days	Jim	Art		0.0%				5/26/2022	5/26/2022	5/27/2022		
34736	3/30/2022		Crenshaw Blvd Rehabilitation	4,253,680.00	14700	850	Day	130 Working Days	Gordon	John M	Deonne	0.0%	2,374 CY	934 CY	14,700 TN	5/31/2022		6/10/2022	11	
34427	4/1/2022		Dist. 6 - 11th Street B/T M.L.K. Jr. Ave. & Orange - Pete		1513		Day		Jerry	Jorge		0.0%								_
34428	4/1/2022		Dist. 2 - S/S 11th Street B/T Orange Ave. & Gardenia A		698		Duy		Jerry	Jorge		0.0%			_					
34430	4/1/2022		Long Beach Blvd. B/T Voctoria Street & Neece Street R		2100		Day		Jeny	Jorge		0.0%								
34479	4/4/2022		Wilson Street Improvement Project No. 22-01	1,061,160.00	2660	250	Day	50 Working Days	Kim	Doug	Deonne	0.0%				6/2/2022	4/14/2022			
34582	4/4/2022		2021-2022 Annual Slurry Seal Project		305	0	Day	30 Working Days	Brian	Rick	Gio	1.0%				4/27/2022	4/27/2022	5/6/2022		
				6,810,043.00					-									5/10/2022		
34552	4/5/2022	Caltrans	Route 15, 215; 08-1M0504	· · · · · · · · · · · · · · · · · · ·	40000	0	Night	60 Working Days	Jim			0.0%				5/4/2022	5/4/2022			
34617	4/7/2022	Moote Companies	Palomino Ranch 1st and 2nd Street	2,213,213.00	7500	800	7500	80 Working Days	Miguel	John W		0.0%				5/2/2022	5/2/2022	5/26/2022	FedEx	
34461	4/8/2022	City of Long Beach	New York Street between Atlantic Avenue & Lewis Aver	44,218.59	2		Day		Јепту	Jorge	Deonne	0.0%								_
				31,552.95																
34462	4/8/2022		Termino Avenue between 3rd Street and 4th Street R-7		2		Day		Jerry	Jorge	Deonne	0.0%							+	
34463	4/8/2022		Ximeno Avenue between 4th Street and 10th Street R-7		47		Day		Jerry	Jorge	Deonne	0.0%								_
34464	4/8/2022	and a mong a contra	Bellflower boulevard between Garford Street and Stearr		2637		Day		Jerry	Jorge	Deonne	0.0%								
34657	4/8/2022	Orbis Real Estates/Toscana Square	Riverside Dr. and Milliken Ave. Street Improvement		4000	2200	Day	45 Working Days	Miguel	Jim		0.0%				6/15/2022	4/18/2022	6/15/2022	DocuSign	
	4/14/2022	County of Orange	JOC for Pavement Maintenance FY 2022-23	5,000,000.00					Gordon	Rick	Gio	0.0%								
34495	4/19/2022	City of Rancho Santa Margarita	Arroyo Vista Rehab	466,705.00	1000	0	Day	45 Working Days	Jim	Rick	Gio	0.0%				4/19/2022	4/19/2022	4/25/2022		
34528	4/19/2022		FY 21/22 Citywdie Street Resurfacing		7000	100	Day	60 Working Days	Jim	Rick	Gio	0.0%				5/3/2022	5/3/2022	5/9/2022		
	4/19/2022		Craimer Ln Project		750	0	Day	5 Working Days	Augustine	Doug	Deonne	0.0%								_
34483	4/20/2022		Asplundh Construction - Balboa Blvd. Median IsaInd				Day		Kim	Jorge	Deonne	99.0%						1000 0000 000 000		-
34484 34485	4/20/2022		WD08-22 Zone 1 (Red) N to 405 W to Lakewood \$				Day		Kim	Jorge	Deonne	17.0%								-
34485 34486	4/20/2022 4/20/2022		WD08-22 Zone 2 (Green) 405 to PCH, W to Redondo			+	Day		Kim	Jorge	Deonne	9.0%								
34466	4/20/2022		WD08-22 Zone 3 (Yellow) PCH to Water, W to Redondu 3 WD08-22 Zone 4 (Blue) PCH/7th to Water, Redondo to 3				Day Day		Kim Kim	Jorge Jorge	Deonne Deonne	46.0% 13.0%							1	
34488	4/20/2022		WD08-22 Zone 5 (Orange) Del Amo to 7th/PCH, Redon \$				Day		Kim	Jorge	Deonne	45.0%								
34508	4/21/2022		Mission Blvd. Pavement Rehab Project 21103 Ph.2		12550	0	Day	40 Working Days	Maurice	TBD	Gio	0.0%				5/20/2022	520/2022	5/25/2022		
34516	4/21/2022		Street Rehabilitation Program Project 21-9271		15470	1180	day	60 Working Days	Maurice	TBD	Deonne	0.0%				5/24/2022		6/9/2022	FedEx	
34524	4/21/2022		SR - 210 S		100		Day & Nite		Gordon	Art		75.0%	0 CY	0 CY	111 TN					
34635	4/27/2022	KB Homes	Falloncrest Offsite Street Improvement CFD	1,376,376.00	500	800	Day	40 Working Days	Miguel	Jim		0.0%				5/31/2022	5/31/2022	6/9/2022	Emailed	_
34669	4/28/2022	City of Lake Elsinore	Downtown Pavement Rehabilitation	1,946,431.45	8500	560	Day	75 Working Days	Gordon	John W	Gio	0.0%	0 CY	915 CY	5,000 TN	6/14/2022	5/26/2022	6/14/2022		
34503	- 5/1/2022		Anaheim Street between Oregon Avenue & Pacific Avel		4180		Day		Jerry	Jone	Deonne	0.0%								
34504	5/1/2022		E. Anaheim Street Atlantic Avenue and Alamitos Avenu		2700		Day		Jerry	Jorge	Deonne	0.0%								
34505	5/1/2022		Loynes Drive between Bellflower Street & Pacific Coast		682		Day		Jerry	Jorge	Deonne	0.0%								
34509	5/1/2022		4th Street between Eim Avenue & Almitos Avenue R-7131A \$		2275		Day		Jerry	Jorge	Deonne	0.0%								
34510	5/1/2022		E. San Antonio Drive b/t Long Beach Blvd. & Atlantic Ave. R-1 \$	529,913.09	1725		Day		Jerry	Jorge	Deonne	0.0%								
34741	- 5/5/2022		FY 21-22 Street & Alley Improvements	5,353,000.00	15946	1287	Day	80 Working Days	Gordon	Jorge	Deonne	0.0%	0 CY	1,356 CY	15,000 TN	6/23/2022	-	6/30/2022		
34547	5/11/2022		Automated People Movers (APM) Various Locations		38,427		Day/Night		Bob	Doug	N/a	2.0%							-	
34565	5/11/2022		FY 21-22 Antonio Pkwy & Alas Drive Paz Overlay		2513	25	Day	25 Working Days	Jim	TBD		0.0%				5/11/2022		5/16/2022		
34600	5/11/2022		FY 22-23 Slurry Seal & Rehabilitation Project		0	0	Day	00 M/ad/ D	Brian	Darren		1.0%				5/12/2022	5/12/2022	5/18/2022		
34621 34623	5/11/2022		San Gabriel River Bikeway	985,312.00	3000	200	Day	90 Working Days	Jim	Jim	Cia	0.0%				5/19/2022	5/19/2022	5/24/2022	FedF	
	5/11/2022	City of Ontario	2022 Pavement Rehabilitation Project	3,959,699.25	20765	275	Day	120 Working Das	Maurice	TBD	Gio	0.0%				5/12/2022	5/12/2022	5/19/2022	FedEx	

ob No.#	Date	Agency / Owner	Project Title	Bid Amount	AC Tonnage	Concrete	e Dav/Night	Contract Time	P.M.	Supt	Coor	Completed	Dirt Removal	Concrete Removal	Grindinas	Cont. Rec.	Date of Letter	Sent Back	Via	
34571	5/13/2022	City of Moreno Valley	Citywide Pavement Rehabilitation Program FY 2021-22 \$	18,746,665.00	71,000	2,100		150 Working Days	Edward	John W	Gio	0.0%	1,000 CY	1,950 CY		6/27/2022	6/27/2022	7/1/2022	Viu	1
34632	5/17/2022		Neighbrhood Slurry Seal Area 3	799,151.00	938	23	Day	45 Working Days	Brian	Rick	Gio	0.0%	1,000 01	23 CY	00,000 114	6/24/2022	6/24/2022	6/27/2022	-	
34618	5/18/2022		Residential Slurry Seal & Miscellaneous Rehabilitation F \$	704.080.00	138	282	Day	40 Working Days	Brian	TBD	0,0	0.0%		20 01		GENEOLE	OIL WEGEL	0/LINEOEL		-
34576	5/19/2022	City of Pomona	Mission Blvd, Buena Vista Ave & Philadelphia Street Re \$	4,119,411.00	14,400	523		60 Working Days	Edward	Jim		0.0%	260 CY	516 CY	13.000 TN	6/7/2022	6/7/2022	6/20/2022		-
34666	5/23/2022	City of Torrance	Emergency Repair-Crenshaw BI & Carson St. \$	145,840,00	350	0	Night	10 Working Days	Gordon	John M	Deonne	0.0%	0 CY	0 CY	0 TN					-
34799	5/25/2022	City of Compton	Annual Residential Street Rehabilitation-Phase 28 \$	6.219.065.00	22050	1012	Day	180 Working Days	Gordon	John M	Deonne	0.0%	5.175 CY	1,150 CY	21,180 TN	6/17/2022		7/5/2022		+
34619	5/26/2022		Spring Street and El Camino Real ADA Improvements F \$	270,925.00	231	33	Day	30 Calendar Days	Kim	Rick	Gio	0.0%				5/31/2022	5/21/2022	6/6/2022		
34624	5/26/2022		2022 Arterial Rehabilitation \$	5,945,346,20	16730	1856	Day	160 Working Days	Jim	Doug	Deonne	0.0%				6/14/2022	6/14/2022	6/16/2022		-
34637	5/31/2022	Duke Realty	Oleandor & Slover Fontana \$	256.081.50	500	100	Day	40 Working Days	Miguel	Jim	Gio	0.0%				5/31/2022	5/31/2022	6/1/2022	Duke Portal	-
34616	6/1/2022		2021-22 Street Rehabilitation at Various Locations \$	7,294,219.00	44368	650	Day	80 Working Days	Maurice	TBD	Deonne	0.0%				6/20/2022	6/16/2022			1
34704	6/1/2022		Route 710 07-0W0704 \$	4,338,152,00	15200	0	Night	100 Working Days	Jim	TBD		0.0%				7/11/2022	7/11/2022	7/14/2022		
34636	6/9/2022		Parking Lot improvement at Various Locations \$	1,672,149,00	5,780	501		90 Calander Days	Edward	Jim	Gio	0.0%	60 CY	494 CY	3.100 TN					-
34724	6/9/2022	City of Anaheim	Weir Canyon Road Rehabilitation from South City \$	2,305,993.90	9233				Maurice	TBD		0.0%		/		7/20/2022	7/18/2022	7/27/2022		-
34648	6/16/2022	March1 LLC	MarchLife Street Rehabilitation \$	1,062,591.65	4800	150	Day	40 Working Days	Miguel	John W	Gio	0.0%				7/21/2022	7/21/2022	7/21/2022	Hand Deliver	-
34670	6/20/2022		Pacific Drive Elementry Coldplane \$	26,605,00	0	0	Day	1 Working Day	Augustine	Randy		0.0%								
34677	6/20/2022		OC Church Lot Coldplane \$	20,834.00	0	0	Day	1 Working Day	Augustine			0.0%								
34676	6/24/2022		Pride Flag Crosswalk / Superior Pavement Markings \$	130,620,11			Day		Kim	Jorge		99.0%								
34686	6/28/2022	City of Mission Viejo	Asphalt Repairs and Asphalt Overlay Project \$	2,542,229.00	14100	0	Day	45 Working Days	Maurice	Rick	Gio	0.0%				7/27/2022	7/27/2022	8/8/2022		
	6/29/2022	Green Giant Landscape	Little Lake Park Parking Lot Rehab-Santa Fe Springs \$	211,546.00	1968	0	Day	4 Working Days	Augustine	TBD		0.0%						a		
34689	6/30/2022	County of San Bernardino	Chino & Montclair Area Various Roads Overlay Project \$	5,639,575.88	19,650	0	Day	100 Working Days	Edward	Jim		0.0%	0 CY	0 CY	20,000 TN					
34702	6/30/2022	City of Temecula	Pavement Rehabiliation Program - Meadow View/ Palor \$	4,302,151.55	10000	320	Day	85 Working Days	Brian	John W.	Gio	0.0%				7/11/2022	7/11/2022	7/14/2022		
34733	7/7/2022		2022 Arterial Roadway Project \$	5,449,254.20	30210	620	Day	90 Working Days	Maurice	TBD	TBD	0.0%				7/12/2022	7/7/2022	7/18/2022	FedEx	
34729	7/12/2022		Pavement Rehabilitation Program Citywide \$	3,629,219.00	18278	590	Day/ Nigh	60 Working Days	Maurice	John W.	TBD	0.0%								
	7/14/2022		Terracina Tract 36557 Lakeshore Drive, Dryden Street : \$	3,060,060.00	11000	1200	Day	60 Working Days	Miguel	John W		0.0%								
34800	7/19/2022	Riverside Construction	Ontario Ranch Road Bridge \$	403,721.85	3540	0	Day		Gordon	Art		0.0%	0 CY	0 CY	280 TN	7/26/2022		8/3/2022	FedEx	
	7/20/2022	City of Murrieta	Murrieta Hot Springs Road \$	3,947,675.50	16000	270	Day/Night	75 Working Days	Jim	John W	Gío	0.0%								
4742	7/27/2022	City of Norco	Shadow Canyon Sunset Ct & Portions of Broken Feathe \$	624,145.00	2,390	48	B Day	35 Working Days	Edward	Jim H.		0.0%	830 CY	48 CY	1,735 TN					
34882	7/28/2022	KB Homes	Tract 20157 Street, Siging & Striping Light Improvemen \$	1,069,069.00	3000	600	Day	36 Working Days	Miguel	Jim H.		0.0%	0 CY	0 CY	0 TN	9/26/2022				
	7/28/2022	EBS INC	Northeast Anaheim Colony (sabina) Neighborhood Improver. \$	1,146,000.00	8000	0	Day		Maurice	Art		0.0%								
	8/9/2022	California Professional Engineering	Citrus Ave at Chase Road Traffic Signal Project \$	223,258.00	627	50	Day		Maurice	John M	Deonne	0.0%								
	8/18/2022	County of Ventura	6030 JOC Paving \$	2,000,000.00			Day		Kim	TBD		0.0%				9/26/2022	8/18/2022			
	9/1/2022	City of Moreno Valley	Bond Job - Citywide Pavement Rehab - FY 20/21 \$	4,056,002.75	17717	35	Day	110 Working Days	Gordon	John W.	Gio	0.0%	2,955 CY	40 CY	10,165 TN	9/6/2022		9/9/2022	FedEx	
	9/1/2022	Skanska	Moreno Beach Drive - Moreno Valley \$	2,806,365.95	23838	0	Day/Night	345 Working Days	Gordon	Art		0.0%	0 CY	0 CY	0 TN					
34823	9/1/2022	City of Long Beach	Wardlow Road between Studebaker Road & Stevely Av \$	787,126.05	160		Day		Jerry	Jorge O.	Deonne	0.0%								1
34824	9/1/2022	City of Long Beach	Temple Avenue between 4th Street & 7th Street R-7131 \$	549,140.98	820		Day		Jerry	Jorge O.	Deonne	0.0%								1
34825	9/1/2022	City of Long Beach	E. 4th Street b/t Cerritos Ave. & Almond Ave. R-7131B \$	631,299.96	817		Day		Jerry	Jorge O.	Deonne	0.0%								-
34826	9/1/2022	City of Long Beach	Dist. 3 Appian Way b/t Sorrento Dr. & 2nd St. R-7153 \$	291,281.27	1180		Day		Jerry	Jorge O.	Deonne	0.0%							_	-
34827 34828	9/1/2022 9/1/2022		Dist. 4 Kilroy Airport Way b/t Redondo Ave. & Spring St \$	751,689.42	4779 3470		Day		Јепу	Jorge O.	Deonne	0.0%								+
4828	9/1/2022	City of Long Beach City of Long Beach	Dist. 9 South Street between De Forest Avenue & Jaym Dist. 4 Studebaker E. Service Road b/t Pavo Ave. & Wa	1,725,162,09	3470		Day Day		Jerry Jerry	Jorge O. Jorge O.	Deonne Deonne	0.0%	-							+-
14023	9/8/2022		2019-20 SB1 Maint & Traffic Improvements Phase 2 - E \$	4,311,788,00	12865	350	Day	150 Working Days	Jim	John W.	Deotinte	0.076								+
	9/12/2022	Prologis	Phase A Street Traffic Signal, Street Light & Fiber Optic \$	22,378,378,00	37000	8000	Day	230 Working Days	Miguel	Jim /John		0.0%	96,000 CY	0 CY	10,000 TN					+
34497	7/23/2022	City of Huntington Beach	HB Police Helipad	393,120.00	1120	230	Day	30 Working Days	Jim	Jorge		0.0%	30,000 01	001	10,000 TN				-	+
	9/15/2022		Pavemenmt Rehab FY 26/27 and 30/31 - Local Streets \$	11.097.080.00	40705	5	Day	150 Working Days	Gordon	John W.		0.0%	0 CY	5 CY	10.730 TN					+
	9/20/2022		E. Riverside Drive & Hamner Avenue Street Improveme \$	13,756,756.00	15000	4300	Day	130 Working Days	Miguel	Jim H.		0.0%	11,000 CY	0 CY						+
	9/27/2022	NASCAR	New Valley Construction- 2023 NASCAR Coliseum Paving pro \$	633,145.00	2760	4300	Day	woning Days	Maurice	Art		0.0%	11,000.01	001	7,000 11					-
	VIZIIZUZZ		Wew vulley construction- 2023 WASCAR Consenti Paving pro	033,143.00	2700	U	Day		Maurice	All		0.076								-
																				+
-																				Ŧ
			Month Total \$	61,353,188.36	\$ 147,902.00															+
			Apparent Low Total \$	126,107,057.68	\$ 395,215.00															ŧ
				398,005,954,44			-		-											

-4



C. LIST OF COMPLETED PROJECTS - LAST THREE YEARS

[**Duplicate Page if needed for listing additional completed projects.**]

Please include only those projects which are similar enough to demonstrate Bidder's ability to perform the required Work.

Project Client	Description of	Period of	Cost of Bidder's	Contact Name
	Bidder's Work	Performance	Work	& Phone
		ee Attach	ed"	

Colony Commerce C/O Caprock Partners 1300 Dove Street Suite 200 Newport Beach, CA 92660 Contact: Eric Nutter (949) 428-1400 Ext. 209 enutter@moote.com Archibald St. Improvements Contract Amount: \$1,949,000.00 Start: 12/2019 Completed: 12/2021

Lennar Homes 25 Enterprise #300 Aliso Viejo, CA 92656 Contact: Diane Hannon (949)349-8000 Diane.hannon@lennar.com

City of Norco 2870 Clark Ave. Norco, AC 92860 Contact: Todd Shank (951) 270-5603 Todd.shank@norco.ca.us

Los Angeles Department of Water and Power 111 North Hope Street, L-43 Los Angeles, Ca 90012 Contact: Joelle Morisseau (213) 367-0123 Joelle.morisseau@LADWP.com

City of Dana Point 33282 Golden Lantern Dana Point, CA 92629 Contact: Scott Fisher (949) 248-3577 <u>sfisher@DanaPoint.org</u>

City of Corona 400 South Vicentia Corona, CA 92852 Contact: Barry Ghaemi (951) 736-2400 bghaemi@Coronaca.gov. Merrill & Haven Street Improvement Contract Amount: \$1,481,832.15 Start: 6/2020 Completed: 12/2021

Wayne Makin Park Slurry Seal Project Contract Amount: \$52,725.89 Start: 10/2021 Completed: 12/2021

Pine Tree Power Plant Access Road Repair Improvements Contract Amount: \$810,400.00 Start: 5/2021 Completed: 7/2021

Slurry Seal Project 19/20 Contract Amount: \$1,897,897.00 Start: 04/2020 Completed: 05/2021

Street Pavement Maintenance & Rehabilitation Project No. 2020.01 Contract Amount: \$3,471,178.00 Start: 6/2021 Completed: 1/2022

City of Anaheim 200 S. Anaheim Boulevard Anaheim, CA 92805 Contact: Jose Cortez (714) 765-5039 jcortez@anaheim.net

.

4

County of Orange 601 North Ross Street Santa Ana, CA 92701 Contact: Stephen Clayton (714) 995-0206 <u>Stephen.clayton@ocpw.ocgov.com</u>

City of Norwalk 12700 Norwalk Blvd. Norwalk, CA 90650 Glen W. C. Kau (562) 929-5723 <u>gkau@norwalkca.gov</u>

City of Garden Grove 11222 Acacia Pkwy Garden Grove, CA 92840 Navin Maru (714) 741-5180 nmaru@ggcity.org State College Boulevard Improvement from Ball Road to SR 91 Freeway Contract Amount: \$484,848.00 Start: 8/2021 Complete: 4/2022

Rossmoor Collectors Grind & Overlay Contract Amount: \$ 2,148,320.90 Start: 4/2021 Complete: 12/2021

Local Streets Rehabilitation Zone 27 East of Gard – No. 7925.3 Contract Amount: \$1,051,330.00 Start: 6/2021 Completed: 12/2021

Arterial STS. Rehabilitation Contract Amount: \$3,185,281.00 Start: 6/2022 Complete: 12/2021

City of Victorville 14343 Civic Drive Victorville CA. 92393 Contact: Bruce Miller 760-955-5085 bmiller@victorvilleca.gov Third Avenue Road improvements Contract Amount: \$1,790,000.00 Start Date: 5/2020 End Date: 10/2020

Orange County Cemetery District 25751 Trabuco Rd. Lake Forest CA. 92630 Contact: Jim Mickartz 949-450-1088 <u>mickartzarch@gmail.com</u>

City of Alhambra 111 S. 1st Street Alhambra, CA. 91801 Contact: Robert Bias 626-580-5000 rbias@cityofalhambra.org

City of Ontario 303 E. B Street Ontario, CA. 91764 Contact: Ariana Kern 909-395-2129 akern@ontarioca.gov

City of Loma Linda 25541 Barton Road Loma Linda, CA. 92354 Contact: T. Jarb Thaipejr 909-799-4400 jthaipejar@lomalinda-ca.gov

City of Jurupa Valley 8920 Limonite Avenue Jurupa Valley, CA. 92509 Contact: Chase Keys 951-332-6464 <u>ckeys@jurupavalley.org</u> El Toro Memorial Park Curb & Dr. Project Contract Amount: \$416,999.99 Start Date: 08/2020 End Date: 11/2020

2020 HUD Street Improvements Project Contract Amount: \$300,433.00 Start Date: 06/2020 End Date: 10/2020

2020 Fall Pavement Rehabilitation Project Contract Amount: \$2,499,333.00 Start Date: 07/2020 End Date: 12/2020

Pavement Rehabilitation –Barton Road Contract Amount: \$768,677.00 Start Date: 04/2020 End Date: 12/2020

Granite Hill Drive Pavement Rehabilitation Contract Amount: \$999,777.00 Start Date: 04/2020 End Date: 10/2020

City of Camarillo 601 Carmen Drive Camarillo, CA 93010 Contact: Thang Tran (805) 388-5345 ttran@cityofcamarillo.org

County of Ventura 800 S. Victoria Avenue, #1600 Ventura, CA 93009 Contact: Matt Maechler (805) 477-1911 matthew.maechler@ventura.org

City of Westminster 8200 Westminster Boulevard Westminster, CA 92683 Contact: Theresa Tran (714) 548-3460 ttran@westminster.ca.gov

City of Newport Beach 100 Civic Center Drive Newport Beach, CA 92660 Contact: Patricia Kharazmi (949) 644-3344 <u>pkharazmi@newportbeachca.gov</u>

City of Huntington Beach 2000 Main Street Huntington Beach, CA 92648 Contact: Joe Fuentes (714) 536-5259 ifuentes@surfcity-hb.org

County of Orange 601 N. Ross Street, 4th Floor Santa Ana, CA 92701 Contact: Albert Rodriguez albert.rodriguez@ocpw.ocgov.com Earl Joseph Drive Paving Contract Amount: \$681,901.50 Start Date: 06/2020 End Date: 07/2020

Yerba Buena Rd. (South) Pavement Resurfacing Contract Amount: \$2,298,467.40 Start Date: 03/2020 End Date: 06/2020

Citywide Overlay Street Improvements Contract Amount: \$1,131,621 Start Date: 02/2020 End Date: 06/2020

Cameo Highlands Street Reconstruction Contract Amount: \$2,425,694.00 Start Date: 07/2020 End Time: 11/2020

Arterial Rehabilitation of Graham St, Slater Ave, Newland St and Atlanta Ave Contract Amount: \$5,181,955.00 Start Date: 05/2020 End Date: 11/2020

JOC Pavement Maintenance Contract Amount: \$2,584,747.69 Start Date: 07/2020 End Date: 08/2020

City of Orange 300 E. Chapman Avenue Orange, CA 92886 Contact: Martin Varona (714) 744-5563 <u>mvarona@cityoforange.org</u> Annual Slurry Seal FY 19-20 Contract Amount: \$377,737.78 Start Date: 06/2020 End Date: 12/2020

City of Norco 2870 Clark Avenue Norco, CA 92860 Contact: Sam Nelson (951) 270-5607 <u>snelson@ci.norco.ca.us</u> FY 2019-2020 Slurry Seal Project Contract Amount: \$147,708.97 Start Date: 06/2020 End Date: 12/2020

City of Compton 205 S. Willowbrook Avenue Compton, CA 90220 Contact: Brittany Duhn (Z & K Consultants) bduhn@zandkconsultants.com Annual Residential Street Rehab – Phase 1 Contract Amount: \$5,295,068.00 Start Date: 05/2020 End Date: 11/2020

City of Simi Valley 2929 Tapo Canyon Rd. Simi Valley, CA 93063 Contact: Sarah Sheshebor (805)583-6792 <u>sshesheb@simivalley.org</u> Simi Valley Minor Street Rehabilitation Contract Amount: \$510,124.25 Start Date: 07/2019 End Date: 08/2019

County of Ventura 501 Poli Street Ventura, CA 93001 Contact: Christopher Solis (805) 654-2054 chris.solis@ventura.org Yerba Buena Area Resurfacing Project Contract Amount: \$3,919,808.95 Start Date: 06/2019 End Date: 12/2019

City of Stanton 7800 Katella Avenue Stanton, CA. 90680 Contact: Guillermo Perez (714) 890-4204 gperez@ci.stanton.ca.us

City of Compton 205 S. Willowbrook Avenue Compton, CA. 90220 Contact: John Strictland (310) 605-5505 jstrictland@comptoncity.org

City of San Clemente 910 Calle Negocio San Clemente, CA. 92673 Contact: Darra Koger (949) 361-3138 kogerD@san-clemente.org

City of South Gate 8650 California Avenue South Gate, CA. 90280 Contact: John Rico (323) 563-9594 jrico@sogate.org 2019 Citywide Street Resurfacing Contract Amount: \$1,206,869.00 Start Date: 10/2019 End Date: 12/2019

Road Repair Service (Pothole Repair) Contract Amount: \$1,019,100.00 Start Date: 08/2019 End Date: 11/2019

Street Rehabilitation for S. Avenue LA Esperanza Contract Amount: \$384,055.00 Start Date: 09/2019 End Date: 10/2019

Circle Park Driveway Project Contract Amount: \$268,576.00 Start Date: 06/2019 End Date: 09/2019

Pardee Homes 1250 Corona Pointe Court, Ste. 600 Corona, CA. 92879 Contact: Nick Lasher (951) 428-4442 nick.lasher@pardeehomes.com

City of Fontana 8353 Sierra Avenue Fontana, CA. 92335 Contact: Kimberly Young (909) 350-7632 kyoung@fontana.org Railroad Canyon Widening Contract Amount: \$5,062,746.00 Start Date: 11/2018 End Time: 08/2019

Citrus Avenue Improvements Contract Amount: \$502,730.00 Start Date: 08/2018 End Date: 10/2019

DR Horton 2280 Wardlow Circle Ste. 100 Corona, CA. 92880 Contact: Keith Alex (951) 830-5872 kalex@drhorton.com

City of Ontario 2201 Dupont Dr. #300 Irvine, CA. 92612 Contact: Kavous Emami (909) 628-6234 Singlton Road Contract Amount: \$1,684,000.00 Start Date: 07/2018 End Date: 12/2019

Eucalyptus Street Improvements Contract Amount: \$1,580,580.00 Start Date: 3/2018 End Date: 10/2019

Irvine Community Development Company 550 Newport Center Dr. Ste. 550 B2 Newport Beach, CA. 92660 Contact: Mike Morse (949) 720-2560

City of Downey 11111 Brookshire Avenue Downey, CA. 90241 Contact: Desi Gutierrez, (562) 904-7110 dgutierr@downeyca.org Portola Springs PA-6 Enclave 5B Phase1, 2 Contract Amount: \$2,055,055.00 Start Date: 09/2018 End Date: 12/2019

FY 18/19 Slurry Seal Project Contract Amount: \$313,425.87 Start Date: 06/2019 End Date: 12/2019

City of Chino PO Box 667 Chino, CA. 91708 Contact: Dustin Postovoit (909) 334-3415 apostovoit@cityofchino.org

City of Lancaster 44933 Fern Avenue Lancaster, CA. 93534 Contact: Greg Wilson (661) 570-8003 gwilson@cityoflancasterca.org Slurry Seal Maintenance Work Contract Amount: \$372,805.00 Start Date: 1/2019 End Date: 12/2019

2018 Pavement Management Program Contract Amount: \$2,720,103.65 Start Date: 3/2019 End Date: 12/2019

City of Colton 650 N. La Cadena Dr. Colton, CA. 92324 Contact: Victor Ortiz (909) 370-5099 <u>vortiz@coltonca.gov</u>

City of Cathedral City 68700 Ave Lalo Guerrero Cathedral City, CA. 92234 Contact: John A. Corella (760) 770-0349 jcorella@cathedralcity.gov

City of San Clemente 910 Calle Negocio San Clemente, CA. 92673 Contact: Gary Voborsky (949) 361-6132 voborskyg@san-clemente.org FY 18-19 Asphalt Paving Project Contract Amount: \$1,377,700.00 Start Date: 3/2019 End Date: 11/2019

Ortega Road Widening Contract Amount: \$459,998.00 Start Date: 2/2019 End Date: 12/2019

Arterial Street Pavement Maintenance Contract Amount: \$1,187,187.00 Start Date: 3/2019 End Date: 7/2019



D. EXPERIENCE AND TECHNICAL QUALIFICATIONS QUESTIONNAIRE

Personnel:

The Bidder shall identify the key personnel to be assigned to this project in a management, construction supervision or engineering capacity.

1. List each person's job title, name and percent of time to be allocated to this project:

Gordon Kline, Project Manager - 10%	
Jim Harnetiaux - Superintendent - 50%	
Art Ramirez - Paving Foreman - 100%	_

2. Summarize each person's specialized education:

Agtec Pointman Training Asphalt Techology

3. List each person's years of construction experience relevant to the project:

14 years 38 years 36 years

4. Summarize such experience:

Construction Background in Various Public & Private Works Projects.

Bidder agrees that personnel named in this Bid will remain on this Project until completion of all relevant Work, unless substituted by personnel of equivalent experience and qualifications approved in advance by the City.

INFORMATION REQUIRED OF BIDDERS

Gordon Kline (951)453-4635

+ +

Work History	 Responsible for org Responsible for pro 	oncrete and slurry operation		Corona, CA y projects.
	2013-2014 Project Manager	Riverside Const	ruction Riv	verside, CA
	 Handled all aspects 	of current jobs		
	 Maintain relationshi 	ips with employees on all	levels	
	2011-2013 PM/Superintendent	All American Asphal		ona, CA
			by All American Asphalt	
	 Managed multiple c 	ontracts from start to con	pletion	
	2008-2011 Owner/Estimator •Estimated potential	ICE Engineering	Rowland Hei	ghts, CA
	Maintain any and all	-		
Education	1992-1996 • High School Diplo		Arlington High School, Riv	verside, CA
Additional Information	•Attended various ed	ucational classes relating	to the construction industry	
	 Works closely with a possible 	all employees to ensure th	e most productive and safe	work environment

James Harnetiaux

Work History

2005-Present Area Superintendent

All American Asphalt

Corona, CA

- •Responsible for all aspects of Construction activity (grading, concrete and paving) in area of Southern CA assigned. This includes:
- -Scheduling of all Construction Activity
- -Responsible for achieving production goals
- -Product Quality

....

- -Ordering of manpower, equipment and materials
- -Safety of company personnel
- -Communication with customers and agencies

1993-2005	All American Asphalt	Corona, CA
Concrete Superint	endent	,
•Responsible for a	l aspects of concrete construction for th	e company. This included:
-Scheduling of con-	rete group throughout Southarn Califa.	

- -Scheduling of concrete crews throughout Southern California
- -Implementation of new areas of work such as Rapid Set concrete construction on numerous Caltrans projects in Southern California
- -Quality control of the concrete work for the company

-Crew Safety

-Responsible for achieving production goals for the Concrete Division

1984-1993 All American Asphalt Corona, CA

Concrete Foreman

•Responsible for the production of a 14-man concrete crew. This included:

- -Reading of plans and specs for correct and accurate placement of the product
- -Scheduling of material and manpower for the operation of curb machine and hand placement of product
- -Quality
- -Safety

Education

1971-1975

High School Diploma

Mater Dei High School, Santa Ana, CA

P.O. Box 2229, Corona, CA 92878-2229

All American Asphalt

Art Ramirez

Work History	ork Hist	VIO
--------------	----------	-----

1988-Present

Corona, CA

California

Paving Superintendent

- Managed daily operations for paving.
- Responsible for proper placement of asphalt materials.

1980--1988

Operating Engineer

 Responsible for daily maintenance and operation of various heavy machinery, including paving machines.

1978-1980	Guy F. Atkinson
	Ouy P. Atkinson

Operating Engineer

 Responsible for daily maintenance and operation of various heavy machinery, including paving machines.

1976-1978 R.J. Noble Orange, CA

Operating Engineer

 Responsible for daily maintenance and operation of various heavy machinery, including paving machines. City of Beaumont Request for bid



Additional Bidder's Statements:

If the Bidder feels that there is additional information which has not been included in the questionnaire above, and which would contribute to the qualification review, it may add that information in a statement here or on an attached sheet, appropriately marked:

N/A	

E. VERIFICATION AND EXECUTION

These Bid Forms shall be executed only by a duly authorized official of the Bidder: I declare under penalty of perjury under the laws of the State of California that the foregoing information is true and correct:

Name of Bidder	All American Asphalt	
Signature	< cl	
Name and Title	Michael Farkas, Secretary	<u>.</u>
Dated	9-30-2022	

City of Beaumont Request for bid



Pennsylvania Avenue Widening CIP 2017-009

NON-COLLUSION AFFIDAVIT CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

Michael Farkas _____, being first duly sworn, deposes and says that he is of All American Asphalt the party making the attached bid; that the bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation; that the bid is genuine and not collusive or sham; that the bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that the bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract of anyone interested in the proposed contract; that all statements contained in the bid are true; and, further, that the bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid, and will not pay, any fee to any corporation, partnership, company association, organization, bid depository, or to any member or agent thereof to effectuate a collusive or sham bid.

I certify (or declare) under penalty of perjury under the laws of the State of California that the foregoing is true and correct.

Name of Bidder	All American Asphalt	
Signature		_
Name and Title	Michael Farkas, Secretary	_
Dated	9-30-2022	

CALIFORNIA JURAT

e

GOV CODE § 8202

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California

County of <u>Riverside</u> B. ROYSTER Notary Public - California	Subscribed and sworn to (or affirmed) before me on this <u>30th</u> day of <u>September</u> 2022, <u>Date</u> <u>Month</u> By (1) <u>Michael Farkas</u> Name of Signer Proved to me on the basis of satisfactory evidence be the person who appeared before me (.) (,)			
Riverside County Commission # 2260352 My Comm. Expires Oct 26, 2022	(and			
	(2)Name of Signer			
	Proved to me on the basis of satisfactory evidence be the person who appeared before me.)			
Signa	ture blanter			
Place Notary Seal Above	Signature of Notary Public			
Though the information below is not required by law, it may prove valuable to person relying on the document and could prevent fraudulent removal and reattachment of this form to another document.				
Further Description of Any Attached Document				
	RIGHT THUMBPRINT RIGHT THUMBPRINT OF SIGNER OF SIGNER			
Title or Type of Document <u>Non-Collusion Affidavit</u>	Top of thumb here Top of thumb here			
Document Date: <u>9-30-2022</u> Number of Pages: <u>1</u>	_			
Signer(s) Other Than Named Above: <u>None</u>				

City of Beaumont Request for bid



Pennsylvania Avenue Widening CIP 2017-009

BID BOND

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

The makers of this bond are,

All American Asphalt

as Principal, and

Fidelity and Deposit Company of Maryland

, as Surety

and are held and firmly bound unto the City of Beaumont, hereinafter called the City, in the penal sum of TEN PERCENT (10%) OF THE TOTAL BID PRICE of the Principal submitted to CITY for the work described below, for the payment of which sum in lawful money of the United States, well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH that whereas the Principal has submitted the accompanying bid dated October 3 _____, 2022 __, for

CIP 2017-009 PENNSYLVANIA AVENUE WIDENING

If the Principal does not withdraw its bid within the time specified in the Contract Documents; and if the Principal is awarded the Contract and provides all documents to the City as required by the Contract Documents; then this obligation shall be null and void. Otherwise, this bond will remain in full force and effect.

Surety, for value received, hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the Contract Documents shall in affect its obligation under this bond, and Surety does hereby waive notice of any such changes.

In the event a lawsuit is brought upon this bond by the City and judgment is recovered, the Surety shall pay all litigation expenses incurred by the City in such suit, including reasonable attorneys' fees, court costs, expert witness fees and expenses.

City of Beaumont Request for bid



Pennsylvania Avenue Widening CIP 2017-009

IN WITNESS WHEREOF, the above-bound parties have executed this instrument under their several seals this 22nd day of September , 2022, the name and corporate seal of each corporation.

(Corporate Seal)

(Corporate Seal)

All American Asphalt Principal By MICHHEL FARKAS SECLETARY Title

Title

Fidelity and Deposit Company of Maryland Surety

Rebeccie Brac Patos

Rebecca Haas-Bates

Attorney-in-Fact

(Attach Attorney-in-Fact Certificate)

Title Attorney-in-Fact

CALIFORNIA ALL-PURPOSE ACKNOWLEDGEMENT

CIVIL CODE § 1189

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

State of California		
County of <u>Riverside</u>		
On <u>September 30, 2022</u>	before me,	B. Royster, Notary Public
personally appeared	Mi	chael Farkas
B. ROYSTER Notary Public - California Riverside County Commission # 2260352 My Comm. Expires Oct 26, 2022	person(s) wh and acknow his/ her/their signature(s) of which the I certify unde California tha	to me on the basis of satisfactory evidence to be nose name(s) is/are subscribed to the within instrum ledged to me that he/she/they executed the same authorized capacity(ies), and that by his/her/th on the instrument the person(s), or the entity upon bel person(s) acted, executed the instrument. Fr PENALTY OF PERJURY under the laws of the State at the forgoing paragraph is true and correct.
Though the information below is not re	equired by law, it i	may prove valuable to person relying on the document attachment of this form to another document.
Title or Type of Document	Bid Bond -	- City of Beaumont
Document Date: September 2	2,2022	Number of Pages: 3
Signer(s) Other Than Named Above:	Rebecca H	aas-Bates, Attorney-in-Fact
Attorney in Fact		Signer's Name: Individual Corporate Officer — Title(s): Partner I I Limited I General Attorney in Fact Trustee Other: Signer is Representing:

City of Beaumont Request for bid

٦

,

4



Pennsylvania Avenue Widening CIP 2017-009

STATE OF C	ALIFORNIA)	
) s	S.
CITY OF)	
On this	day of	, in the year 2019, before me,
		, a Notary Public in and for said state, personally
appeared		, known to me to be the person
whose name	is subscribed to	the within instrument as the Attorney-In-Fact of the
(Surety) ackn	lowledged to me	that he subscribed the name of the
	_	(Surety) thereto and his own name as Attorney-In-
Fact.		

Notary Public in and for said State

(SEAL)

Commission expires: _____

NOTE: A copy of the Power-of-Attorney to local representatives of the bonding company must be attached hereto.

CALIFORNIA ALL-PURPOSE ACKNOWLEDGMENT

******	10101010101010101010101010101010101010
A notary public or oth document to which this	er officer completing this certificate verifies only the identity of the individual who signed the s certificate is attached, and not the truthfulness, accuracy, or validity of that document.
State of California)
County of Orange)
On09/22/2022	before me, L. Gomez, Notary Public
Date	Here Insert Name and Title of the Officer
personally appeared	Rebecca Haas-Bates

Name(s) of Signer(s)

who proved to me on the basis of satisfactory evidence to be the person(s) whose name(s) is/are subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their authorized capacity(les), and that by his/her/their signature(s) on the instrument the person(s), or the entity upon behalf of which the person(s) acted, executed the instrument.

I certify under PENALTY OF PERJURY under the laws of the State of California that the foregoing paragraph is true and correct.

WITNESS my hand and official seal.

L. GOMEZ lotary Public - California Orange County Commission # 2413682 Comm. Expires Aug 23, 2026

Departmention of Attacks of Department

Signature R. K

Signature of Notary Public

Place Notary Seal Above

OPTIONAL -

Though this section is optional, completing this information can deter alteration of the document or fraudulent reattachment of this form to an unintended document.

Description of Atta	ached Document				
Title or Type of Do	ocument:	Bid Bond	Doc	ument Date:	09/22/2022
	Three (3) Signer(s)				
Capacity(ies) Clair					
	becca Haas-Bates		Signer's Name	:	
Corporate Office	r – Title(s):		Corporate C	Officer - Title(s)	
Partner – Lim	nited 🛛 General			🗌 Limited 🛛 🗋 G	
Individual	Attorney in Fact		🗆 Individual	🗆 Attorney	in Fact
Trustee	🗌 Guardian or Cons	ervator			n or Conservator
Other:					
Signer Is Representing:		Signer Is Representing:			
Fidelity and Deposit (Company of Maryland	······································	3 - · · · · · · · · · · · · ·		

©2014 National Notary Association · www.NationalNotary.org · 1-800-US NOTARY (1-800-876-6827) Item #5907

EXTRACT FROM BY-LAWS OF THE COMPANIES

"Article V, Section 8, <u>Attorneys-in-Fact</u>. The Chief Executive Officer, the President, or any Executive Vice President or Vice President may, by written instrument under the attested corporate seal, appoint attorneys-in-fact with authority to execute bonds, policies, recognizances, stipulations, undertakings, or other like instruments on behalf of the Company, and may authorize any officer or any such attorney-in-fact to affix the corporate seal thereto; and may with or without cause modify of revoke any such appointment or authority at any time."

CERTIFICATE

I, the undersigned, Secretary of the ZURICH AMERICAN INSURANCE COMPANY, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND, do hereby certify that the foregoing Power of Attorney is still in full force and effect on the date of this certificate; and I do further certify that Article V, Section 8, of the By-Laws of the Companies is still in force.

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the ZURICH AMERICAN INSURANCE COMPANY at a meeting duly called and held on the 15th day of December 1998.

RESOLVED: "That the signature of the President or a Vice President and the attesting signature of a Secretary or an Assistant Secretary and the Seal of the Company may be affixed by facsimile on any Power of Attorney...Any such Power or any certificate thereof bearing such facsimile signature and seal shall be valid and binding on the Company."

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at a meeting duly called and held on the 5th day of May, 1994, and the following resolution of the Board of Directors of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at a meeting duly called and held on the 10th day of May, 1990.

RESOLVED: "That the facsimile or mechanically reproduced seal of the company and facsimile or mechanically reproduced signature of any Vice-President, Secretary, or Assistant Secretary of the Company, whether made heretofore or hereafter, wherever appearing upon a certified copy of any power of attorney issued by the Company, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

IN TESTIMONY WHEREOF, I have hereunto subscribed my name and affixed the corporate seals of the said Companies, this 22nd day of September ______, 2022 .



Sur Hodges

Brian M. Hodges Vice President

By:

TO REPORT A CLAIM WITH REGARD TO A SURETY BOND, PLEASE SUBMIT A COMPLETE DESCRIPTION OF THE CLAIM INCLUDING THE PRINCIPAL ON THE BOND, THE BOND NUMBER, AND YOUR CONTACT INFORMATION TO:

Zurich Surety Claims 1299 Zurich Way Schaumburg, IL 60196-1056 www.reportsfclaims@zurichna.com 800-626-4577



Addendum No. 1 RFB 2017-009 Pennsylvania Avenue Widening Project

This addendum is for the purpose of adding, clarifying, or deleting certain information to the construction contract documents as follows:

Notice Inviting Bids

BID OPENING TIME has been changed from 1:15 pm to 11:15am as shown below. There are no other changes to the bid dates and times.

Bid Published: Bids Must Be Received By: Place Of Bid Receipt:

Questions In By: Bid Opening Date: Bid Opening Location: September 9, 2022 October 3, 2022 @ 11:00 A.M. 550 E. Sixth Street (City Hall) Beaumont, CA 92223 September 21, 2022 @ 11:00 A.M. October 3, 2022 @ 11:15 A.M. 550 E. Sixth Street (City Hall), Room 4 Beaumont, CA 92223

Bid Plans

Construction Note 87 on Sheet 14 in the Bid Plans shall be amended to read, "JACK AND BORE 42-INCH **RCP** CULVERT."

Plan Holders List

The current Access Report from Public Purchase will serve as the plan holders list and is attached to this addendum for the bidder's reference. Additional bidders not shown on this list may still access the bid documents on Public Purchase between now and when the bids are due.

Attachments

The following attachments are made a part of this addendum.

• Plan Holders List



RFB 2017-009 Pennsylvania Avenue Widening Project

SPHAL

Dated: September 28, 2022

By:

Dustin S. Christensen Principal Engineer Public Works

By:

Date Received by Bidder:

9-29-2022

(Bidder's Signature) ARY MIC (Type or Print Name)

(Bidder's Company Name)

Bidder shall include a signed copy of this Addendum No. 1 with the bid proposal.

End of Addendum No. 1

2

Access ReportAgencyCity of EBid Number2017-00Bid TitlePennsyl

City of Beaumont (CA) 2017-009 (re-bid) Pennsylvania Avenue Widening (CIP 2017-009) (re-bid)

Vendor Name	Accessed First Time	Most Recent Access
School Wholesale Supplies LL(2022-09-12 02:49 AM PDT	2022-09-12 02:49 AM PDT
Construction Bidboard, Inc.	2022-09-12 09:11 AM PDT	2022-09-23 11:42 AM PDT
	2022-09-15 07:56 AM PDT	2022-09-27 09:11 AM PDT
	2022-09-10 08:42 AM PDT	2022-09-27 08:42 AM PDT
Crosstown Electrical & Data, In	2022-09-26 07:26 AM PDT	2022-09-27 07:44 AM PDT
	2022-09-12 04:13 AM PDT	2022-09-13 04:33 AM PDT
Beador Construction Company	2022-09-15 07:42 AM PDT	2022-09-23 09:45 AM PDT
CMD	2022-09-15 10:30 AM PDT	2022-09-15 10:30 AM PDT
Paragon Partners Ltd.	2022-09-14 02:36 PM PDT	2022-09-14 02:43 PM PDT
	2022-09-12 01:56 AM PDT	2022-09-12 01:56 AM PDT
	2022-09-14 07:50 PM PDT	2022-09-22 03:14 PM PDT
	2022-09-14 09:02 AM PDT	2022-09-14 09:07 AM PDT
ONYX PAVING COMPANY IN(2022-09-20 10:54 AM PDT	2022-09-20 10:59 AM PDT
BidClerk	2022-09-19 12:43 PM PDT	2022-09-19 12:43 PM PDT
	2022-09-11 05:52 PM PDT	2022-09-11 05:53 PM PDT
Beaumont-Cherry Valley Water		2022-09-19 04:21 PM PDT
Roadway Engineering & Const	2022-09-13 10:13 AM PDT	2022-09-27 04:25 PM PDT
	2022-09-13 12:47 AM PDT	2022-09-22 11:06 PM PDT
•	2022-09-12 07:30 AM PDT	2022-09-21 09:25 AM PDT
AGC Plan Room	2022-09-14 12:59 PM PDT	2022-09-14 01:06 PM PDT
. ,	2022-09-10 03:14 PM PDT	2022-09-27 03:14 PM PDT
	2022-09-11 06:52 AM PDT	2022-09-26 12:52 PM PDT
Hardy and Harper, Inc	2022-09-14 03:02 PM PDT	2022-09-26 07:49 AM PDT
	2022-09-14 03:07 AM PDT	2022-09-14 03:07 AM PDT
	2022-09-12 07:40 AM PDT	2022-09-27 08:20 AM PDT
Calmex Engineering, Inc.	2022-09-19 08:47 AM PDT	2022-09-19 08:47 AM PDT
•	2022-09-15 04:28 PM PDT	2022-09-15 04:29 PM PDT
MSL Electric, Inc	2022-09-15 08:51 AM PDT	2022-09-15 08:54 AM PDT
	2022-09-14 10:41 AM PDT	2022-09-27 04:31 PM PDT
FALCON Engineering Services	2022-09-12 09:12 AM PDT	2022-09-12 09:18 AM PDT
•	2022-09-22 10:58 AM PDT	2022-09-22 10:58 AM PDT
Cal Stripe Inc.	2022-09-16 06:44 AM PDT	2022-09-26 02:22 PM PDT

CITY OF BEAUMONT PUBLIC WORKS AGREEMENT

EXHIBIT "C"

Insurance Certificates and Endorsements

(Insert behind this page.)